



solid-studless

partitions

a

USG® Metal Lath and Plaster

1017

A.I.A. File No. 20-B-11

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|-----------------|------------|------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. | Studless—Metal Lath & Plaster—solid— $\frac{3}{8}$ " riblath—100:2-100:2 gypsum sand plaster wt 18 width 2" | T-162-OSU (f) | | | | Good performance—adaptable in areas of large volume constr. | a-1017 |
| | | NBS-527-F51 (s) | 38 | | 127 | | |

description

This partition assembly is an economical monolithic plaster construction, 2", 2 $\frac{1}{4}$ " or 2 $\frac{1}{2}$ " in thickness, widely recognized for its space-saving features. USG $\frac{3}{8}$ " Riblath, attached at the floor and ceiling by special runners, contributes vertical rigidity and reinforcement while providing an excellent light-weight plaster base. Nesting and wire tying of ribs on adjacent sheets makes the Riblath a nearly continuous reinforcing membrane which requires temporary bracing only until the partition has been plastered on one side.

The $\frac{3}{8}$ " Riblath for this assembly is slit and expanded from rust-resisting steel in a herringbone mesh pattern with longitudinal ribs— $\frac{3}{8}$ " V-shaped ribs at 4 $\frac{1}{2}$ " intervals and inverted intermediate $\frac{3}{16}$ " ribs. The excellent mechanical keying properties and proper distribution of reinforcing provided by this plaster base give assemblies using it good crack resistance and fire resistance (see table, above).

USG $\frac{3}{8}$ "
riblath**function and utility**

This assembly is ideal for use wherever non-load bearing plastered partitions are desired and particularly where space saving and economy are the most important factors. Its features are:

Economical—solid plaster partitions are accepted as the most economical fire-resistant plaster partition assemblies. The 2" thickness saves space and costly floor area.


Performance—nationally accepted and used in schools, dormitories, apartments and hotels as a functional, economical, space-saving partition construction requiring little maintenance.

Fire Protection—constructed of incombustible components, this assembly has a one-hour fire resistance rating.





Strength—resists high impact loads without discernible cracking. Additional strength and rigidity may be gained by increasing the plaster thickness (see USG Gypsum Plasters Folder in this series).

limitations


1. A non-load bearing partition.
2. Limiting height is 10'.
3. Any door frames used must be fabricated and anchored to prevent twisting and impact vibrations (see Specifications, page 2).
4. Solid partitions, like all other non-load bearing partition constructions, should be isolated from reinforced concrete framing columns and beams. The partition will not resist stresses transmitted to it by movement or deflection of the structural components of the building.
5. Not recommended for use with flat plate reinforced concrete floor-ceiling constructions, unless isolated from the flat plate.







components



see "plaster bases" product catalog for full description on accessories & sizes



USG casing beads (expanded or short flange)



specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.

2. Steel door frames should be fabricated from 16 gauge metal, minimum, shop primed. The opening at the trim return should be accurately formed to the overall thickness of the partition.

Base plates, designed with two anchor holes to prevent rotation, should be securely welded to the flanges to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate.

Four jamb anchors should be provided on each jamb, welded to

the trim returns (see detail page 3) and wire-tied to the riblath. Separate bracing shall be furnished to keep the frame in alignment.

Grouting of the door is required on all installations. Under no conditions shall the lath and plaster terminate against the trim return of the door frame. If door frame struts are used, they shall not exceed $\frac{5}{8}$ " in the direction of the partition thickness.


Door closers are recommended on all oversize doors and doors where the weight of the door (including attached hardware) exceeds 50 lbs.

3. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and


(continued on page 4)

details


scale: 3" = 1'-0"





ceiling attachment




ceiling attachment




light fixture attachment


combination base
runner & screed




metal base




wood base




corner


partition
intersection



outlet box



wall intersection



metal door jamb



elevation — cross section thru frame

specifications (continued from page 2)

humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements, except the floor, and control joints be specified where:

- a. a partition abuts any structural element or dissimilar wall or ceiling assembly.
- b. the partition construction changes within the plane of the partition.
4. The minimum thickness of plaster over conduit, pipe and the back of electrical outlets should be $\frac{1}{2}$ ". The back of all electrical boxes should be reinforced with metal lath.
5. Where a plaster surface is flush with metal, metal bucks, metal windows, or metal base, the plaster should be grooved between the two materials.
6. **Fixture Attachment**—Lightweight fixtures and trim shall be installed by drilling set dry sand plaster to a minimum depth of $\frac{3}{4}$ " and inserting a plastic plug or other expandable anchor for anchorage of attachment screws.
7. **Ceramic Tile**—(Where ceramic tile is required a portland cement-lime plaster shall be applied in scratch and brown coats to $\frac{3}{8}$ " grounds over metal lath as a base). (Ceramic tile shall be adhesively attached over the finished gypsum plaster in accordance with adhesive manufacturer's specifications.)

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. USG 3.4 lb. $\frac{3}{8}$ " Riblath 27" x ceiling height.
- b. USG Metal Base—2 $\frac{1}{2}$ " (18) (20) ga.
- c. USG Metal Base Splice Plate.
- d. USG Double Metal Base Clip.
- e. USG Floor Runner and Screed.
- f. USG L-Type Ceiling Runner.
- g. USG Partition Terminal.
- h. USG Corner Bead (specify type from page 2).
- i. USG Casing Bead (specify type from page 2).
- j. USG Base Screed (specify type from page 2).
- k. USG Cold Rolled Channels $\frac{3}{4}$ ", 1 $\frac{1}{2}$ ", 2".
- l. 18 ga. Tie Wire.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ROCKLATH (plaster base).

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

erection and plaster base attachment

Floor tracks shall be (USG 2 $\frac{1}{2}$ " Metal Base and Double Base Clips) or (USG Floor Runner and Screed) securely attached 24" o.c. Ceiling runner shall be USG L-Type Ceiling Runner attached 16" o.c. and located so that the USG $\frac{3}{8}$ " Riblath will be positioned in the center of the partition.

Attachment to concrete shall be with concrete stub nails or power driven anchors; to ceiling grillage with a double strand of 18 gauge tie wire; to plaster or gypsum lath with toggle bolts or staples.

The riblath shall be erected vertically, attached to the floor runner or set in a groove of the grouted metal base and securely wire-tied 8" o.c. to the ceiling runner. Wire-tie the nested edges of sheets 12" o.c. and securely tie the riblath to jamb inserts or door frames. At all interior angles, metal lath shall be formed into the corners and carried out onto the abutting surface, and adequately secured.

Partition terminals and cased openings shall be finished with USG Partition Terminal wire-tied securely in place.

Temporary bracing shall not be less than $\frac{3}{4}$ " C. R. Channels placed horizontally near mid-height of the partition and tied to the riblath 24" o.c. and with 1 $\frac{1}{2}$ " angle braces placed vertically not over 6' o.c. Wedge the vertical braces at top and bottom and tie the horizontal $\frac{3}{4}$ " channel to hold lath in place. Bracing shall remain in place until the brown coat of plaster on the side opposite the bracing has set.

lathing accessories

a. **Metal Base** shall be 2 $\frac{1}{2}$ " high, (18) (20) gauge, painted. Metal base shall be notched to a neat miter in forming all angles, in continuous runs, ends shall be evenly butted and internally spliced with a splice plate. Base shall be securely held in place by clipping to base clips.

b. **USG Partition Terminal** shall be provided as detailed and where indicated. Attach with 18-gauge tie wire 6" o.c.

c. **Metal Corner Bead** () shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with wire-ties, etc., spaced not over 8" o.c. stagger in two wings.

d. **Casing Bead No.** () shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed.

e. **Base Screed No.** () shall be installed 6" above the finish floor, unless otherwise indicated. Set screeds level, true to line, in lengths as long as practical, with joints aligned with a suitable splice. Wire-tie in place.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

partitions

a

solid-channel stud

USG® Metal Lath and Plaster

1027

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|--------------------------------------|------------|------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | Chan Stud—Solid Metal Lath & Plaster— $\frac{3}{4}$ " cr chan 16" o.c.—3.4# dm met lath—STRUCTO-LITE (Type R) plaster wt 12 width $2\frac{1}{2}$ " | UL Des 19-2 hr (f) | N/A | | 137 | 2-hr. rating also obtainable with 2" of wood fiber plaster | a-1027 |
| 1 hr. | Chan Stud—Solid Metal Lath & Plaster— $\frac{3}{4}$ " cr chan 16" o.c.—2.5# dm met lath—100:2-100:2 gypsum sand plaster wt 18 width 2" | MLA T-129 OSU (f) NBS-523 F45 (s) | 37 | | 133 | Standard solid partition design | a-1027 |

wall furring application

| | | | | | | | |
|---|---|---|---|---|-----|--------------------------------------|--------|
| — | $\frac{3}{4}$ " C.R. Channels 16" o.c., cross braced, 3.4# diamond mesh metal lath, $\frac{5}{8}$ " sanded basecoat plaster, lime putty finish coat | — | — | — | 203 | No vapor barrier; isolation adequate | a-1027 |
|---|---|---|---|---|-----|--------------------------------------|--------|

description

This partition assembly is an economical monolithic plaster construction, 2" or more in thickness, widely recognized for its space-saving features. USG Cold Rolled Channels, placed vertically, act as permanent studs and are attached at the floor and ceiling by special runners. USG Metal Lath, slit and expanded from rust-resisting steel, is wire-tied to the studs providing an ideal, lightweight base for economical application of gypsum plasters.

Metal lath for this assembly is available in two types (see Specifications, page 6). The excellent mechanical keying properties and equal distribution of reinforcing provided by this plaster base give these assemblies high fire resistance and acceptable sound transmission loss ratings (see table, above). For greater fire resistance or increased ceiling height, solid partitions thicker than 2" may be used (see table below).

function and utility

This assembly is ideal for use wherever non-load bearing plastered partitions are desired and particularly where space saving and economy are the most important factors. Its features are:

Economical—Solid plaster partitions are accepted as the most economical fire-resistant plaster partitions. The 2" thickness saves space and costly floor area.

Performance—nationally accepted and used in schools, dormitories, apartments and hotels as a functional, economical, space-saving partition construction requiring little maintenance.

Lightweight—In structural design the dead load ranges from 12 to 23 lbs. per sq. ft. depending on type of plaster aggregate and plaster thickness used.

Fire Protection—Constructed of incombustible components, this assembly has established fire resistance ratings of up to two hours (see table above).

Sound Isolation—provides a 39 decibel (9-freq.) average sound transmission loss, considered satisfactory for normal requirements within offices, apartments and hotel units.

Strength—Highly resistant to impact damage. Additional strength and rigidity may be gained by increasing the plaster thickness (see USG Gypsum Plasters Folder in this series).

limitations

1. A non-load bearing partition.
2. Limiting height for 2" thickness is 12'. (See table below for limitations of other thicknesses).
3. Door frames must be anchored to prevent twisting and impact vibrations (see Specifications, page 6).
4. Solid partitions, like all other non-load bearing partition constructions, should be isolated from reinforced concrete framing columns and beams. The partition will not resist


stresses transmitted to it by movement or deflection of the structural components of the building.

5. Not recommended for use with flat plate reinforced concrete floor-ceiling constructions, unless isolated from the flat plate.


partition thickness—limiting heights

| partition construction | thickness | limiting ceiling ht. |
|--|------------------|----------------------|
| $\frac{3}{4}$ " Cold Rolled Channels Diamond Mesh Lath & Plaster | 2" | 12'-0" |
| $\frac{3}{4}$ " Cold Rolled Channels Diamond Mesh Lath & Plaster | $2\frac{1}{4}$ " | 14'-0" |
| $\frac{3}{4}$ " Cold Rolled Channels Diamond Mesh Lath & Plaster | $2\frac{1}{2}$ " | 16'-0" |
| $1\frac{1}{2}$ " Cold Rolled Channels Diamond Mesh Lath & Plaster | $2\frac{3}{4}$ " | 18'-0" |
| $1\frac{1}{2}$ " Cold Rolled Channels Diamond Mesh Lath & Plaster | 3" | 20'-0" |
| $1\frac{1}{2}$ " Cold Rolled Channels Diamond Mesh Lath & Plaster | $3\frac{1}{2}$ " | 22'-0" |


NOTE: No limitation on length of this partition for heights under 12'-0". Length between columns, or walls, shall not be greater than 2 times the partition height when the latter exceeds 16'-0"; nor greater than the height when it is 24'-0" or more. Heights over 20'-0" shall have horizontal girts every 6'-0".




components




USG Z-type ceiling runner




USG Z-type floor runner




USG floor runner
& screed




USG
double
base clip



USG
single
base clip



see "plaster bases" product catalog for
full description on accessories & sizes



USG metal base & splice plate




USG
selv-edge
cornerite



USG
1-A
expanded
corner bead




USG
4-R
expanded
corner bead




USG metal base
splice plate


USG casing beads (expanded or short flange)




#66 square edge




#60 semi-square edge




#4 or #138 quarter round



USG
adjustable
wall furring
bracket



USG 2"
partition terminal





USG cold rolled
channels


details

scale: 3" = 1'-0"




ceiling attachment







suspended ceiling attachment





floor attachment



intersecting walls



metal door frame details







core walls

Core walls, as vertical shafts encasing the usual plumbing supply and waste lines, vent ducts and electrical conduits, require more free space than can be provided within the usual partition assembly. The channel stud core wall provides almost unlimited space for mechanical installations within the partition.

Core walls are easily constructed using channel studs and metal lath, provided proper bracing is used to compensate for the stress skin action of the one side. The non-lathed side of the studs shall be stiffened with $\frac{3}{4}$ " channel horizontal braces spaced vertically at midpoint to 9'-0", third points to 13'-6"; and $\frac{3}{4}$ " channel bracket mid-girts spaced not over 30" o.c. horizontally (see detail).

horizontal section

scale: 3" = 1'-0"



exterior wall furring





It is recommended that all exterior walls be furred. Asphaltic or bituminous bonding agents are not recommended as a plaster base. Channel studs, metal lath and plaster provide an exterior wall furring system that offers the same space-saving features, economical construction and readily decorated interior wall surface found in the related solid plaster partition.

This system consists of three horizontal $\frac{3}{4}$ " channels, located not more than 6" from the floor and ceiling, and one at the midpoint between floor and ceiling attached to the wall with USG Adjustable Wall Furring Brackets not more than 36" o.c. Vertical channels are wire tied to these horizontal members, with spacing determined by the maximum allowable spacing of supports for the type of metal lath used (see below). Metal lath is wire tied on the vertical channels and plastered to $\frac{3}{4}$ " grounds. If height exceeds 10'-0" using $\frac{3}{4}$ " channels, additional horizontal channels are required, spaced not more than 4'-6" o.c.

| type of lath | weight per sq. yd. | maximum allowable spacing |
|-----------------------|--------------------|---------------------------|
| Diamond Mesh | 2.5 lb. | 12" |
| Diamond Mesh | 3.4 lb. | 16" |
| $\frac{1}{8}$ " Z-Rib | 2.75 lb. | 16" |
| $\frac{1}{8}$ " Z-Rib | 3.4 lb. | 19" |


adjustable wall furring brackets

1. Wall furring brackets shall be attached not more than 36" o.c. horizontally and 4'-6" o.c. vertically.
2. After attachment, bend bracket to horizontal position.
3. Wire-tie plumbed channel to bracket $\frac{1}{4}$ " min. ($2\frac{1}{4}$ " max.) from wall.
4. Bend excess of bracket down.




elevation

floor attachment



top set



metal

specifications

notes to architect

1. In cold weather, all glazing should be completed and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.

2. Steel door frames should be fabricated from 16 gauge metal, minimum, shop primed. The opening at the trim return should be accurately formed to the overall thickness of the partition.

Base plates, designed with two anchor holes to prevent rotation, should be securely welded to the flanges to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate.

Four jamb anchors should be provided on each jamb, welded to the trim returns. (See detail page 3.)

Steel door frames should be grouted solid with mortar when the scratch coat of plaster is applied. Under no conditions shall the lath and plaster terminate against the trim return of the door frame.

Door closers are recommended on all oversize doors and doors where the weight of the door (including attached hardware) exceeds 50 lbs.

3. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements except the floor, and control joints be specified where:

- a. a partition abuts any structural element or dissimilar wall or ceiling assembly.
- b. the partition construction changes within the plane of the partition.

4. The minimum thickness of plaster over conduit, pipe and the back of electrical outlets should be ½". The back of all electrical boxes should be reinforced with metal lath.

5. Where a plaster surface is flush with metal, metal bucks, metal windows, or metal base, the plaster should be grooved between the two materials.

6. Fixture attachment—Lightweight fixtures and trim shall be installed using plastic plugs or other expandable anchors for screw attachment. Heavy fixture attachment is not recommended.

7. Ceramic Tile—Where ceramic tile is required, a portland cement-lime plaster shall be applied in scratch and brown coats to ⅝" grounds over metal lath as a base. Metal lath shall be tied to the tile side of the channel studs.

(Ceramic tile may be adhesively attached over the finished gypsum plaster in accordance with the adhesive manufacturer's specifications.)

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. USG Floor Runner and Screed.
- b. USG Metal Base—2½" (18) (20) ga.
- c. USG Metal Base Splice Plate.
- d. USG Double Metal Base Clip.
- e. USG Single Metal Base Clip.
- f. USG Z-Type Ceiling Runner.
- g. USG Z-Type Floor Runner.
- h. USG Partition Terminal.
- i. USG Corner Bead (specify type from page 2).
- j. USG Casing Bead (specify type from page 2).
- k. USG Cold Rolled Channels ¾", 1½", 2".
- l. USG Adjustable Wall Furring Bracket.
- m. 18 Ga. tie wire.
- n. Metal Lath shall be (2.5 lb.) (3.4 lb.) Diamond Mesh, (2.75 lb.) (3.4 lb.) Z-Riblath 27" x 96".

floor and ceiling track erection

Floor and ceiling track shall be of the type and size shown on the plans or as herein specified and shall be aligned accurately according to the partition layout.

Floor tracks shall be (USG 2½" Metal Base and Double Base Clips) (USG 2½" Metal Base and Single Base Clips) securely attached 16" o.c. or (USG Floor Runner and Screed) (USG Z-Type Floor Runner) securely attached 24" o.c.

Attachment to concrete shall be with concrete stub nails or power driven anchors; to ceiling grillage with a double strand of 18 gauge tie wire; to plaster or gypsum lath with toggle bolts or staples.

partition system erection

Studs shall be ¾" C.R. Channel, and the partition thickness two inches unless otherwise noted. Studs shall be spaced not to exceed 16" o.c. and shall be of sufficient length to properly engage the USG Z-Type Ceiling Runner and the USG Floor Runner and Screed, or the USG Double Base Clips. A stud shall be wire tied at each jamb of steel or wood door frames and at openings cased with the USG Partition Terminal.

A horizontal reinforcement shall be used over all openings and shall consist of a ⅜" round rod or a ⅛" by 1¼" flat bar. Saddle tied to each vertical stud, the bar or rod should extend out to the first stud beyond the frame.



channel stud core wall erection

The core wall shall consist of two lath and plaster diaphragms supported by a channel iron grillage.

Runner tracks shall be provided at each face.

Floor runners shall consist of Single Base Clips at 16" o.c. with 2½" USG Metal Base Face Plate or the USG Z-Type Floor Runner.

The ceiling tracks shall be USG Z-Type Ceiling Runner.

The double row of ¾" c.r. channel studs shall be spaced not to exceed 16" o.c. and shall be of sufficient length to properly engage the floor and ceiling runners.

Aligning ¾" channels shall be saddle-tied to the inside face at each stud. A pair of aligning channels on partitions 9'-0" or less at mid-point or at third points not to exceed 4'-0".

The channel girts shall be tied together by forming brackets of ¾" channels, spaced 30" o.c. along the horizontal aligning channels. Legs of the brackets and channels to be nested and securely wire-tied.

channel stud furring system erection

¾" channel studs shall be erected vertically 16" o.c. and aligned and secured by:

1. Engaging the Single Base Clip or the Z-Type Floor Runner.
2. Engaging the Z-Type ceiling runner.
3. Saddle tying to horizontal ¾" channel girts spaced not to exceed 4'-6" o.c.

The horizontal girts shall be secured to the masonry back-up at 36" o.c. by saddle tying the channel to serrated leg of USG Adjustable Wall Furring Brackets.

door frame erection

Studs shall be attached to the steel door frame, nested in the notches of the jamb anchor clips and securely wire tied. A ⅜" round rod or a ⅛" x 1¼" flat bar horizontal reinforcement shall be used over the head of the door, extending out to engage the first stud beyond the frame. The reinforcing shall be securely wire tied at each channel intersection.

plaster base attachment

Metal Lath shall be applied with the long dimension of the sheet across the supports. The ends of all lath shall be lapped not less than 1 inch. If end laps are made between supports, they shall be adequately laced or tied with 18 gauge tie wire. The sides of diamond mesh lath shall be lapped not less than ½ inch. The sides of riblath shall be lapped by nesting outside ribs, and shall be wire tied to every support, and between supports not to exceed 9 inch intervals. All metal lath shall be placed so that the lower sheets overlap the upper sheets. Wherever possible, ends of lath in adjacent courses shall be staggered. Metal lath shall be secured to all supports, with 18 gauge tie wire at intervals not exceeding 6 inches. At all interior angles, metal lath shall be formed into the corners and carried out onto the abutting surface and adequately secured.

lathing accessories

a. Metal Base—2½ inch (18) (20) gauge, painted, shall be notched to a neat miter in forming all angles. In continuous runs ends shall be evenly butted and internally spliced with a splice plate. Metal base shall be securely held in place by engaging the base clips.

b. Metal Corner Bead No. () shall be provided on all exterior plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with wire-ties, spaced not over 8" o.c.; stagger in two wings.

c. Casing Bead No. () shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Attach with 18 gauge tie wire 6" o.c.

d. USG Partition Terminal shall be provided as detailed and where indicated. Attach with 18 gauge tie wire 6" o.c.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (plaster, metal products); STRUCTO-LITE (plaster).

a-1027

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



UNITED
STATES
GYPSUM

solid

partitions

a

ROCKLATH* and Plaster PLASTER BASE

1036

| fire rating | description | test no. | sound rating | | relative cost index | comments | folder reference |
|-------------|--|-----------------|--------------|---------|---------------------|---|------------------|
| | | | stc | 9-f avg | | | |
| 1 hr. | Studless—Solid Gypsum Lath & Plaster— $\frac{1}{2}$ " long length ROCKLATH— $\frac{3}{4}$ " 100:1-100:2 gypsum sand wt 16 width 2" | T-118-OSU (f) | | | | Economical on volume projects where special fitting or cutting is minimum | a-1036 |
| | | NBS-510 F29 (s) | 34 | | 120 | | |

wall furring applications

| | | | | | | | |
|---|--|---|---|---|-----|---|--------|
| — | $\frac{3}{4}$ " C.R. Channels 16" o.c., cross braced, $\frac{3}{8}$ " Insulating ROCKLATH and BRACE-TITE* Clips, $\frac{1}{2}$ " sanded base-coat plaster, lime putty finish | — | — | — | 185 | Isolation adequate; good vapor barrier | a-1036 |
| — | $\frac{3}{8}$ " Long Length Insulating ROCKLATH, supported by $\frac{3}{4}$ " horizontal channels 36" o.c., $\frac{3}{4}$ " sanded basecoat plaster, lime putty finish | — | — | — | 203 | Limited to 12' ceiling height. Control joints should be used 20' o.c. | a-1036 |

description

This partition assembly is an economical monolithic plaster construction, 2" or more in thickness, which has been readily accepted for its space-saving features. $\frac{1}{2}$ ", V-edge, Long Length ROCKLATH plaster base is held vertically by floor and ceiling runners and plastered on both sides. Temporary bracing is required until the assembly has been partially plastered.

function and utility

This assembly is ideal for use wherever non-load bearing plastered partitions are desired and particularly where space-saving and economy are the most important factors. Its features are:

Economical—solid plaster partitions are accepted as the most economical fire-resistant plaster partition assemblies. The 2" thickness saves space and costly floor area. Material costs are less because no studs are required.

Lightweight—In structural design the dead load for 2" solid plaster partitions ranges from 11 to 16 lbs. per sq. ft., depending on the type of plaster aggregate used.

Performance—nationally accepted and used in schools, dormitories, apartments, and hotels as a functional, economical, space-saving partition construction requiring little maintenance.

Fire Protection—Constructed of incombustible components, this assembly has an established fire resistance rating of one hour (see table above).


Strength—A 240 ft.-lb. impact load concentrated at the center of a 2" x 8'-0" x 16'-0" panel failed to cause serious cracking. Additional strength and rigidity may be gained by increasing the plaster thickness (see USG Gypsum Plasters Folder in this series).

limitations








1. A non-load bearing partition.
2. Limiting height is 10'.
3. Door frames must be fabricated and anchored to prevent twisting and impact vibration (see Specifications, page 6).
4. Solid lath and plaster partitions, like all other non-load bearing partition constructions, should be isolated from

reinforced concrete framing columns and beams. The partition will not resist stresses transmitted to it by movement or deflection of the structural components of the building.






5. Not recommended for use with flat plate reinforced concrete floor-ceiling constructions, unless isolated from the flat plate.



components



see "plaster bases" product catalog for full description on accessories & sizes



details

scale: 3" = 1'-0"




solid

partitions


a

ROCKLATH* and Plaster
PLASTER BASE


1036




ceiling attachment




ceiling attachment




cabinet
fixture attachment




metal base




top set base




light
fixture attachment




corner




partition
intersection




partition
terminal




wood base
& wood runner




wall
intersection



electrical
conduit




outlet
box




integral
wood door frame

details

scale: 3" = 1'-0"



elevation—cross section thru frame



exterior wall furring

It is recommended that all exterior walls be furred. Asphaltic or bituminous bonding agents are not recommended as a plaster base. $\frac{3}{8}$ " square edge Long Length Insulating ROCKLATH and plaster provide structural and economic advantages for special furring conditions.

In this system USG Adjustable Wall Furring Brackets, spaced not more than 36" o.c. and properly secured to the exterior wall, provide the support for $\frac{3}{4}$ " channels placed 36" o.c. horizontally. Long Length Insulating ROCKLATH is attached to the channels by wire ties, and plaster is applied to $\frac{3}{4}$ " grounds.



function and utility

The same space-saving features, fire protection and other economies found in the solid ROCKLATH and plaster partition apply to this exterior wall furring system. In addition, when Insulating ROCKLATH Plaster Base is used its features include:

1. Condensation control.
2. Protection of interior wall surface from moisture seepage.
3. Insulation and vapor barrier.
4. A degree of isolation from structural movement.

limitations

1. Long Length Insulating ROCKLATH wall furring is not economical for cut-up wall areas containing a large percentage of openings.
2. Limiting height of Long Length Insulating ROCKLATH Furring System is 12'-0".





ceiling attachment

floor attachment


details

adjustable wall furring brackets


1. Wall furring brackets should be attached not more than 36" o.c. horizontally and vertically.
2. After attachment, bend bracket to horizontal position.
3. Wire-tie plumbed channel to bracket $\frac{1}{4}$ " min. ($2\frac{1}{4}$ " max.) from wall.
4. Bend excess of bracket down.




**ceiling isolation
at furred wall**




**adjustable wall furring
bracket and attachment
of ROCKLATH plaster base**




**jamb section at
metal door or window**




**column or
wall isolation**



**detail at typical
closet carrier**



metal base



core wall horizontal section

specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.

2. Steel door frames should be fabricated from 16 gauge metal, minimum, shop primed. The opening at the trim return should be accurately formed to the overall thickness of the partition.

Base plates, designed with two anchor holes to prevent rotation, should be securely attached to trim returns to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate.

Four jamb anchors should be provided on each jamb, welded to the trim returns (see detail page 4) and wire-tied to the ROCKLATH. Separate bracing shall be furnished to keep the frame in alignment.

Grouting of the door frame is required on all installations. The grout shall be raked out to allow the lath and plaster to be inserted into the frame. Under no conditions shall the lath and plaster terminate against the trim return of the door frame.

If door frame struts are used, they shall not exceed $\frac{5}{8}$ " in the direction of the partition thickness.

Door closers are recommended on all oversize doors and doors where the weight of the door (including attached hardware) exceeds 50 lbs.

3. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements, and control joints be specified where:

- a. a partition abuts any structural element or dissimilar wall or ceiling assembly.
- b. the partition construction changes within the plane of the partition.

4. Holes cut in a thin lath and plaster membrane, such as door frames, borrowed lights, etc., cause a concentration of stresses in the plaster. The use of cornerite, striplath and self-furring diamond mesh lath is recommended at the weakened area to distribute concentrated stresses.

5. The minimum thickness of plaster over the back of electrical outlets should be $\frac{1}{2}$ "; over electrical conduits or cables a full $\frac{3}{8}$ " thickness of base coat plaster. Accordingly the maximum size for conduit and pipe should be 1"; switch boxes and convenience outlets should not exceed $1\frac{1}{2}$ " in depth including plaster ring. The back of all electrical boxes conduit and cables should be covered with 15 lb. felt under metal lath fastened to the ROCKLATH.

6. Where a plaster surface is flush with metal, metal bucks, metal windows, or metal base, the plaster should be grooved between the two materials.

7. On all fire-rated partitions, all metal base assemblies should be filled with a grout of gypsum plaster.

8. **Fixture Attachment**—Lightweight fixtures and trim shall be installed by drilling set dry plaster to a minimum depth of $\frac{3}{4}$ " and inserting a plastic plug or other expandable anchor for anchorage of attachment screws.

Cabinet and shelving grounds shall consist of $\frac{3}{4}$ " (actual dimension) by $1\frac{1}{2}$ " wood strips, having 6d (minimum) coated nails driven $\frac{3}{8}$ " into both edges at not over 12" o.c., attached to the ROCKLATH by nailing, wire tying or bolting.

9. This partition is not recommended for use where the unplastered face of the gypsum lath is not protected from wetting or high humidity such as behind a preset bath tub. The USG Metal Lath, Channel Stud and Plaster partition is recommended for use in such areas (see USG Systems Folder).

10. **Ceramic Tile**—(Where ceramic tile is required over ROCKLATH, self-furring diamond mesh metal lath shall be stapled over the ROCKLATH plaster base with staples spaced approximately 8" o.c., horizontally and vertically, and portland cement-lime plaster shall be applied in scratch and brown coats to $\frac{5}{8}$ " grounds over lath as a base for the ceramic tile). (Ceramic tile shall be adhesively attached over the finished gypsum plaster in accordance with adhesive manufacturer's specifications.)

11. To retain maximum sound isolation, the integrity of the partition should not be voided by openings such as electrical outlets, medicine cabinets, vents, etc., that create sound leaks. Use sand aggregate only, do not use lightweight aggregates.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architect Service Department, 101 S. Wacker Dr., Chicago, Ill., 60606.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. ROCKLATH Plaster Base shall be ($\frac{1}{2}$ ", V-edge, Long Length ROCKLATH for solid partition) ($\frac{3}{8}$ " square edge, Long Length Insulating ROCKLATH for exterior wall furring).
- b. USG Metal Base— $2\frac{1}{2}$ " (18) (20) ga.
- c. USG Metal Base Splice Plate.
- d. USG Double Metal Base Clip.
- e. USG Single Metal Base Clip.
- f. USG Floor Runner and Screed.
- g. USG L-Type Ceiling Runner.
- h. USG Ceiling Runner Clips.
- i. USG Partition Terminal.
- j. USG Selv-edge Cornerite (2" x 2") (3" x 3").
- k. USG 4" Striplath.
- l. USG Self-Furring Junior Diamond Mesh Metal Lath.
- m. USG Corner Bead (specify type from page 2).
- n. USG Casing Bead (specify type from page 2).
- o. USG Base Screed (specify type from page 2).
- p. USG Cold Rolled Channels $\frac{3}{4}$ ", $1\frac{1}{2}$ ", 2".
- q. USG Bracing Clips.
- r. 18 Ga. tie wire.
- s. USG Adjustable Wall Furring Bracket.
- t. BRACE-TITE* Field Clip BT-1 (for wall furring).
- u. BRACE-TITE Starter Clip BT-1 (for wall furring).
- v. USG Z-Type Ceiling Runner (for wall furring).



solid

partitions

a

ROCKLATH* and Plaster
PLASTER BASE

1036

partition erection and plaster base attachment

Floor tracks shall be (USG 2½" Metal Base and Double Base Clips) or (USG Floor Runner and Screed) securely attached 24" o.c. Ceiling runner shall be USG L-Type Ceiling Runner attached 16" o.c. and located so that the ROCKLATH will be positioned in the center of the partition.

Attachment to concrete shall be with concrete stub nails or power driven anchors; to ceiling grillage with a double strand of 18 gauge tie wire; to plaster or gypsum lath with toggle bolts or staples.

The ½" Long Length ROCKLATH shall be cut in length to allow ¼" minimum and 1¼" maximum top clearance at the ceiling. Erect vertically with the V-joint edges brought into close contact with the adjacent edge. Attach ROCKLATH to the floor runner or set in a groove of the grouted metal base and securely clip to the ceiling runner with two USG Ceiling Runner Clips per board. Wire-tie the ROCKLATH securely to the jamb inserts or door frames. ROCKLATH having cut vertical edges shall be used only at the ends of partitions or at door frames and not in the central portion of the partition.

Temporary bracing shall be not less than ¾" C.R. channels placed horizontally and 1½" angle stiffener placed vertically. For partitions up to 8'-6" high one horizontal brace is placed near mid-height of the partition. For partitions over 8'-6" high two horizontal braces at third points shall be used. Vertical stiffeners placed not over 6' o.c. shall be used on partitions over 6' in length. The horizontal channel shall extend the full length of the partition and be fastened with USG Bracing Clip or securely wire-tied at the center of the lath and the ends of the channel. Wedge the vertical stiffeners at top and bottom and securely wire-tie to horizontal bracing. Bracing shall remain in place until the brown coat of plaster on the side opposite the bracing has set.

Grounds shall be set to provide ¾" minimum thickness, including ⅛" finish.

wall furring erection and plaster base attachment

Floor tracks shall be (USG Floor Runner and Screed attached 24" o.c.) or (USG 2½" Metal Base and Single Base Clips attached 24" o.c., grouted and grooved).

USG L-Type Ceiling Runner shall be attached 16" o.c. to the construction above as required, plumbed up from the floor runner, or a furring channel shall be installed 6" from top as specified below.

USG Adjustable Wall Furring Brackets, with serrated edges up, shall be attached to the masonry walls not over 4" from columns or other abutting construction and not over 36" o.c. horizontally and vertically, and as required above and below windows, using (one 2" cut nail in mortar joints of brick clay tile, or cement block or in the field of lightweight aggregate blocks) (¾" concrete stub nails or power-driven nails or other suitable fasteners in monolithic concrete). Fastenings shall be driven through top hole of bracket. Furring channels shall be laid horizontally on the furring brackets with the legs down, plumbed to a line with the ceiling runner and base, and wire tied to the bracket with a double strand of 18-gauge tie wire. Excess bracket length shall be bent down.

⅜" Long Length Insulating ROCKLATH shall be applied with the long edges vertically and butted lightly, with the foil facing the furred space. The bottom of the lath shall be set in the groove provided in the base grout or wood runner. The top of the lath shall be wire tied over a nail at the edges to each intermediate horizontal channel. ROCKLATH shall be cut and fit to allow slight clearance around window frames.

4" Striplath shall be applied over the full length of all ROCKLATH joints above and below windows.

Grounds shall be set to provide ¾" minimum plaster thickness, including ⅛" finish.

lathing accessories

a. **Metal Base** 2½ inch, (18) (20) gauge, painted, shall be notched to a neat miter in forming all angles. In continuous runs, ends shall be evenly butted and internally spliced with a splice plate. Base shall be securely held in place by engaging the base clips.

b. **Cornerite** (2" x 2") (3" x 3") shall be installed in all interior plaster angles. Staple at the edges.

c. **Metal Corner Bead No. (000000)** shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with galvanized staples, etc., spaced not over 8" o.c.; stagger in two wings.

d. **Casing Bead No. (000000)** shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed.

e. **Reinforcing**—Install a strip of self-furring diamond mesh lath over joints between dissimilar plaster bases. At all openings, reinforce the corners attaching a 12" x 24" piece of self-furring diamond mesh lath diagonally across the corners.

f. **USG Partition Terminals** shall be installed at partition terminals and cased openings where indicated on the drawings. Staple or wire-tie securely in place.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ROCKLATH (plaster base); BRACE-TITE (lathing system).

NOTE: Since methods and conditions of application and use are beyond our control, the United States Gypsum Company will not be responsible for failure of its products when not used according to our directions and specifications.

a-1036



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

partitions

a

USG® 2" Solid Gypsum Drywall

1047

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|--------------------|------------|------|---------------------|----------|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | Solid Drywall— $\frac{1}{2}$ " SHEETROCK FIRECODE "C" gypsum wallbd faces ea side over 1" USG gypsum corebd—face layers lamin—joints stag & fin—USG #218 track at flr— $\frac{1}{2}$ " met trim at sidewall/clg wt 8 width 2" | T-1339-OSU (f) | N/A | | 120 | | a-1047 |
| 2 hrs. est | Solid Drywall— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd faces ea side over 1" USG gypsum corebd—face layers lamin—joints stag & fin wt 9 width $2\frac{1}{4}$ " | TL-59-98 (s) | 34 | | 124 | | a-1047 |
| 2 hrs. | Solid Drywall Vent Shaft— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd faces ea side over 1" USG gypsum corebd—face layers lamin & screw att—joints stag & unfin— $\frac{3}{8}$ "x1 $\frac{1}{2}$ " angle runners horiz at flr clg & qtr points wt 9.4 width $2\frac{1}{4}$ " | UL Des 21-2 hr (f) | N/A | | 124 | | a-1047 |
| 1½ hrs. | Solid Drywall— $\frac{1}{2}$ " SHEETROCK gypsum wallbd faces ea side over 1" USG gypsum corebd—face layers lamin—joints stag & fin—1" sq wd runner ea side wt 8 width 2" | T-1175-OSU (f) | N/A | | 105 | | a-1047 |

description

In this non-load bearing partition assembly SHEETROCK® Gypsum Wallboard face layers are job-laminated to both sides of USG Coreboard. The Coreboard, a 1" thick fireproof gypsum core encased in strong gray liner paper on both sides and long edges, is 24" wide and mill-fabricated to standard lengths. Integrally formed "V" T & G edges facilitate accurate alignment of the coreboard during erection to metal floor and ceiling runners. The partition when completed with the PERF-A-TAPE® Joint System and DUR-A-BEAD® Corner Reinforcement is ideally suited for interior dividers and vent shaft construction requiring a 2-hour fire resistance rating.

SHEETROCK for this assembly is $\frac{1}{2}$ " or $\frac{5}{8}$ " thick and available in two types (see Specifications page 5). SHEETROCK FIRECODE® Gypsum Wallboards have a specially formulated core containing special mineral materials that generally obtain higher fire resistance ratings than with plain SHEETROCK wallboard (see table above).

function and utility

Fire Resistant—Constructed of incombustible components (except when wood runners are used), the system has obtained fire endurance and hose stream ratings of 2 hours. Ideal as vent shaft.

Versatile—Adaptable for use in virtually every type of new construction or alteration work for permanent space division. In remodeling or modernization, normal work proceeds with a minimum of disturbance because these job-erected partitions are quickly and easily installed.

Easily Decorated—A highly suitable base for any decorative treatment—paint, wallpaper, fabrics or plastic films.

Economical—Erects faster than most other types of partitions. Utilizes low-cost materials and a minimum number of components. In addition, the 2" thickness saves space and costly floor area.

limitations

1. Non-load-bearing.
2. Limiting height: (Based on partitions with complete perimeter restraint and no openings. Where openings occur in


short runs, consider limiting height as that corresponding to "over 18 ft." width between restraints.)

| width between restraints | 2" solid partition | $2\frac{1}{4}$ " solid partition (1) |
|--------------------------|--------------------|--------------------------------------|
| Up to 12' | 12' | 14' |
| 12' to 18' | 11' | 13' |
| Over 18' | 10' | 12' |


(1) When $\frac{5}{8}$ " SHEETROCK Wallboard used as face layers.

3. Partition should not be used where exposed to abnormal moisture or excessively high humidity or temperature.


4. Installation of partition requires close coordination with electrician.



components




1" "V" edged
T & G coreboard




tapered edge SHEETROCK
gypsum wallboard

see "gypsum wallboard and joint treatment" product
catalogs for full description on accessories & sizes




USG-158 metal runner



$1\frac{3}{8}$ " x $\frac{7}{8}$ "—22 ga.
metal angle runner



USG control
joint #093






no. 100 PERF-A-BEAD* reinforcement



DUR-A-BEAD corner reinforcement



USG metal trim



1" USG drywall screw—type S—bugle head



1 1/4" USG drywall screw—type W—bugle head



1 1/4" USG drywall screw—type S—bugle head



1 5/8" USG drywall screw—type S—trim head



2 1/4" USG drywall screw—type S—bugle head





1 1/2" USG drywall screw—type G—bugle head



details

scale: 3" = 1'-0"


ceiling attachments




floor attachment & base




wall plan sections




partition intersection



coreboard edge joint



wall control joint








corner




details

scale: 3" = 1'-0"




metal door frame



intersecting walls




fixture attachment




details/vent shaft


ceiling attachment




floor attachment



alternate ceiling attachment



wall plan section



wall elevation

specifications

notes to architect

1. Metal door and borrowed light frames should be formed from 18-ga. steel minimum, shop primed. The opening between the trim returns should be accurately formed to the overall thickness of the partition.

Floor anchor plates should be 14-ga. steel minimum, designed with two anchor holes to prevent rotation and welded to trim flanges to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate. Jamb anchor clips should be formed of 18-ga. steel minimum, and welded in the jamb and head. (See details page 4.)

Door frame struts should be 1" x 1/4" hot rolled steel bar stock. Where struts are not used, temporary bracing should be used to level and plumb frame until partition is erected.

All one-piece metal door and borrowed light frames should be spot grouted at the jamb anchor clips, after the coreboard is installed. A grouting of DURABOND or USG Ready-Mixed Joint Compound should be applied just before the face layer is inserted to securely adhere the wallboard to the frame. Under no conditions should the wallboard terminate against the trim return of the door frame.

Where wood door or borrowed light frames are required, the nominal 1" x 1" wood runner detailed for floor and ceiling runners should be used for the rough buck. In the case of door frames, the jamb section of the rough buck may serve as a strut and should extend from floor to ceiling and be securely toenailed to runners.

Door closers and bumpers are required on all doors where the weight of the door (including attached hardware) exceeds 50 lbs.

2. Non-load bearing drywall partitions will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements, except the floor, by control joints or other means where:

- a. A partition abuts any structural element or dissimilar wall or ceiling assembly.
- b. The partition construction changes within the plane of the partition.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

3. Holes cut in a thin wallboard membrane such as door frames, borrowed lights, etc., cause a concentration of stresses in the wallboard typically at intersection of head and jamb. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

4. Electrical Fixtures—The depth of electrical boxes should not exceed 1 1/2".

5. Ceramic Tile—SHEETROCK W/R Gypsum Wallboard is recommended as a base for the adhesive application of ceramic, metal and plastic tile.

6. Partition must be caulked to obtain 34 STC sound rating.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 70°F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Joint Treatment Folder for PERF-A-TAPE Joint System Specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. Coreboard—1" thick, 24" wide, USG "V" T & G edge Gypsum Coreboard, lengths as required.
- b. Faceboards—(1/2") (5/8") thick, 48" wide, (Tapered Edge SHEETROCK Wallboard) (SHEETROCK FIRECODE) lengths as required.
- c. Laminating Adhesive—PERF-A-TAPE Joint Compound (embedding type) or USG Laminating Adhesive.
- d. Joint Treatment—PERF-A-TAPE or DURABOND* Joint System.
- e. Fasteners—(specify type from page 2).
- f. USG Metal Trim (specify type from page 2).
- g. USG Corner Bead—DUR-A-BEAD, PERF-A-BEAD* (specify type from page 2).
- h. USG No. 158 Metal Runner.
- i. Metal Angle Runners—1 3/8"x7/8"x22 ga.

runner erection

All partitions shall be aligned accurately according to the partition layout.

Floor and ceiling runner tracks shall be securely attached:

1. To Concrete Slabs—Using concrete stub nails or power driven anchors, spaced not to exceed 24" o.c.
2. To Wood Framing—Using suitable fasteners spaced not to exceed 24" o.c.
3. To Suspended Ceilings—Using toggle or molly bolts, spaced not to exceed 24" o.c.



partition erection

Cut coreboard to fit accurately between floor and ceiling angles and install vertically with tongue edge leading. Fasten coreboard to angle runners with two 1 1/4" Type S Screws placed 3" in from each edge. Erect succeeding panels using the same procedure.

At partition intersections, coreboards shall be nailed together with 10d nails spaced 24" o.c. Panels shall be inserted in jamb anchor clips at all door frames, borrowed light frames and partition terminals and spot grouted at the clip locations.

Face boards shall be cut to full floor-to-ceiling height. Apply laminating adhesive to surface of coreboard and laminate in place using moderate pressure to insure adequate bond. Offset face panel joints at least 3" from coreboard joints. Screw face layer to coreboard at vertical joints and at center of faceboard with USG 1 1/2" Type G Screws. Screws along vertical edges shall occur 36" o.c. maximum, within 2" of joint and 12" of both ends. Screws in field shall occur 48" o.c. maximum and within 24" of both ends.

Coreboards and face boards shall be cut neatly to fit around all outlets and switch boxes. Suitable fastener anchorage shall be provided as required for the attachment of shelves and cabinets.

Work done by this contractor shall be coordinated properly with that to be done by other trades.

vent shaft erection

Floor, ceiling and sidewall angle runners shall be aligned accurately according to the partition layout. Fasten runners securely to structural supports with suitable fasteners 24" o.c. USG No. 158 metal ceiling runners shall be installed by fastening through the web; 1 3/8"x7/8"x22 ga. galvanized metal angle runners on the floor and sidewalls by fastening through the short leg. As an alternate, metal angles may be used as ceiling runners. Side angle runners 30" long shall be centered for attachment of horizontal bracing angles.

1 3/8"x7/8"x22 ga. galvanized bracing angles shall be installed at quarter points down from the ceiling, up from the floor and spaced no greater than 5' o.c. Position long leg for wallboard attachment and fasten to sidewall angles with 1" USG Drywall Screw Type S.

5/8" SHEETROCK FIRECODE Wallboard inner layer shall be applied vertically and fastened to angles and runners with 1"

USG Drywall Screws Type S spaced 16" o.c. 1" coreboard shall be erected vertically and laminated to inner wallboard layer with vertical joints staggered 12" from wallboard joints. When No. 158 metal ceiling runner is used, the fasteners attaching the 5/8" thick inner layer to runner may be omitted.

Second floor and side angle runners (and ceiling angles, if required) shall be positioned with the long leg against the coreboard secured to structural members with suitable fasteners and attached to coreboard with 2 1/4" USG Drywall Screws Type S spaced 12" o.c. Drive screws at least 6" away from coreboard edges.

5/8" SHEETROCK FIRECODE face layer shall be laminated and erected vertically with vertical joints staggered 12" from joints in coreboard. Face layer shall be attached to angles around perimeter with 1" Type S screws 12" o.c.

wallboard accessories

a. **PERF-A-TAPE or DURABOND Joint System** shall be used on all face board joints and internal angles formed by the intersections of walls and ceilings.

b. **Laminating Adhesive** shall be USG PERF-A-TAPE Joint Compound (embedding type) mixed according to manufacturer's directions or USG Laminating Adhesive spread to provide adhesive beads 1/2" high x 5/16" wide at the base and spaced 4 1/2" o.c.

c. **Metal Corner Bead No. ()** shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.

d. **Metal Trim No. ()** shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.


e. **Fasteners** shall be as shown on drawings or as herein specified. Fasteners shall be driven no less than 3/8" from ends or edges of wallboard to provide uniform dimple not over 1/32" deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

f. **Control Joints** shall be provided in the face layer as indicated and where detailed. Staple in place.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products, gypsum coreboard, adhesives); SHEETROCK, FIRECODE (gypsum wallboard); PERF-A-TAPE, DURABOND (joint treatment); DUR-A-BEAD, PERF-A-BEAD, PERF-A-TRIM (corner reinforcement).

a-1047

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



UNITED
STATES
GYPSUM

partitions

a

USG® Studwall Gypsum Drywall

1057

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|--------------------|------------|------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. | 278 Gypsum Studwall— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd— $1\frac{1}{8}$ "x6" lamin gypsum studs 24" o.c.—wallbd screw att both sides 18" o.c. wt 7 width $2\frac{3}{8}$ " | UL Des 16-1 hr (f) | N/A | | 113 | Basic interior divider—chase allows easy elect. installation | a-1057 |

description

In this non-load bearing partition assembly of SHEETROCK® Gypsum Wallboard face layers are job-laminated to both sides of $1\frac{1}{8}$ " x 6" gypsum studs positioned vertically 24" o.c. The SHEETROCK panels are attached to 25 ga. electro-galvanized steel floor and ceiling runners with specially designed power-driven, self-tapping steel screws. The gypsum studs, factory-laminated in stock lengths, are cut 12" shorter than the partition height to facilitate electrical installation. The partition when completed with the PERF-A-TAPE® Joint System and DUR-A-BEAD® Corner Reinforcement is ideal for use as space separation within units in all types of non-residential construction.

SHEETROCK for this assembly is $\frac{1}{2}$ " thick for Studwall #258 or $\frac{5}{8}$ " thick for Studwall #278 and available in two types (see Specifications, page 6). SHEETROCK FIRECODE® Gypsum Wallboards have a specially formulated core containing special mineral materials that generally obtain higher fire resistance ratings than with plain SHEETROCK wallboard (see table above).

function and utility

Fire Resistance—Constructed of incombustible components (except when wood runners are used), a fire resistance rating of 1 hour has been established for the Studwall #278 with $\frac{5}{8}$ " SHEETROCK FIRECODE face layers.

Lightweight—Excellent utility where space savings and reduced loads are design requirements:

| type | thickness | weight psf. |
|---------------|------------------|-------------|
| Studwall #258 | $2\frac{3}{8}$ " | 6 lbs. |
| Studwall #278 | $2\frac{3}{8}$ " | 7 lbs. |


Easily Decorated—The systems inherently provide back blocking; minimize joint ridging. SHEETROCK face panels provide a highly suitable base for any decorative treatment—paint, wallpaper, fabrics or plastic films.

Economical—Utilizes low-cost materials and a minimum number of components.


Versatile—Available in two thicknesses to meet varying job requirements. Adaptable for use in virtually every type of new construction or alteration work for permanent space division within units.

limitations


1. Non-load bearing.
2. Limiting height: 12'.
3. Partition should not be used where exposed to abnormal moisture or excessively high humidity.




components





tapered edge
SHEETROCK gypsum wallboard




1 5/8" x 6"
gypsum stud



no. 100 PERF-A-BEAD* reinforcement





USG
metal stud





USG metal runner



DUR-A-BEAD* corner reinforcement



USG metal trim



USG control
joint #093

see "gypsum wallboard and joint treatment" product catalogs for full description on accessories & sizes



3/8" USG drywall screw—type S—pan head



3/8" USG drywall screw—type S-12—pan head




1" USG drywall screw—type S—bugle head




1 5/8" USG drywall screw—type S—trim head



1 1/2" USG drywall screw—type G—bugle head



pierces & folds light metals




positive & permanent lock

USG metal lock fastener



details

scale: 3" = 1'-0"




typical joint detail

ceiling attachment




starting panel detail



floor attachment




fixture attachment



wall plan sections


partition intersection
(metal)


partition terminal



partition corner
(metal)

details









scale: 3" = 1'-0"

metal door frames

standard reveal type
frame (18 ga. min.)




SHEETROCK
gypsum
wallboard




details


ceiling attachment




floor attachment



base




partition terminal



elevation


cross section thru wood door frame



jamb


wood door frame

wall plan sections



partition corner

partition intersection



wall intersection

specifications

notes to architect

1. Metal door and borrowed light frames should be formed from 18-ga. steel minimum, shop primed. The opening between the trim returns should be accurately formed to the overall thickness of the partition.

Floor anchor plates should be 14-ga. steel minimum, designed with two anchor holes to prevent rotation and welded to trim flanges to dampen door impact vibrations. Floor anchorage should be by two power driven anchors or equivalent per plate. Door frames designed for attachment to a floor to ceiling height metal stud acting as a strut-stud adjacent to each jamb are recommended. Jamb anchor clips should be formed of 18-ga. steel minimum, welded in the jamb and head (see detail page 4), and screw attached to the stud.

Door frame struts, when required, should be $\frac{1}{4}$ " minimum thickness, hot rolled steel bar stock and of sufficient width to completely fill doorstop void, anchoring jamb securely. All door frame struts should be supplied as an integral part of the door frame.

All one-piece metal door and borrowed light frames should be spot grouted at the jamb anchor clips, after the stud and before the wallboard is installed. A grouting of DURABOND or USG Ready-Mixed Joint Compound should be applied just before the face layer is inserted to securely adhere the wallboard to the frame. Under no conditions should the wallboard terminate against the trim return of the door frame.

Door closers and bumpers are required on all doors where the weight of the door (including attached hardware) exceeds 50 lbs.

2. Non-load bearing drywall partitions will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements, except the floor, by control joints or other means where:

- a. A partition abuts any structural element or dissimilar wall or ceiling assembly.
- b. The partition construction changes within the plane of the partition.

In long partition runs, vertical control joints should be provided at intervals no greater than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

3. Holes cut in a thin wallboard membrane such as door frames, borrowed lights, etc., cause a concentration of stresses in the wallboard typically at intersection of head and jamb. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

4. Electrical Fixtures—The depth of electrical boxes should not exceed $1\frac{1}{2}$ ". A 25-ga. (min.) galvanized steel plate should be placed behind all electrical boxes for reinforcing. A metal stud adjacent to the electrical box may be desired to provide additional reinforcement.

5. Ceramic Tile—The use of SHEETROCK W/R Gypsum Wallboard is recommended to provide a base for the adhesive application of ceramic, metal and plastic tile.

6. Where wood base is required, it should be applied with trim head screws placed at each stud location and midway between stud locations (12" o.c.) and at other points where required.

7. The use of a non-hardening caulking material to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure is recommended to improve sound control. Eliminate cutting holes back to back and adjacent to each other.

8. Fixture attachment—Wood or metal mounting strips for cabinets or shelving should be bolted through the wallboard and studs using an elevator bolt with a $\frac{3}{4}$ " (min.) head diameter. Only lightweight fixtures should be attached to face layer between gypsum studs using sheet metal screws and 25-ga. (min.) steel plate or strip.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly with the range of 55° to 70° F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Joint Treatment Folder for Joint System Specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

a. Faceboards—($\frac{1}{2}$ " ($\frac{5}{8}$ ") thick, 48" wide Tapered Edge SHEETROCK (Regular) (FIRECODE), lengths as required.

b. Gypsum Studs— $1\frac{3}{8}$ " x 6" USG Gypsum Studs, factory laminated ($\frac{1}{2}$ "- $\frac{5}{8}$ "- $\frac{1}{2}$ ") in stock lengths.

c. USG No. 158 ($1\frac{5}{8}$ ") Runner.

d. USG No. 158 ($1\frac{5}{8}$ ") Metal Stud.

e. Laminating Adhesive—PERF-A-TAPE Joint Compound (embedding type) or USG Laminating Adhesive.

f. Joint Treatment—PERF-A-TAPE or DURABOND* Joint System.

g. Fasteners—(specify type from page 2).

h. USG Metal Trim (specify type from page 2).

i. USG Corner Bead—DUR-A-BEAD, PERF-A-BEAD* (specify type from page 2).

**erection and lamination**

All partitions shall be aligned accurately according to the partition layout.

Floor and ceiling runners shall be securely attached to concrete slabs with concrete stub nails or power-driven anchors, to suspended ceilings with toggle or molly bolts, to wood framing with suitable fasteners. Space fasteners not to exceed 24" o.c. on ceilings and walls and 16" o.c. on floors.

Metal studs shall be installed vertically at "T" intersections, partition terminals and intersections with structural members or walls. Securely fasten all studs to floor and ceiling runners with the USG Metal Lock Fastener or $\frac{3}{8}$ " USG Drywall Screws Type S, pan head.

Gypsum wallboard face layers shall be cut to full floor-to-ceiling height for vertical installation. The ends of the face panels shall fit over the runner flanges. Vertical joints shall occur over gypsum studs and shall be staggered on opposite sides of the partition. Wallboard shall be cut to fit neatly around all outlets and switch boxes. Suitable fastener anchorage shall be provided as required for the attachment of shelves and cabinets. Work done by this contractor shall be coordinated properly with that done by other trades.

Gypsum studs shall be laminated to the back of face panels at the center line prior to erection. Studs shall terminate no more than 6" from top and bottom edges of face panels. Allow adhesive to set and dry before moving panels.

Erect face panels with studs attached alternately to opposite sides of the partition. Securely laminate face layer to gypsum studs at vertical joints. Gypsum studs in completed assembly shall be no greater than 24" o.c. Fasten face layers to floor and ceiling runners and to vertical flanges of all metal studs with 1" USG Drywall Screws Type S spaced 12" o.c. Screw face layers to gypsum studs with $1\frac{1}{2}$ " USG Drywall Screws Type G. Screws along vertical edges shall occur 36" o.c. maximum, within 2" of joint and 12" of both ends. Screws in field shall occur 48" o.c. maximum and within 24" of both ends.

Vertical panel joints shall be kept at least 6" away from structural members, partition terminals, intersections, corners, doors and other openings. Partition corners shall contain two metal studs, one in each wall cavity, erected vertically, fastened securely to floor and ceiling runners, and attached to each other through one face layer with 1" USG Drywall Screws Type S spaced 24" o.c.

door frames

Floor to ceiling height metal studs shall be inserted into each side of the steel door frame to act as a strut-stud. Attach strut-studs to floor and ceiling runners with the USG Metal Lock Fastener and to each adjacent jamb anchor clip with two $\frac{3}{8}$ " USG Drywall Screws Type S-12, pan head. Over the metal door install a cut-to-length section of runner with flanges slit and web bent to allow flanges to overlap and attach to adjacent strut-studs. A cut-to-length stud extending from the doorhead runner to the ceiling runner shall be centered between strut-studs and securely fastened to runners.

wallboard accessories

a. **PERF-A-TAPE or DURABOND Joint System** shall be used on all face board joints and internal angles formed by the intersections of walls and ceilings.

b. **Laminating Adhesive** shall be PERF-A-TAPE Joint Compound (embedding type) mixed according to manufacturer's directions or USG Laminating Adhesive spread to provide adhesive beads $\frac{3}{8}$ " high x $\frac{1}{2}$ " wide at the base and spaced 2" o.c. and 1" away from each edge of the gypsum studs.

c. **Metal Corner Bead No. ()** shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.

d. **Metal Trim No. ()** shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.

e. **Fasteners** shall be as shown on drawings or as herein specified. Fasteners shall be driven not less than $\frac{3}{8}$ " from ends or edges of wallboard to provide uniform dimple not over $\frac{1}{32}$ " deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

f. **Control Joints** shall be provided in the face layer as indicated and where detailed. Staple in place.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products, adhesives); SHEETROCK, FIRECODE (gypsum wallboard); PERF-A-TAPE, DURABOND (joint treatment); DUR-A-BEAD, PERF-A-BEAD, PERF-A-TRIM (corner reinforcement).

a-1057

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selecta
for
Sales
Offices

partitions

a

USG® Ribwall Gypsum Drywall

1067



A.I.A. File No. 20-B-21

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|------------------------------------|------------|------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | 418 Gypsum Ribwall—2 layers $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd ea side—1"x6" gypsum ribs 24" o.c. lamin betw base layers—wallbd screw att—joints fin wt 12 width $4\frac{1}{8}$ " | UL Des 17-2 hr (f) TL-63-15 (s) | | 51 | 165 | Has design flexibility for pipe chase or party walls | a-1067 |
| 1 hr. est | 368 Gypsum Ribwall— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd—1"x6" gypsum ribs 24" o.c. lamin betw single layer wallbd ea side—wallbd screw att at joints—joints fin wt 8 width $3\frac{3}{4}$ " | TL-62-285 (s) | | 43 | 130 | | a-1067 |

description

These incombustible non-load bearing partition assemblies are of two types that incorporate cavity space $1\frac{3}{8}$ " to $2\frac{1}{2}$ " deep. The cavity improves fire and sound resistance and accommodates electrical services and plumbing. Opposite faces are reinforced by attached gypsum ribs, but are not joined by common ribs.

#418 Ribwall consists of a double row, each side, of $\frac{5}{8}$ " SHEETROCK® FIRECODE® Gypsum Wallboard face layers job-laminated to staggered 1" x 6" gypsum ribs. The SHEETROCK panels are attached to USG No. 158, 25 ga. electrogalvanized steel, floor and ceiling runners with specially designed power-driven, self-tapping steel screws. The gypsum ribs, snapped and separated on the job from stock lengths of 1" Coreboard prescored 6" o.c., are cut 12" shorter than the partition height to provide electrical chases. The partition when completed with the PERF-A-TAPE® Joint System and DUR-A-BEAD® Corner Reinforcement has very good sound attenuation characteristics (see table above).

#368 Ribwall consists of $\frac{5}{8}$ " SHEETROCK FIRECODE Wallboard face layers job-laminated to $1\frac{3}{8}$ " x 6" gypsum ribs. The ribs are mill-fabricated, staggered 12" o.c. and cut 12" shorter than the partition height. The SHEETROCK Panels are screw-attached to both sides of USG No. 212 ($2\frac{1}{2}$ ") floor and ceiling runners.

SHEETROCK for these assemblies is $\frac{5}{8}$ " thick and available in two types (see Specifications, page 7). Tapered edge SHEETROCK Wallboard may be used for #368 Ribwall; SHEETROCK FIRECODE Gypsum Wallboard is used for #418 Ribwall. Lower cost BAXBORD® Gypsum Backing Board may be used as a base layer for Ribwall #418. SHEETROCK FIRECODE Gypsum Wallboards have a specially formulated core containing special mineral materials that generally obtain higher fire resistance ratings than with regular SHEETROCK wallboard (see table above).

function and utility

Fire Resistance—Constructed of incombustible components, the Ribwall #418 has a fire resistance rating of 2 hours.

Sound Transmission—Ribwall #418 has obtained a 51 sound transmission class rating suitable for party walls. Ribwall #368 has a 43 STC rating suitable for low-cost partitions where sound isolation is secondary.

| test no. | method | decibel frequency in cps | | | | | | | | | | | | STC |
|-----------|--------|--------------------------|-----|-----|-----|-----|-----|------|------|------|------|------|----|-----|
| | | 125 | 175 | 250 | 350 | 500 | 700 | 1000 | 1400 | 2000 | 2800 | 4000 | | |
| TL-63-15 | Lab | 41 | 40 | 42 | 45 | 49 | 50 | 53 | 53 | 51 | 54 | 60 | 51 | |
| TL-62-285 | Lab | 29 | 30 | 36 | 39 | 42 | 42 | 43 | 46 | 42 | 44 | 50 | 43 | |

Lightweight—Space savings and reduced loads are superior for sound and fire ratings obtained. #368 Ribwall—thickness $3\frac{3}{4}$ ", weight 8 psf; #418 Ribwall—thickness $4\frac{1}{8}$ ", weight 12 psf.

Easily Decorated—The systems inherently provide back-blocking; minimize joint ridging. SHEETROCK face panels provide a highly suitable base for any decorative treatment—paint, wallpaper, fabrics or plastic films.

Economical—Utilizes low-cost materials and a minimum number of components.

Versatile—#418 Ribwall is adaptable for use as party walls in virtually every type of new construction or alteration where privacy is important. Has design flexibility for use as vent shafts.

limitations

1. Non-load bearing.
2. Limiting height: 8' for #368 Ribwall; 12' for #418 Ribwall with restraints less than 20', 10' with restraints over 20'.
3. Partition should not be used where exposed to abnormal moisture or excessively high humidity.

USG #158 metal
ceiling runner

adhesive
ribbons

1"x6"
gypsum
rib

SHEETROCK
gypsum
wallboard
face panel

BAXBORD
gypsum
backing
board

USG #158 metal
floor runner


#418 Ribwall

A.I.A. File No. 20-B-21


components




tapered edge SHEETROCK
gypsum wallboard




1" x 6" gypsum rib




USG
metal stud



1 1/8" x 6" gypsum rib



USG metal runner



USG control
joint #093



3/8" USG drywall screw—type S—pan head



3/8" USG drywall screw—type S-12—pan head



1" USG drywall screw—type S—bugle head




2 1/4" USG drywall screw—type S—bugle head




2 1/4" USG drywall screw—type S—trim head



1 1/2" USG drywall screw—type G—bugle head






no. 100 PERF-A-BEAD* reinforcement




DUR-A-BEAD* corner reinforcement




USG metal trim



see "gypsum wallboard & joint
treatment" product catalogs for
full description on accessories



positive & permanent lock




pierces & folds light metal

USG metal lock fastener


details/ #418 Ribwall

scale: 3" = 1'-0"




typical joint detail

ceiling attachment




floor attachment




wood

top set


wall plan sections




wall intersection



partition intersection








partition corner



outlet box



details / #418 Ribwall






details / #418 Ribwall

scale: 3" = 1'-0"


fixture attachment



metal door frames




details / #368 Ribwall




typical joint detail

ceiling attachment




wall plan sections



NOTE: see typ. control joint details—page 4.



floor attachment



partition corner

partition intersection

miscellaneous





specifications

notes to architect

1. Where this partition is used as a sound barrier, the integrity of the partition should not be voided by doors and borrowed lights. Metal door and borrowed light frames if required should be formed from 18-ga. steel minimum, shop primed. The opening between the trim returns should be accurately formed to the overall thickness of the partition.

Floor anchor plates should be 14-ga. steel minimum, designed with two anchor holes to prevent rotation and welded to trim flanges to dampen door impact vibrations. Floor anchorage should be by two power driven anchors or equivalent per plate. Door frames designed for attachment to a floor to ceiling height metal stud acting as a strut-stud adjacent to each jamb are recommended. Jamb anchor clips should be formed of 18-ga. steel minimum, welded in the jamb and head (see detail page 4), and screw attached to the stud.

Door frame struts, when required, should be 1/4" minimum thickness, hot rolled steel bar stock and of sufficient width to completely fill doorstop void, anchoring jamb securely. All door frame struts should be supplied as an integral part of the door frame.

All one-piece metal door and borrowed light frames should be spot grouted at the jamb anchor clips, after the stud and before the wallboard is installed. A grouting of DURABOND or USG Ready-Mixed Joint Compound should be applied just before the face layer is inserted to securely adhere the wallboard to the frame. Under no conditions should the wallboard terminate against the trim return of the door frame.

Door closers and bumpers are required on all doors where the weight of the door (including attached hardware) exceeds 50 lbs.

2. Non-load bearing drywall partitions will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements except the floor by control joints or other means where:

- a. A partition abuts any structural element or dissimilar wall or ceiling assembly.
- b. The partition construction changes within the plane of the partition.

In long partition runs, vertical control joints should be provided at intervals no greater than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

3. Holes cut in a thin wallboard membrane such as door frames, borrowed lights, etc., causes a concentration of stresses in the wallboard typically at intersection of head and jamb. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the opinion of the architect, for reasons of economy or design, a control joint is not specified.

4. **Electrical Fixtures**—The depth of electrical boxes should not exceed 2 7/8". A 25-ga. (min.) galvanized steel plate should be placed behind all electrical boxes for reinforcing. A metal stud adjacent to the electrical box may be desired to provide additional reinforcement.

5. Where additional chases for electrical conduit or pipe are required, they may be provided by using gypsum ribs which terminate no more than 6" from top and bottom edges of face panels.

6. **Ceramic Tile**—The use of SHEETROCK W/R Gypsum Wallboard is recommended to provide a base for the adhesive application of ceramic, metal and plastic tile.

7. Where wood base is required it should be applied with trim head screws placed at each stud location and midway between stud locations (12" o.c.) and at other points where required.

8. The use of a non-hardening caulking material to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure is recommended to improve sound control. Eliminate cutting holes back to back and adjacent to each other.

9. **Fixture attachment**—Metal mounting strips for cabinets or shelving should be screw attached through the first layer of wallboard into supplementary metal studs (see detail). Only lightweight fixtures should be attached to face layer between gypsum ribs using sheet metal screws and 25-ga. (min.) steel plate or strip.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly with the range of 55° to 70° F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Joint Treatment Folder for Joint System Specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. Faceboards—5/8" thick, 48" wide Tapered Edge SHEETROCK (Regular) (FIRECODE), lengths as required.
- b. Base Layer—5/8" thick, 48" wide BAXBORD, 8'.
- c. Gypsum Ribs—1" x 6" USG Gypsum Ribs, snapped and separated from 1" x 24" USG Coreboard prescored 6" o.c. (for #418); 1 1/8" x 6" Gypsum Ribs, factory laminated (for #368).
- d. USG No. 158 (1 1/8")—212 (2 1/2") Metal Runner.
- e. USG No. 158 (1 1/8")—212 (2 1/2") Metal Stud.
- f. Laminating Adhesive—PERF-A-TAPE Joint Compound (embedding type) or USG Laminating Adhesive.
- g. Joint Treatment—PERF-A-TAPE or DURABOND* Joint System.
- h. Fasteners—(specify type from page 2).
- i. USG Metal Trim (specify type from page 2).
- j. USG Corner Bead—DUR-A-BEAD, PERF-A-BEAD* (specify type from page 2).
- k. Caulking—Presstite 579.64 Mastic as manufactured by Presstite Division of Interchemical Corp. or equal.

erection and lamination

All partitions shall be aligned accurately according to the partition layout.

Floor and ceiling runners shall be securely attached to concrete slabs with concrete stub nails or power-driven anchors, to suspended ceilings with toggle or molly bolts, to wood framing with suitable fasteners. Fasteners shall be spaced not to exceed 24" o.c. on ceilings and walls and 16" o.c. on floors.

Metal studs shall be installed vertically at "T" intersections, partition terminals and intersections with structural members or walls. Securely fasten all studs to floor and ceiling runners with the USG Metal Lock Fastener or $\frac{3}{8}$ " USG Drywall Screws Type S, pan head.

Gypsum wallboard panels shall be cut to full floor-to-ceiling height for vertical installation. The ends of the panels shall fit over the runner flanges. Vertical joints between wallboard panels shall occur over gypsum ribs and shall be staggered from the joints in the base layer and from joints on the opposite partition side. Wallboard shall be cut to fit neatly around all outlets and switch boxes. Suitable fastener anchorage shall be provided as required for the attachment of shelves and cabinets. Work done by this contractor shall be coordinated properly with that done by other trades.

Two gypsum ribs shall be laminated to the back of each wallboard panel prior to erection. Space one rib at the centerline of the panel and the other at the edge with one-half the rib attached to the panel. Ribs shall terminate no more than 6" from top and bottom edges of panels. Allow adhesive to set and dry before moving panels.

Erect wallboard panels with ribs attached vertically to both sides of the partition. Securely laminate wallboard to gypsum ribs at vertical joints. In completed assembly gypsum ribs shall be spaced no more than 24" o.c. and staggered on opposite partition sides so ribs are not in contact. Fasten wallboard to floor and ceiling runners and to vertical flanges of all metal studs with 1" USG Drywall Screws Type S spaced 12" o.c. Attach wallboard panels to gypsum ribs at vertical joints with $1\frac{1}{2}$ " USG Drywall Screws Type G. Space screws along vertical joints within 12" of runners, within 2" of joint and 36" o.c. maximum. Space screws in field within 24" of runners and 48" o.c. maximum. Screws in field of base layer on #418 rib-wall may be omitted.

Face panels on #418 ribwall shall be applied vertically and staggered so that vertical joints occur half way between those of the base layer. Laminate face layer to base layer and hold in place with $1\frac{1}{2}$ " USG Drywall Screws Type G spaced as described above.

Vertical panel joints shall be kept at least 6" away from structural members, partition terminals, intersections, corners,

doors and other openings. Partition corners shall contain two metal studs, one in each wall cavity, erected vertically, fastened securely to floor and ceiling runners, and attached to each other through one base and/or one face layer with USG Drywall Screws Type S.

door frames

Floor to ceiling height metal studs shall be inserted into each side of the steel door frame to act as a strut-stud. Attach strut-studs to floor and ceiling runners with the USG Metal Lock Fastener and to each adjacent jamb anchor clip with two $\frac{3}{8}$ " USG Drywall Screws Type S-12, pan head. Over the metal door install a cut-to-length section of runner with flanges slit and web bent to allow flanges to overlap and attach to adjacent strut-studs. A cut-to-length stud extending from the doorhead runner to the ceiling runner shall be centered between strut-studs and securely fastened to runners.

wallboard accessories

a. PERF-A-TAPE or DURABOND Joint System shall be used on all face board joints and internal angles formed by the intersections of walls and ceilings.

b. Laminating Adhesive shall be PERF-A-TAPE Joint Compound (embedding type) mixed according to manufacturer's directions or USG Laminating Adhesive spread to provide adhesive beads $\frac{5}{8}$ " high x $\frac{1}{2}$ " wide at the base and spaced 2" o.c. and 1" away from each edge of the gypsum ribs. For face layer lamination only, adhesive beads shall be $\frac{1}{2}$ " high x $\frac{3}{16}$ " wide at the base and spaced $4\frac{1}{2}$ " o.c.

c. Metal Corner Bead No. () shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.

d. Metal Trim No. () shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.

e. Fasteners shall be as shown on drawings or as herein specified. Fasteners shall be driven not less than $\frac{3}{8}$ " from ends or edges of wallboard to provide uniform dimple not over $\frac{1}{32}$ " deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

f. Control Joints shall be provided in the face layer as indicated and where detailed. Staple in place.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products, adhesives); SHEETROCK, FIRECODE (gypsum wallboard); PERF-A-TAPE, DURABOND (joint treatment); DUR-A-BEAD, PERF-A-BEAD, PERF-A-TRIM (corner reinforcement); BAXBORD (gypsum backing board); THERMAFIBER (insulation products).

a-1067

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Catalog
for
Sales
Offices

partitions

a

USG® Double & Triple Solid Gypsum Drywall

1077

A.I.A. File No. 20-B-21

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|---|------------|------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | Double Solid Drywall—½" SHEETROCK gypsum wallbd—two rows of 1" USG gypsum corebd spaced 1½" apart—wallbd lamin & screw att ea face—joints fin—perimeter caulked wt 13 width 4¾" | T-1310-OSU (f) USG-13-FT-G&H (s) | 46 | | 150 | Excellent, versatile—best value in 45-49 stc range | a-1077 |
| 2 hrs. | Double Solid Drywall—½" SHEETROCK gypsum wallbd lamin ea face to two rows of 1" USG gypsum corebd spaced 3" apart—1½" THERMAFIBER sound atten blkts stapled to back of one row—stl runners—joints fin—perimeter caulked wt 13 width 6" | UL Des 26-2 hr USG-96-FT-G&H (f) (s) Field Test KSO-109006-c (s) | 60 56 | 55 | 165 | Fire rating also applies without wool. Outstanding sound isolation at low cost | a-1077 |
| 2 hrs. est | Triple Solid Drywall—½" SHEETROCK gypsum wallbd—3 rows of 1" USG gypsum corebd ea spaced min 1½" & 1½" apart—1½" THERMAFIBER sound atten blkts att to back of one outer row—wallbd lamin & screw att to outer rows—joints fin—perimeter caulked wt 17 width 6¾" | USG-94-FT-G&H (s) | 59 | | 210 | Septum improves resistance against sound leaks on job | a-1077 |
| 2 hrs. est | Triple Solid Drywall—½" SHEETROCK gypsum wallbd—3 rows of 1" USG gypsum corebd ea spaced 1½" apart—wallbd lamin & screw att to outer rows—joints fin—perimeter caulked wt 18 width 6¾" | USG-95-FT-G&H (s) | 53 | | 195 | Among best lamin. drywall party walls in 50-54 stc range | a-1077 |

description

In these non-load bearing partition assemblies SHEETROCK® Gypsum Wallboard face layers are job-laminated to the outer sides of parallel rows of USG Gypsum Coreboard, spaced a specified distance apart. The coreboard, a 1" thick fireproof gypsum core encased in strong gray liner paper on both sides, is 24" wide and mill-fabricated to standard lengths. Integrally formed "V" T&G edges facilitate accurate alignment of the coreboard with metal angle floor and ceiling runners.

Double Solid: two parallel rows of coreboard spaced 1½" apart with ½" thick x 4' wide SHEETROCK face layers both sides are recommended for party walls where a 46 sound transmission class is needed. For a 56 to 60 STC, coreboards are spaced 3" apart and 1½" THERMAFIBER® Sound Attenuation Blankets are attached to the back side of one coreboard row. These partitions are used where greater core widths are needed for plumbing enclosures and other mechanical installations, and where fire resistance ratings up to 2 hours are desired.

Triple Solid: three separate rows of USG Coreboard are spaced a minimum of 1½" apart with ½" thick x 4' wide SHEETROCK face layers laminated to outer coreboard rows. The center coreboard row serves as a "septum" or uncut barrier to prevent sound from leaking through openings cut in the partition faces for electrical or plumbing fixtures, medicine cabinets, etc. Electrical conduit and boxes may be installed in the space on either side of the septum. By increasing the space between the coreboard rows, greater core widths may be obtained for light mechanical equipment without destroying the outstanding sound control properties of this assembly.

The partitions are completed with the PERF-A-TAPE® Joint System and DUR-A-BEAD® Corner Reinforcement. A resilient non-hardening caulking compound is used between the metal floor and ceiling runners and the basic construction and around the perimeter of the partition.

function and utility

Fire Resistance—2-hour fire-resistance classifications have been obtained for Double Solid Partitions and based on this, are estimated for Triple Solid Partitions.

Sound Control—These partitions afford excellent resistance to sound transmission. Job tests confirm the superiority of these systems over traditional masonry or resilient clip systems in providing efficient sound control on the job (see page 2 for specific sound transmission values).

Versatility—Adaptable for use as a dividing partition between units in apartments, office buildings, schools, motels,

dormitories or any type of building construction where excellent sound control and pipe chase enclosures are design requirements. Component materials readily adapt to building modules or dimensions.

Light Weight—The completed partitions weigh appreciably less than masonry walls with comparable sound resistance.

Economy—Low cost, simple components; easy installation; and the ease and flexibility in providing for electrical and light mechanical installations result in extremely favorable cost factors for this high degree of sound control. The weight of this partition may provide savings in structural framing.


limitations

1. Non-load bearing.
2. Allowable maximum height:


| width between restraint | max. ceiling height |
|-------------------------|---------------------|
| Up to 10' | 10' |
| 10' to 14' | 9' |
| Over 14' | 8' |

3. Walls must not be flexed before adhesive dries in order to prevent bond failure.

4. Partition should not be used where exposed to abnormal moisture or excessively high humidity or temperature.




double solid




triple solid

components


see "gypsum wallboard and joint treatment" product catalogs for full description on accessories & sizes





tapered edge SHEETROCK
gypsum wallboard



1" "V" edged
T & G coreboard





no. 100 PERF-A-BEAD * reinforcement




1 3/8" x 7/8" —22 ga. metal angle runner




DUR-A-BEAD corner reinforcement



USG control
joint #093



USG metal trim



1 1/4" USG drywall screw—type S—bugle head



2 1/4" USG drywall screw—type S—trim head



1 1/2" USG drywall screw—type G—bugle head



1 5/8" USG drywall screw—type S—bugle head

sound transmission loss



| test no. | method | decibel frequency in cps | | | | | | | | | | | | | | | | | | | | STC | |
|---------------|--------|--------------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|------|------|------|------|------|------|------|-----|------|
| | | 125 | 160 | 175 | 200 | 250 | 315 | 350 | 400 | 500 | 630 | 700 | 800 | 1000 | 1250 | 1400 | 1600 | 2000 | 2500 | 2800 | 3150 | | 4000 |
| USG-13-FT-G&H | Lab | 30 | — | 30 | — | 35 | — | 40 | — | 43 | — | 48 | — | 49 | — | 50 | — | 50 | — | 57 | — | 56 | 46 |
| KSO-109006-C | Field | 34 | — | 42 | — | 46 | — | 50 | — | 52 | — | 55 | — | 60 | — | 61 | — | 63 | — | 63 | — | 70 | 56 |
| | | 34 | 41 | — | 44 | 46 | 47 | — | 49 | 52 | 54 | — | 55 | 60 | 61 | — | 63 | 63 | 63 | — | 67 | 70 | 55† |
| USG-96-FT-G&H | Lab | 41 | — | 46 | — | 52 | — | 54 | — | 56 | — | 58 | — | 60 | — | 62 | — | 61 | — | 65 | — | 66 | 60 |
| USG-94-FT-G&H | Lab | 39 | — | 43 | — | 53 | — | 53 | — | 58 | — | 58 | — | 62 | — | 65 | — | 62 | — | 66 | — | 66 | 59 |
| USG-95-FT-G&H | Lab | 34 | — | 35 | — | 43 | — | 49 | — | 54 | — | 56 | — | 60 | — | 61 | — | 61 | — | 66 | — | 66 | 53 |

†STC based on 16 frequencies.



details/double solid

scale: 3" = 1'-0"



ceiling attachments



floor attachments & bases




intersecting walls



details/double solid


scale: 3" = 1'-0"

intersecting walls




partition wall intersection


PERF-A-TAPE
corner
reinforcement




double solid & 2" solid




wall control joint



perimeter relief
ceiling intersection




perimeter relief
wall intersection




partition relief
column intersection

metal door frame




jamb

floor anchor clips
secured with no
less than two
suitable fasteners





elevation
cross section thru frame



jamb anchor clip



details/double solid

ceiling attachment






partition intersection

floor attachment



partition wall intersection


fixture attachments—double & triple solid




details/triple solid

scale: 3" = 1'-0"


ceiling attachment




floor attachment



intersecting walls



partition intersection



specifications—notes to architect

1. Where these partitions are used as a sound barrier, the integrity of the partition should not be voided by doors and borrowed lights. Metal door and borrowed light frames if required should be formed from 18-ga. steel minimum, shop primed. The opening between the trim returns should be accurately formed to the overall thickness of the partition.

Floor anchor plates should be 14-ga. steel minimum, designed with two anchor holes to prevent rotation and welded to trim flanges to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate. Jamb anchor clips should be formed of 18-ga. steel minimum, and welded in the jamb and head. (See details page 4.)

Door frame struts should be 1" x 1/4" hot rolled steel bar stock and should extend from a minimum of 16" below head of frame in each jamb to the ceiling.

All one-piece metal door and borrowed light frames should be spot grouted at the jamb anchor clips, after the coreboard is installed. A grouting of DURABOND or USG Ready-Mixed Joint Compound should be applied just before the face layer is inserted to securely adhere the wallboard to the frame. Under no conditions should the wallboard terminate against the trim return of the door frame.

Door closers and bumpers are required on all doors where the weight of the door (including attached hardware) exceeds 50 lbs.

2. Non-load bearing drywall partitions will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements except the floor by control joints or other means where:

- A partition abuts any structural element or dissimilar wall or ceiling assembly.
- The partition construction changes within the plane of the partition.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

3. Holes cut in a thin wallboard membrane such as door frames, borrowed lights, etc., cause a concentration of stresses in the wallboard typically at intersection of head and jamb. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.



4. Electrical Fixtures—*The depth of electrical boxes should not exceed 2½".*

5. Ceramic Tile—*SHEETROCK W/R Gypsum Wallboard is recommended as a base for the adhesive application of ceramic, metal and plastic tile.*

6. *Where these partitions are used as a sound barrier, the use of caulking to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure is recommended. Eliminate cutting holes back to back and adjacent to each other. The integrity of the triple solid septum should not be destroyed by cutting holes.*

7. Fixture Attachment—*Lightweight fixtures and trim should be installed using plastic plugs or other expandable anchors for screw attachment. Medium and heavy weight fixtures should be supported by elevator bolts with ¾" (min.) head diameter or bolts welded to nested 1½" channels. Care should be taken so fixture attachments do not contact septum sound barrier.*

8. *The excellent sound attenuation of these partitions is due to the resilient effect of the gypsum diaphragms. Although the system is structurally adequate, it should not be expected to provide the same degree of rigidity as a metal or wood-framed partition with wallboard directly attached to both stud faces.*

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 70°F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Joint Treatment Folder for PERF-A-TAPE Joint System Specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. Coreboard—1" thick, 24" wide, USG "V" T&G edge Gypsum Coreboard, lengths as required.
- b. Faceboards—(½") (⅝") thick, 48" wide, Tapered Edge SHEETROCK Wallboard lengths as required.

c. Laminating Adhesive—PERF-A-TAPE Joint Compound (embedding type) or USG Laminating Adhesive.

d. Joint Treatment—PERF-A-TAPE or DURABOND* Joint System.

e. Fasteners—(specify type from page 2).

f. USG Metal Trim (specify type from page 2).

g. USG Corner Bead—DUR-A-BEAD, PERF-A-BEAD* (specify type from page 2).

h. Metal Angle Runners—1½" x ⅞" x 22 ga.

i. Insulation—1½" THERMAFIBER Sound Attenuation Blankets, 24" x 48".

j. Caulking—Presstite 579.64 Mastic as manufactured by Presstite Division Interchemical Corporation or equal.

erection—double solid partition

All partitions shall be aligned accurately according to the partition layout.

Floor and ceiling runners shall be shaped as detailed in the drawings, spaced to provide a minimum of (1½") (3") space between 1" coreboards and securely attached to floor and ceiling constructions with suitable fasteners spaced 24" o.c.

Cut coreboard to fit accurately between floor and ceiling runners and install vertically with tongue edge leading.

Begin installing coreboard at the door frame by engaging the vertical edge in the jamb anchor clips in each jamb. Place cut-to-fit coreboard over metal frame header by engaging bottom edge in anchor clips and attaching to ceiling runners with 1¼" USG Drywall Screws—Type S placed 3" in from each edge. Erect succeeding panels by fastening coreboard to vertical flanges of both floor and ceiling runners with 1¼" USG Drywall Screws—Type S placed 3" in from each edge.

At partition intersections, coreboards shall be nailed together with 10d nails spaced 24" o.c. Panels shall be inserted in jamb anchor clips at all door frames, borrowed light frames and partition terminals and spot grouted at the clip locations.

Face boards shall be cut to ½" less than floor-to-ceiling height. Apply laminating adhesive and laminate in place to coreboards using moderate pressure to insure adequate bond. Install face boards with ¼" space at top and bottom and at vertical intersections with terminal walls. Caulk ¼" gap around entire perimeter. Offset face panel joints at least 3" from coreboard joints. Screw face layer to coreboard with USG 1½" Type G Screws. Screws along vertical edges shall occur 36" o.c. maximum, within 2" of joint and 12" of both ends. Screws in field shall occur 48" o.c. maximum and within 24" of both ends.

Coreboards and face boards shall be cut neatly to fit around all outlets and switch boxes and caulking used to seal all cut-outs. Caulking shall be applied around all electrical boxes. Suitable fastener anchorage shall be provided as required for the attachment of shelves and cabinets.

Work done by this contractor shall be coordinated properly with that to be done by other trades.

erection—triple solid partition

All partitions shall be aligned accurately according to the partition layout.

Floor and ceiling runners shall be $1\frac{3}{8}$ "x $7\frac{7}{8}$ "x22 ga. metal angles, spaced to provide a minimum of $1\frac{1}{8}$ " space between 1" coreboards, caulked prior to attachment to basic construction with a resilient non-hardening caulking compound and securely attached to floor and ceiling constructions with suitable fasteners spaced 24" o.c.

Cut coreboard to fit accurately between floor and ceiling runners and install vertically with tongue edge leading. Fasten coreboard to vertical flanges of both floor and ceiling runners with $1\frac{1}{4}$ " USG Drywall Screws Type S placed 3" in from each edge.

Coreboard in septum row shall have tongue facing in opposite direction from tongues in outer coreboard rows with vertical joints staggered from joints in outer coreboard rows.

At partition intersections, coreboards shall be nailed together with 10d nails spaced 24" o.c.

Face boards shall be cut to $\frac{1}{2}$ " less than full floor-to-ceiling height. Apply laminating adhesive and laminate in place to coreboards using moderate pressure to insure adequate bond. Install face boards with $\frac{1}{4}$ " space at top and bottom and at vertical intersections with terminal walls. Caulk $\frac{1}{4}$ " gap around entire perimeter. Offset face panel joints at least 3" from coreboard joints. Screw face layer to coreboard with USG $1\frac{1}{2}$ " Type G Screws. Screws along vertical edges shall occur 36" o.c. maximum, within 2" of joint and 12" of both ends. Screws in field shall occur 48" o.c. maximum and within 24" of both ends.

Coreboards and face boards shall be cut neatly to fit around all outlets and switch boxes. Provide suitable fastener anchorage for the attachment of shelves and cabinets.

Caulk septum core at vertical intersections with terminal walls and around the perimeter of all face layers, outlets, switch boxes, pipes, plumbing fixtures and other holes cut in the face layers with a resilient non-hardening caulking compound.

Work done by this contractor shall be coordinated properly with that to be done by other trades.

wallboard accessories

a. **PERF-A-TAPE or DURABOND Joint System** shall be used on all face board joints and internal angles formed by the intersections of walls and ceilings.

b. **Laminating Adhesive** shall be PERF-A-TAPE Joint Compound (embedding type) mixed according to manufacturer's directions or USG Laminating Adhesive applied in strips, 2' o.c., running continuously from floor to ceiling. Each strip shall consist of four beads $\frac{1}{2}$ " high and $\frac{3}{8}$ " wide at the base and spaced $1\frac{1}{2}$ " to 2" o.c.

c. **Metal Corner Bead No. ()** shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.

d. **Metal Trim No. ()** shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.

e. **Fasteners** shall be as shown on drawings or as herein specified. Fasteners shall be driven not less than $\frac{3}{8}$ " from ends or edges of wallboard to provide uniform dimple not over $\frac{1}{32}$ " deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

f. **Control Joints** shall be provided in the face layer as indicated and where detailed. Staple in place.

TRADEMARKS: The following trademarks are owned and/or registered in the U. S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products, gypsum coreboard, adhesives); SHEETROCK, FIRECODE (gypsum wallboard); PERF-A-TAPE, DURABOND (joint treatment); DUR-A-BEAD, PERF-A-BEAD, PERF-A-TRIM (corner reinforcement); THERMAFIBER (insulation products).

a-1077

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Director
for
Sales
Officers

partitions

a

steel studs or solid gypsum

IMPERIAL* Plaster Systems
HIGH-STRENGTH VENEER

1147

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|---|----------------------|------------------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | Met Stud—2 layers 5/8" IMPERIAL plaster base Type X & thin coat plaster—3/8" USG met studs 24" o.c.—base layer screw att—face layer lamin—joints taped—1/16" IMPERIAL plaster wt 12 width 6 3/8" | UL Des 11-2 hr (f) TL-63-177 (s) | 50 | | 174 | Excellent for corridors; sound performance based on perimeter caulking | a-1147 |
| 2 hrs. | Met Stud—2 layers 1/2" IMPERIAL plaster base & thin coat plaster—2 1/2" USG met studs 24" o.c.—run track gasketed & caulked—base layer screw att—face layer strip lamin 24" o.c. & att with Type G screws betw studs—2" THERMAFIBER sound atten bkts att one side—1/16" IMPERIAL plaster—perimeter caulked wt 10 width 4 3/4" | UL Des 27-2 hr (f) CK 654-66 (s) USG-127-FT-G&H (s) Field Test KSO-1090072-a (s) | 52 48 | 53 49 | 183 | CK 654-66 based on 2 layers Type X base screw-attached and 1" THERMAFIBER blankets; fire test same construction without wool | a-1147 |
| 2 hrs. est | Solid Gypsum—3/8" IMPERIAL plaster base & thin coat plaster—pl base lamin ea face to 1" USG gypsum corebd—met angle runners at flr & clg—joints stag & taped—1/16" IMPERIAL plaster wt 10 width 2 1/2" | TL-63-208 (s) | 34 | | 135 | | a-1147 |
| 2 hrs. est | Double Solid Gypsum—1/2" IMPERIAL plaster base & thin coat plaster—pl base strip lamin & att with Type G screws to 1" USG gypsum corebd—met angle runners at flr & clg 3" apart—2" THERMAFIBER sound atten bkts stapled to corebd one side—1/16" IMPERIAL plaster—joints taped—perimeter caulked wt 13 width 6 3/8" | Field Test KSO-1090072-d (s) | 54 | 54 | 178 | | a-1147 |
| 1 hr. est | Met Stud—1/2" IMPERIAL plaster base Type X & thin coat plaster—3/8" USG met studs 24" o.c.—2 layers pl base one side & single layer opp side both appl vert & screw att—1" THERMAFIBER sound atten bkts stapled to single layer—joints stag & taped—1/16" IMPERIAL plaster—perimeter caulked wt 8 width 5 1/4" | CK-664-2 (s) | | 51 | 159 | | a-1147 |
| 1 hr. | Met Stud—1 layer 1/2" IMPERIAL plaster base Type X & thin coat plaster—3/8" USG met studs 24" o.c.—pl base screw att—1" THERMAFIBER sound atten bkts stapled one side—joints stag & taped—1/16" IMPERIAL plaster—perimeter caulked wt 8 width 4 3/4" | T-3124-OSU (f) CK-664-1 (s) | | 45 | 134 | Fire test based on assembly with 2 1/2" studs, without wool. Stud spacing at 16" o.c. recommended | a-1147 |

ceiling application

| | | | | | | | |
|--------|--|---------------------|--|-----|--------------|--|--------|
| 2 hrs. | $\frac{1}{2}$ " IMPERIAL gypsum pl base Type X & thin coat plaster ceiling—USG met fur chan 24" o.c.—pl base att with screws 12" o.c.—joints taped— $\frac{1}{16}$ " IMPERIAL plaster clg wt 4 | UL Des 221-2 hr (f) | | N/A | clg matls 55 | Spacing of furring channel at 16" o.c. recommended | a-1147 |
|--------|--|---------------------|--|-----|--------------|--|--------|

For wall furring application, see page 4.

description

In the IMPERIAL Plaster Systems a thin veneer ($\frac{1}{16}$ " to $\frac{3}{32}$ " thick) of specially formulated, high-strength gypsum plaster is applied over IMPERIAL Plaster Base. Either IMPERIAL Plaster Finish is applied in a single-coat system, or IMPERIAL Plaster Basecoat is used in a two-coat application as a superior base for DIAMOND* Finish, STRUCTO-GAUGE* Gauging Plaster and lime, or Keene's-lime-sand-float finish.

IMPERIAL Plaster Base, 4' wide, has a high-strength, high-density core, either regular or Type X fire-rated, covered with special absorption face paper designed for thin-coat plastering. Versatile IMPERIAL Base, as outlined below, is used with metal or wood studs, metal furring channels or in laminated gypsum construction to meet design requirements for interior partitions, party walls, chase wall, furring and column fireproofing.

1. **USG® Metal Studs**, available in 4 widths (see Specifications, page 6), set in metal runners, with 1-layer, $\frac{1}{2}$ " thick IMPERIAL Base, Type X core, screw-attached to $2\frac{1}{2}$ " studs 16" o.c., this partition has a 1-hour fire rating and suited for interior partitions and corridor walls. With double layer $\frac{1}{2}$ " IMPERIAL Base, Type X, attached by means of Type S screws to $2\frac{1}{2}$ " studs spaced 16" o.c., a 2-hour fire rating plus sound control suitable for party walls is available. Where added partition width is required, double rows of USG No. 158 studs, 24" o.c. are erected to provide chase walls with up to $11\frac{3}{4}$ " net pipe chase width (see page 4).


2. **Metal Furring Channel**—With Insulating (foil-back) IMPERIAL Plaster Base screwed to USG Furring Channels erected 16" o.c. direct to masonry or furred with brackets and $\frac{3}{4}$ " channels, this construction provides an excellent vapor

barrier and offers significant insulating value as exterior wall furring (see details, page 4).

3. **Laminated Gypsum**—Economical, space saving, 2-hour (estimated) $2\frac{1}{2}$ " solid partitions, suitable for interior dividers, are built with $\frac{5}{8}$ " IMPERIAL Type X Base job-laminated to both sides of 1" USG Coreboard secured in metal angle runners.


With $\frac{1}{2}$ " IMPERIAL Plaster Base job-laminated to the outside of two coreboard rows, set in angle runners spaced $1\frac{1}{8}$ " apart, a double solid partition offers estimated 2-hour fire resistance.

(continued on page 6)



components/details

scale: 3" = 1'-0"



$\frac{1}{2}$ " or $\frac{5}{8}$ "

IMPERIAL plaster base USG coreboard

see "plaster bases" product catalog for full description on accessories & sizes



$\frac{3}{8}$ " USG screw—type S—pan head



$\frac{3}{8}$ " USG screw—type S-12—pan head




1" USG screw—type S—bugle head



$1\frac{5}{16}$ " USG screw—type S—bugle head




$1\frac{5}{8}$ " USG screw—type S—bugle head




$2\frac{1}{4}$ " USG screw—type S—trim head




$1\frac{1}{2}$ " USG screw—type G—bugle head




USG metal stud




IMPERIAL joint reinforcement tape




USG metal runner




$\frac{7}{8}$ " x $1\frac{3}{8}$ " 22-ga. metal angle runner




USG metal furring channel



USG control joint #093




USG metal base & splice plate




USG cold rolled channel

metal stud partitions

ceiling attachment



floor attachment



top set

metal




800 series corner bead



700 series metal trim



wall plan sections





partition corner


intersection

details

door frames



wall plan sections



details

chase walls


Chase walls, as vertical shafts encasing the usual plumbing supply and wastelines, vent ducts and electrical conduits, require more free space than can be provided within the usual partition assembly.

The Metal Stud chase wall may be formed of two USG Studs bracketed together with 12"x12" gussets of 1/2" or 5/8" IMPERIAL plaster base (see detail). Gussets should be spaced not to exceed 36" o.c. and securely attached to USG Studs using three 1" Type S Screws. Limiting height for this chase wall is 10'.

wall furring



Exterior walls are readily furred using IMPERIAL Plaster Base screw-attached to USG Metal Furring Channels erected vertically 16" o.c. Channels are either fastened directly to masonry or furred using USG Adjustable Wall Furring Brackets and 3/4" channels to provide additional space for pipes, conduits or ducts (see details below).

IMPERIAL Plaster Base and Plaster may also be laminated to rigid polystyrene foam insulation applied directly to the interior of masonry, precast or monolithic concrete exterior walls (see USG Bulletin PM-103 for detailed information).




chase wall

ceiling attachment




elevation—vertical application




metal window jamb


floor attachment



metal



top set




metal window jamb

details


scale: 3" = 1'-0"

2 1/4" solid partitions

ceiling attachment




floor attachment




double solid partitions


ceiling attachment







floor attachment



wall plan sections



wall plan sections



description (continued from page 1)

Coreboards with greater separation offer enclosures for plumbing and mechanical installation. Stapling 1½" THERMAFIBER* Sound Attenuation Blankets to back of one coreboard row gives outstanding sound isolation (Field Test STC 54) for party walls (see table, page 1).

4. **Wood Studs**—IMPERIAL Base may be nail or screw-attached to wood studs where 1-hour fire protection is needed. For details refer to USG Systems Folder, IMPERIAL Plaster and Wood Framing.

5. **PYROBAR Partition Tile**—With IMPERIAL Base and Plaster applied, 4-hour column fire protection is available (see separate Systems Folder).

function and utility

IMPERIAL Plaster Systems are designed for interior partitions, exterior wall furring or wherever conventional plaster or dry-wall systems are used. Perfectly integrated components provide beautiful, hard surfaces ready for next-day decoration.

Durability—The high-strength, abrasion- and crack-resistant features of IMPERIAL Plaster offer the durability needed in high traffic areas, and obtainable with few other materials.

Fire Resistance—Incombustible components provide systems with fire-resistance ratings up to 2 hours (see table, page 1).

Sound Control—The systems offer sound isolation up to 54 STC; ideal for party walls.

Versatility—Adaptable to most dimensions or modules in virtually all types of buildings, these systems meet all normal design and job conditions.

Light Weight—The completed systems weigh appreciably less than masonry partitions of the same thickness.

Economy—Simple, inexpensive components erect quickly at a lower cost than conventional plaster systems. Finish is rapidly applied by machine or hand application.

limitations

(1) Non-load bearing. (2) This assembly should not be used where exposed to abnormal moisture or excessive high humidity or temperature. (3) Allowable maximum stud spacing with single layer plaster base: 16" o.c. (4) Allowable maximum height:

| partition description | limiting height |
|------------------------|-----------------|
| USG metal studs 1½" | 8'-6" |
| 2½" | 11'-0" |
| 3½" | 14'-6" |
| 4" | 15'-0" |
| chase walls | 10'-0" |
| 2¼" solid† | 10'-0" |
| double solid | 8'-0" |
| exterior wall furring‡ | 12'-0" |

†Using ½" IMPERIAL Base face layers.

‡Using Adjustable Wall Furring Bracket.

specifications

notes to architect

1. Metal door and borrowed light frames should be formed from 16-ga. steel minimum, shop primed. The opening between the trim returns should be accurately formed to the overall thickness of the partition.

Floor anchor plates should be 14-ga. steel minimum, designed with two anchor holes to prevent rotation and welded to trim flanges to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate.

Jamb anchor and core centering clips should be formed of 18-ga. steel min., and welded in the jamb and head (see details). Jamb anchor clips are screw-attached to USG metal studs.

Door frame struts, when required, should be 1" x ¼" hot rolled

bar stock and should extend from a minimum of 16" below head of frame in each jamb to the ceiling. Where struts are not used, temporary bracing should be used to level and plumb frame until partition is erected.

Grouting of the door frame is recommended on all installations and is required where heavy or oversize doors are used. The grout should be raked out to allow the lath and plaster to be inserted into the frame. Under no conditions should the lath and plaster terminate against the trim return of the door frame.

Door closers and bumpers are required on all doors where the weight of the door (including attached hardware) exceeds 50 lbs.

2. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements, except the floor, by control joints or other means where:

- a partition abuts a structural element or dissimilar wall or ceiling assembly.
- the partition construction changes within the plane of the partition.

In long partition runs, control joints should be provided at no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

3. Holes cut in a thin diaphragm of lath and plaster, such as door frames, borrowed lights, etc., cause a concentration of stresses in the plaster diaphragm. The use of additional reinforcement is recommended at the weakened area to distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

4. Additional chases for electrical conduit or pipe can be provided in Metal Stud partitions by cutting round holes no greater in size than 75% of the stud width, located in the center of the stud web and spaced at least 12" apart. Additional holes should not be cut where a fire rating is required.

5. **Electrical Fixtures**—The depth of electrical boxes should not exceed 1½" for the 2¼" Solid Partition and 2½" for the Double Solid Partition when 1⅛" minimum air space is specified.

6. **Fixture Attachment**—Lightweight fixtures and trim should be installed by drilling and inserting a plastic plug or other expandable anchor for anchorage of attachment screws. Wood or metal mounting strips for cabinets and shelving should be toggle bolted through the lath and plaster, locating fasteners as near the studs as possible.

7. **Ceramic Tile**—IMPERIAL Plaster Base is not recommended as a base for the adhesive application of ceramic, metal and plastic tile unless the edges are protected from wetting and the entire surface is sealed with adhesive or other material recommended by the tile manufacturer. SHEETROCK* W/R Gypsum Wallboard is recommended for this use (see USG Product Folder in this series on Gypsum Wallboard).

8. Where these partitions are used as a sound barrier, the use of non-hardening caulking material to seal all cut-outs, such as at electrical fixtures, and to seal all intersections with the adjoining structure is recommended. Eliminate cutting holes back to back and adjacent to each other; block flanking paths at all intersections. Door and borrowed light openings are not recommended when these partitions are used as a party wall.

9. Proper sealing of IMPERIAL Plaster surfaces before painting is essential (see USG Paint Products Folder, Specifications). The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather, the building shall be maintained above 55° F. for an adequate period prior to, during, and after installation of systems including the application of IMPERIAL Plaster. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements. IMPERIAL Plaster Base shall be protected from contamination or overspray of materials containing lime or casein additives.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. IMPERIAL Plaster Base—($\frac{1}{2}$ " ($\frac{5}{8}$ ") thick, 48" wide, square edge, (Regular) (Insulating) (Type X), lengths as required.
- b. Coreboard—1" thick, 24" wide, USG "V" T&G edge Gypsum Coreboard, lengths as required.
- c. Laminating Adhesive—USG Laminating Adhesive mixed in accordance with manufacturer's directions.
- d. Fasteners— $\frac{3}{8}$ ", 1", 1 $\frac{1}{4}$ ", 1 $\frac{5}{16}$ " and 1 $\frac{3}{8}$ " USG Screw Type S; 1 $\frac{1}{2}$ " USG Screw Type G.
- e. USG Metal Studs—(1 $\frac{5}{8}$ " (2 $\frac{1}{2}$ ") (3 $\frac{5}{8}$ " (4")), lengths as required.
- f. USG Metal Runner—(1 $\frac{5}{8}$ " (2 $\frac{1}{2}$ ") (3 $\frac{5}{8}$ " (4")) for USG Metal Studs.
- g. USG Metal Angle Runner.
- h. USG Metal Furring Channel.
- i. IMPERIAL Tape—for joint reinforcement.
- j. USG $\frac{3}{4}$ " Cold Rolled Channels.
- k. USG Adjustable Wall Furring Bracket.
- l. Accessories—(800-A) (800-B) Corner Bead, (700-A) (700-B) Metal Trim, USG Control Joint #093.

metal stud partition system

stud system erection

Metal Runners shall be aligned accurately at floor and ceiling according to partition layouts and secured with suitable fasteners to the structural elements at a spacing not to exceed 24" o.c., or secured to suspended ceilings at a maximum spacing of 16" o.c.

Studs shall be positioned vertically engaging both floor and ceiling runners and spaced no greater than 16" o.c. All studs located adjacent to door and window frames, partition intersections, and corners shall be anchored to the ceiling and floor runner flanges by positive screw engagement with $\frac{3}{8}$ " Type S pan head screws or by locking the studs with the USG Metal Lock Fasteners. When necessary, studs shall be spliced with a minimum 8" nested lap with one positive attachment per stud flange.

Studs shall be placed in direct contact with all door frame jambs, abutting partitions, partition corners and existing construction elements. Where a stud is installed directly to exterior walls and there is a possibility of water penetration through the walls, an asphalt felt protection strip shall be installed between the stud and the wall surface. Studs shall be

securely anchored to the jamb and head anchor clips of each door or borrowed light frame by bolt or screw attachment (not required for frames with structural bar struts). Over metal door and borrowed light frames a cut-to-length section of runner track with a web-flange bend at each end shall be placed horizontally and securely fastened with one positive attachment per flange. A cut-to-length stud (extending to the ceiling runner) shall be positioned at the location of vertical joints over the door frame header.

panel erection—single layer

IMPERIAL Plaster Base shall be applied face out with long dimension (parallel—*preferred*) (at right angles) to framing members. All abutting ends and edges shall occur over stud flanges. IMPERIAL Plaster Base of maximum practical length shall be used to minimize end joints. Joints on opposite sides of a partition shall be so arranged as to occur on different studs. For vertical application of base, screws shall be spaced a maximum of 12" o.c. in the field of the base and 8" o.c. staggered along the vertical abutting edges. For horizontal base application, screws shall be spaced a maximum of 12" o.c. in the field of the base and 12" o.c. along the abutting end joints.

panel erection—double layer

For screw attachment, 1" screws spaced 16" o.c. for the first layer and 1 $\frac{5}{16}$ " screws spaced 16" o.c. for the second layer shall be used. In both cases the plaster base shall be applied vertically with the joints in the face layer offset from the inner plaster base layer.

In double layer laminated construction, inner plaster base layers shall be attached with 1" USG Screws Type S spaced 8" o.c. at joint edges and 12" o.c. in the field. Second plaster base layers shall be applied vertically with USG Laminating Adhesive spread on the back side, joints staggered approximately 12" and fastened to first layer with 1 $\frac{1}{2}$ " USG Screw Type G. Screws shall be driven approximately 2' from ends and 4' o.c. in field of panel; 1' from ends and 3' o.c. along vertical edges aligned approximately 3" from the edges.

chase wall erection

Chase wall partitions shall be aligned accurately according to the partition layout. A double row of floor and ceiling runners shall be securely attached 24" o.c. to concrete slabs with concrete stud nails or power-driven anchors, to suspended ceilings with toggle bolts or staples, or to wood framing with suitable fasteners.

A double row of USG No. 158 metal studs shall be positioned vertically in the runners so that studs are opposite each other in pairs with the flanges pointing in the same direction, spaced no greater than 24" o.c. All studs located adjacent to door and window frames, partition intersections and corners shall be anchored to runner flanges with USG Metal Lock Fastener or by positive screw engagement through each stud flange and runner flange.

Cross bracing between the rows of studs shall be cut from ($\frac{1}{2}$ " ($\frac{5}{8}$ ") IMPERIAL Plaster Base into minimum 12" by chase width pieces and screw-attached to the stud webs at quarter points in the partition height, with USG Screws Type S—spaced 8" o.c. in each stud web or a minimum of three screws per stud web. Single face layer or base layer ($\frac{1}{2}$ " ($\frac{5}{8}$ ") IMPERIAL Plaster Base shall be applied vertically. USG 1" Type S Screws shall be spaced 12" o.c. in the field of the board and 8" o.c. staggered at the vertical joints.

wall furring—direct attachment of channels

Metal Furring Channels shall be attached vertically to masonry or concrete surfaces spaced not more than 16" o.c.; each channel fastened with hammer-set or power-activated stud fasteners or concrete stud nails spaced 24" o.c. on alternate wing flanges (staggered). Whenever the furring channel is installed directly to an exterior wall and there is a possibility

of water penetration through the walls, an asphalt felt protection strip shall be installed between the furring channel and the wall surface.

wall furring bracket attachment of channels

USG Adjustable Wall Furring Brackets, with serrated edges up, shall be attached to the masonry walls not over 4" from columns or other abutting construction and not over 36" o.c. horizontally; not over 6" from floor and ceiling, not over 48" vertically and as required above and below windows. (One 2" cut nail in mortar joints of brick or clay tile or cement block, or in the field of lightweight aggregate blocks) (5/8" concrete stub nails or power-driven nails or other suitable fasteners in monolithic concrete) shall be fastened through the top hole of the brackets. 3/4" cold rolled channels shall be laid horizontally on the furring brackets with the legs down, plumbed vertically from ceiling to floor and wire tied to the bracket with a double strand of 16 ga. or triple strand of 18 ga. tie wire; excess bracket length bent down.

The Metal Furring Channel, spaced 24" o.c. maximum, shall be erected vertically and wire tied with a double strand of 16 ga. or triple strand of 18 ga. galvanized tie wire at the junction of each 3/4" channel.

At outside corners of masonry walls the IMPERIAL Plaster Base shall be supported by attaching it to either short horizontal pieces of furring channel mitered to extend around the corners or a vertical USG Metal Stud whenever furring brackets are used.

2 1/4" solid partition system erection

Floor and ceiling runners shall be accurately aligned according to the partition layout and securely fastened with suitable fasteners not less than 24" o.c.

Coreboard shall be cut to fit accurately between floor and ceiling runners and installed vertically with tongue edge leading. Coreboard shall be attached to runners with two 1 1/4" Type S Screws placed 3" in from each edge. Erection of succeeding panels shall follow the same procedure.

At partition intersections, coreboards shall be nailed together with 10d nails spaced 24" o.c. Panels shall be inserted in jamb anchor clips at all door frames, borrowed light frames and partition terminals and spot grouted at the clip locations.

IMPERIAL Plaster Base shall be cut to full floor-to-ceiling height. USG Laminating Adhesive shall be applied to back of face layers and laminated in place using moderate pressure to insure adequate bond. Face panel joints shall be offset at least 3" from coreboard joints. Face layer to coreboard shall be attached with USG Type G Screws driven about 2' from ends and 4' in field of panel; 1' from ends and 3' along vertical edges aligned about 2" from vertical edges.

double solid partition system erection

Floor and ceiling runners shall be shaped as detailed in the drawings, spaced to provide a minimum of 1 1/8" space between 1" coreboards and securely attached to floor and ceiling constructions with suitable fasteners spaced 24" o.c. Other specifications per 2 1/4" solid partition.

accessory application

a. IMPERIAL Tape shall be applied over all IMPERIAL Plaster Base joints with a spring-driven hand stapler using 3/8" staples. Tape shall be applied over the full length of all joints but shall not overlap at intersections. Tape shall be affixed with two staples at the top of the tape—one on each side of the joint, 24" o.c. (8" o.c. for fire-rated assemblies) along the length of the tape, alternating from side to side, with two staples at the bottom.

At wall-ceiling intersections, the tape shall be stapled every 24" along the ceiling edge only; for wall and partition interior corners, stapled every 24" on one edge only, working from top to bottom. All interior corners shall have tape positioned to bridge the joint.

When low humidity or rapid drying job conditions exist during lathing and plastering, DURABOND* Joint System shall be used on all joints, internal corners, trim and corner beads and allowed to set and dry thoroughly before finish plaster application.

b. Laminating Adhesive shall be USG Laminating Adhesive mixed according to manufacturer's directions and spread to provide adhesive beads 1/2" high x 3/8" wide at the base and spaced 4 1/2" o.c. for full sheet lamination. For strip lamination adhesive shall be applied in vertical strips spaced 24" o.c. Each strip shall consist of four adhesive beads 1 1/2" to 2" o.c.

c. Corner Bead—All vertical and horizontal exterior corners shall be reinforced with 800-A or B Corner Bead fastened with staples not over 12" o.c. on both flanges along the entire length of the bead.

d. Casing Bead—When an IMPERIAL wall or partition terminates against masonry or other dissimilar material, USG Metal Trim shall be applied over the IMPERIAL Plaster Base and fastened on the perforated side with staples spaced 12" o.c. The trim shall firmly abut the dissimilar material forming a neat joint.

e. Screws shall be power-driven with an electric screwdriver and set so that the screwhead provides a slight depression below the surface of the IMPERIAL Plaster Base without tearing through the face paper.

f. Control Joint shall be provided in the non-resilient face layer as indicated and shall be fastened with staples not over 12" o.c. on both flanges along entire joint length.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured and/or sold by that company: DIAMOND, STRUCTO-GAUGE (plaster); IMPERIAL (plaster and base, joint reinforcement); USG (metal products, gypsum coreboard, adhesives); SHEETROCK (gypsum wallboard); THERMAFIBER (insulation products); DURABOND (joint system).

a-1147

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Section
for
Sales
Office

partitions

a

1157

resilient attachment

Masonry and Plaster



A.I.A. File No. 10-D

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|--|------------|------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 3 hrs. est | Gypsum Tile & Plaster—3" hol PYROBAR—2x2 wd fur 16" o.c. vert—1½" THERMAFIBER sound atten bkts betw fur—R-5 resil clips att to wd fur—¾" ROCKLATH pl base—½" gypsum sand plaster one side & opp side ¾" direct—perimeter caulked wt 22.5 width 6½" | USG-123-FT-G&H (s) Field Test KSO-1090072-f (s) | 55 | 52 | 202 | Excellent sound & fire resistance. No outlets in 123-FT test; two caulked outlets in field test | a-1157 |
| 3 hrs. est | Gypsum Tile & Plaster—4" hol PYROBAR—R-5 resil clips—¾" ROCKLATH pl base—½" gypsum sand plaster one side & opp side ¾" direct—perimeter caulked wt 27 width 6" | USG-110-FT-G&H (s) Field Test KSO-1090072-e (s) | 50 | 47 | 178 | Good attenuation. No outlets in 110-FT; two caulked outlets in field test | a-1157 |
| 3 hrs. est | Gypsum Tile & Plaster—3" hol PYROBAR—R-5 resil clips—¾" ROCKLATH pl base—½" gypsum sand plaster one side & opp side ¾" direct wt 24 width 4¾" | TL-60-127 (s) | 50 | | 178 | Excellent fire resistance—reduces sound leaks & flanking paths | a-1157 |
| 3 hrs. est | Gypsum Tile & Plaster—3" hol PYROBAR—#500 resil clips—¾" cr chan & 3.4# dm met lath—¾" gypsum sand plaster one side & opp side ¾" direct wt 27 width 5¼" | NBS-313 (s) | 46 | | 195 | | a-1157 |

wall furring application

| | | | | | | | |
|---|---|---|---|---|-----|--|--------|
| — | R-5 Resilient Clips 16" o.c., Insulating ROCKLATH and BRIDJOINT® Clips, ½" sanded basecoat plaster, lime putty finish | — | — | — | 141 | Resiliency of R-5 Clip reduces transfer of structural stresses to surface membrane | a-1157 |
|---|---|---|---|---|-----|--|--------|

description

In these fire-resistant assemblies, ROCKLATH® Plaster Base or USG® Metal Lath and plaster wall facings are resiliently furred from PYROBAR® Gypsum Partition Tile or other masonry surface with special USG Resilient Clips. These clips improve sound transmission loss and make this partition highly suitable for party walls. The clips also greatly reduce the possibility of movement, vibration and thermal shock being transmitted from the masonry base to the plaster surface. The resilient clips may be attached to concrete block, clay or brick masonry to provide a resiliently floated, easily decorated lath and plaster surface for these types of masonry.

In the resilient attachment of ROCKLATH over masonry, the ROCKLATH is horizontally applied with end joints staggered and secured by USG R-5 Resilient Clips. These clips are spaced not more than 16" o.c. horizontally and vertically, furring the ROCKLATH ½" from the masonry.

With vertical 2x2 wood furring strips 16" o.c. nailed to 3" hollow PYROBAR Tile, R-5 Resilient Clips nailed to strips and 1½" THERMAFIBER Sound Attenuation Blankets between strips, an excellent sound insulative and fire-resistive party wall is obtained (see table above).

Metal lath may be resiliently furred from masonry surfaces with USG #500 Resilient Clips spaced 16" on center. ¾" channel spaced 16" o.c. is wire tied to the clips and metal lath is tied to the channels.

Pre-cast into a hollow core unit 12"x30", PYROBAR tile is easily laid-up with gypsum mortar to form a lightweight, highly fire-resistant non-load bearing masonry wall. It is available in three thicknesses, and may be plastered on one side, with a resiliently attached lath and plaster facing on the other. The finished partition has very good sound isolation and fire resistance ratings (see table above).

function and utility


Fireproof—PYROBAR Partition Tile provides the greatest fire protection per inch thickness of any commercial partition assembly—estimated 3 hours for partition plastered one side, resilient lath and plaster on other side (see table above).

Lightweight—Reduces dead load. PYROBAR Partition Tile is 30% to 50% lighter than commonly used masonry units.

Sound Isolation—Very good sound isolation—up to 55 STC—at a low cost (see table above).

Economical—Ease of maintenance and tenant renovations continue to make PYROBAR a leading office building partition construction.

(see page 3 for Limitations)




A.I.A. File No. 10-D

components

scale: 3" = 1'-0"

see "plaster bases" product catalog for full description on accessories & sizes



resilient clip R-5



BRIDJOINT clip B-1




5-A
bull nose
corner bead



10-A
bull nose
expanded flange
corner bead




R-SF resilient
starter-finisher



resilient clip No. 500




USG
4-R
expanded
corner bead




1-A
expanded
flange
corner bead


USG casing beads (expanded or short flange)




USG cold
rolled channel



#66 square edge




#4 or #138 quarter round




#60 semi-square




USG masonry
base clip




USG metal base
splice plate




USG metal base
& splice plate




partition wall intersection



cross section wall elevation
ROCKLATH plaster base—sound isolation



cross section wall elev.
resilient ROCKLATH plaster base



wall-plan view
resilient metal lath

limitations

1. A non-load bearing partition.
2. Portland cement and lime mortars do not bond satisfactorily to PYROBAR Partition Tile. Self-furring metal lath attached to PYROBAR is required to support a portland cement plaster.
3. PYROBAR, like other masonry plaster bases, is subject to volume change due to fluctuations in temperature and humidity. Control joints should be provided to relieve these stresses (see Specifications).
4. PYROBAR is not recommended for a masonry back-up of exterior wall construction.

technical data

| PYROBAR unit description | thickness | wt.-psf. | limiting height |
|--|-------------------|----------|-----------------|
| 3" Hollow, Plaster 1 side, M/L-Pl., Res. Clip other side | 5 $\frac{1}{4}$ " | 27 lbs. | 13' |
| 4" Hollow, Plaster 1 side, M/L-Pl., Res. Clip other side | 6 $\frac{1}{4}$ " | 30 lbs. | 17' |
| 3" Hollow, Plaster 1 side, R/L-Pl., Res. Clip other side | 5" | 23 lbs. | 13' |
| 4" Hollow, Plaster 1 side, R/L-Pl., Res. Clip other side | 6" | 27 lbs. | 17' |

specifications

notes to architect

1. It is assumed that this construction will be used primarily in party walls and dividing partitions for its sound isolation value, and that such partitions will not contain openings, will not exceed 30' in length so as to require control joints, and will not require fixture attachments. If any of these conditions are present, see "Notes to Architect" in PYROBAR Partition Tile & Plaster systems folder in this series.
2. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.
3. To retain maximum sound isolation, the integrity of the partition should not be voided by openings such as electrical outlets, medicine cabinets, vents, etc. that create sound leaks. The use of caulking to seal all cut-outs and to seal all inter-sections with the adjoining structure is recommended.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

Insulating Wool Products Folder for Sound Attenuation Blanket Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. PYROBAR Gypsum Partition Tile shall be (3") (4") (6") (solid) (hollow).
- b. RED TOP* Partition Tile Cement.
- c. Clean, sharp sand, complying with ASTM C35 (not available from U.S.G.).
- d. USG Selv-edge Cornerite (2"x2") (3"x3").
- e. USG Striplath.
- f. USG Self-Furring Junior Diamond Mesh Metal Lath.
- g. USG Corner Bead (specify type from page 2).
- h. USG Casing Bead (specify type from page 2).
- i. USG Control Joint.
- j. USG $\frac{3}{4}$ " Cold Rolled Channels.
- k. USG Resilient Clip R-5.
- l. USG Resilient Clip No. 500.
- m. USG BRIDJOINT* Clip B-1.
- n. ROCKLATH Plaster Base shall be ($\frac{3}{8}$ "x16"x48") ($\frac{3}{8}$ "x16"x96") Regular or Perforated.
- o. Metal Lath shall be 3.4 lb. Diamond Mesh 27"x96".
- p. 18 ga. Tie Wire.
- q. THERMAFIBER Sound Attenuation Blankets 1 $\frac{1}{2}$ "x15"x48".
- r. 2x2 Wood Furring (not available from U.S.G.).
- s. R-SF Resilient Starter-Finisher Clip.

partition erection

All mortar shall be mixed in proportions of 1 part Partition Tile Cement to 3 parts sand, by weight. Mortar shall not be retempered.

After door frames are erected and rough plumbing and wiring are in place, the first course shall be laid with core holes horizontal by bedding mortar to a true and straight line according to partition layout as shown on plans. Succeeding courses shall be laid to a line in $\frac{1}{2}$ " thick full mortar beds iniformly level in each course. Vertical joints shall be staggered and head joints shall be filled with $\frac{1}{2}$ " of mortar. Cut all joints flush. Use of broken tile shall be kept to a minimum. Chinks and crevices shall be slushed full with mortar.

Lintels shall be formed as shown in the plans. Partitions shall be well anchored to intersecting masonry walls 12 $\frac{1}{2}$ " o.c.

sound transmission loss

| test no. | method | decibel frequency in cps | | | | | | | | | | | | | | | | | | | | STC | |
|------------------|--------|--------------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|------|------|------|------|------|------|------|-----|------|
| | | 125 | 160 | 175 | 200 | 250 | 315 | 350 | 400 | 500 | 630 | 700 | 800 | 1000 | 1250 | 1400 | 1600 | 2000 | 2500 | 2800 | 3150 | | 4000 |
| TL-60-127 | Lab | 33 | — | 37 | — | 38 | — | 46 | — | 48 | — | 51 | — | 51 | — | 55 | — | 55 | — | 60 | — | 64 | 50 |
| KSO-1090072-e | Field | 25 | — | 33 | — | 37 | — | 41 | — | 46 | — | 52 | — | 53 | — | 54 | — | 56 | — | 60 | — | 63 | 47 |
| | | 25 | 30 | — | 33 | 37 | 37 | — | 44 | 46 | 49 | — | 53 | 53 | 53 | — | 53 | 56 | 59 | — | 61 | 63 | 47 |
| USG-110-FT-G & H | Lab | 28 | — | 34 | — | 40 | — | 44 | — | 47 | — | 55 | — | 58 | — | 59 | — | 61 | — | 63 | — | 61 | 50 |
| USG-123-FT-G & H | Lab | 37 | — | 51 | — | 49 | — | 49 | — | 54 | — | 54 | — | 58 | — | 60 | — | 60 | — | 63 | — | 62 | 55 |
| KSO-1090072-f | Field | 32 | — | 38 | — | 46 | — | 46 | — | 49 | — | 50 | — | 53 | — | 52 | — | 58 | — | 61 | — | 66 | 52 |
| | | 32 | 36 | — | 39 | 46 | 44 | — | 46 | 49 | 50 | — | 51 | 53 | 52 | — | 54 | 58 | 62 | — | 62 | 66 | 52 |

vertically with corrugated wall ties or 16d or 20d cut nails imbedded in mortar joints.

Wedge partition tightly at ceiling with skew cut tile corners every third tile. Joints between tile and ceiling shall be slushed full with mortar.

PYROBAR shall not be chased or cut out more than half its thickness for conduit or other piping. Metal lath shall be placed flush over the chase and secured in place.

plaster base attachment

metal lath with resilient clips

Securely attach the USG #500 Resilient Furring Clip to the face of the PYROBAR Partition using an angular driven 1 3/4" staple or a 8d cut nail. Cut nails, if used, shall be driven only into the solid part of the partition and not into the core holes. Clips to be spaced not to exceed 16" o.c. both ways. 3/4" cold rolled channels shall be erected vertically, the legs of the channel nested into the grooves on the inner face of each clip and saddle tied with a double strand of 18 ga. tie wire.

Metal lath shall be applied with the long dimension of the sheet across the supports. The ends of all lath shall be lapped not less than 1". If end laps are made between supports they shall be adequately tied with 18 ga. tie wire. The sides of diamond mesh lath shall be lapped not less than 1/2".

Wherever possible, end of lath in adjacent courses shall be staggered.

Metal lath shall be secured to all supports at intervals not exceeding 6".

At all interior angles, metal lath shall be formed into the corners and carried out into the abutting surface, and adequately secured.

ROCKLATH with resilient clips

USG R-5 Resilient Clips shall be securely attached to the PYROBAR tile with an angular driven 1 3/4" fence staple with one leg penetrating the PYROBAR and the other bridging the attachment flange of the clip.

The clips shall be spaced at a maximum of 16" o.c. and at each lath end joint.

ROCKLATH Plaster Base shall be applied face out with the long dimension at right angles to the framing members. All joints shall be butted together and the lath shall be accurately cut and neatly fitted around all electrical outlets, openings, etc.

Succeeding courses of ROCKLATH Plaster Base shall be similarly applied with end joints staggered.

At the floor and ceiling line shim out the ROCKLATH using a narrow piece of ROCKLATH and nail in place.

ROCKLATH with resilient clips on wood furring strips

Wood furring strips shall be sized 2x2, spaced 16" o.c. and installed vertically using nails of sufficient length to penetrate at least 1 1/2" into solid part of tile and not core holes. Strips may be angle nailed on alternate sides if necessary. 1 1/2" THERMAFIBER Sound Attenuation Blankets shall be placed between strips and held in place with staples.

ROCKLATH Plaster Base shall be applied face out with end joints staggered in adjacent courses and with 1/4" clearance around partition perimeter. Ends of lath shall be aligned and secured with R-5 Resilient Clips spaced 16" o.c. and nailed to furring strips with 1 1/8" lathing nail. Top and bottom lath courses shall be attached at floor and ceiling line with R-SF Clips spaced 16" o.c. and nailed to furring strips.

lathing accessories

a. Cornerite (2"x2") (3"x3") shall be installed in all interior plaster angles. Staple at the edges (required only for ROCKLATH Plaster Base).

b. Metal Corner Bead No. () shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with wire-ties or galvanized staples, spaced not over 8" o.c.; stagger in two wings.

c. Casing Bead No. () shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Wire-tie or staple in place.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ROCKLATH (plaster base); PYROBAR (gypsum partition tile); RED TOP (partition tile cement); BRIDJOINT (clips).

a-1157

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selection
for
Sales
Offices



direct attachment

partitions

a

PYROBAR* Partition Tile and Plaster

1167

A.I.A. File No. 10-D

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|-------------------------------|------------|------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 4 hrs. | Gypsum Tile & Plaster—4" hol PYROBAR tile— $\frac{5}{8}$ " 100:3 gypsum sand plaster wt 26 width $5\frac{1}{4}$ " | T-118-OSU (f) NBS-305 (s) | 42 | | 159 | Excellent fire protection—good plaster base | a-1167 |
| 4 hrs. | Gypsum Tile & Plaster—6" hol PYROBAR tile— $\frac{1}{2}$ " 100:3 gypsum sand plaster one side only wt 28 width $6\frac{1}{2}$ " | T-26-1-OSU (f) | N/A | | 139 | Excellent fire protection, low dead load | a-1167 |
| 3 hrs. | Gypsum Tile & Plaster—4" hol PYROBAR tile— $\frac{1}{2}$ " 100:3 gypsum sand plaster one side only wt 20 width $4\frac{1}{2}$ " | T-118-29&30-OSU (f) | N/A | | 124 | | a-1167 |
| 3 hrs. | Gypsum Tile & Plaster—3" hol PYROBAR— $\frac{5}{8}$ " 100:3 gypsum sand plaster wt 23 width $4\frac{1}{4}$ " | T-26-5-OSU (f) NBS-304 (s) | 40 | | 154 | Incombustible—good plaster base—economical | a-1167 |
| 3 hrs. | Gypsum Tile—3" solid PYROBAR—unplastered wt 16 width 3" | T-26-3-OSU (f) | | | 91 | Excellent fire protection for weight & cost | a-1167 |
| 2 hrs. | Gypsum Tile & Plaster—3" hol PYROBAR— $\frac{5}{8}$ " 100:3 gypsum sand plaster one side only wt 17 width $3\frac{3}{8}$ " | GA-T-1101-OSU (f) | | | 118 | Good protection for chase walls, vent & elevator shafts | a-1167 |
| 1 hr. | Gypsum Tile—3" hol PYROBAR—unplastered wt 11 width 3" | BMS-92 table 24 (f) | | | 78 | | a-1167 |
| 1 hr. | Gypsum Tile—2" solid PYROBAR—unplastered wt 11 width 2" | BMS-92 table 24 (f) | | | 86 | For col. fireprfg., short runs & vent shafts only | a-1167 |

description

This partition assembly, suitable for both new construction and alteration work, consists of gypsum plaster applied directly to PYROBAR Gypsum Partition Tile. Pre-cast into a hollow core unit, 12" x 30", PYROBAR is easily laid-up with gypsum mortar to form a lightweight, highly fire-resistant, non-load bearing masonry wall. Indented surfaces and kiln-drying make PYROBAR an ideal plaster base that forms a strong natural bond with gypsum plaster.

PYROBAR is available in three thicknesses (see table below) and may be plastered on one or both sides to provide fire resistance ratings that meet most requirements (see table above).

function and utility

Fireproof—PYROBAR Partition Tile provides the greatest fire protection per inch of thickness of any commercial partition assembly—4 hours for two assemblies, plastered one and two sides; 3 hours for 3" and 4" hollow PYROBAR, both plastered and unplastered (see table above).

Lightweight—Reduces dead load. PYROBAR Partition Tile is 30% to 50% lighter than commonly used masonry units.

Plaster Bond—PYROBAR is more compatible with gypsum basecoat plasters than any other masonry plaster base.

Sound Isolation—Good sound isolation at a low cost (see table above). Where greater sound isolation is desired, resilient attachment of ROCKLATH* Plaster Base or USG® Metal Lath to PYROBAR is recommended (see USG Folder a-1156).

Economical—Ease of maintenance and tenant renovations continue to make PYROBAR a leading office building partition construction.

limitations


1. A non-load bearing partition.
2. Portland cement and lime mortars do not bond satisfactorily to PYROBAR Partition Tile. Self-furring metal lath attached to PYROBAR is required to support a Portland cement plaster.
3. PYROBAR, like other masonry plaster bases, is subject to volume change due to fluctuations in temperature and hu-

midity. Control joints, as detailed on page 4, should be provided to relieve these stresses (see Specifications).

4. PYROBAR is not recommended for a masonry back-up of exterior walls or less-than-ceiling-height partitions.

technical data


| PYROBAR unit—description | thickness | wt.—psf. | limiting height |
|----------------------------|------------------|----------|-----------------|
| 3" Solid, Unplastered | 3" | 16 lbs. | 11' |
| 3" Hollow, Unplastered | 3" | 11 lbs. | 11' |
| 3" Hollow, Plaster 1 side | $3\frac{3}{8}$ " | 17 lbs. | 13' |
| 3" Hollow, Plaster 2 sides | $4\frac{1}{4}$ " | 23 lbs. | 13' |
| 4" Hollow, Plaster 1 side | $4\frac{5}{8}$ " | 20 lbs. | 17' |
| 4" Hollow, Plaster 2 sides | $5\frac{1}{4}$ " | 26 lbs. | 17' |
| 6" Hollow, Plaster 2 sides | $7\frac{1}{4}$ " | 33 lbs. | 30' |




components





PYROBAR partition tile




USG metal base
splice plate



USG metal base
& splice plate




USG masonry
base clip



see "plaster bases" product catalog for
full description on accessories & sizes




USG casing beads
(expanded or short flange)



USG 7-A curved point
base screed




USG 8-A
picture mould




details

scale: 3"=1'-0"




metal


top set




wood




cement or terrazzo



structural glazed tile




ceramic tile




ceramic tile wainscot

details


scale: 3"=1'-0"




partition terminal at flush concrete column




partition control joint




alt. partition terminal at flush concrete column




partition terminal




outlet box




partition wall intersection



corner













partition intersection



perimeter relief ceiling intersection

details







core walls

Core walls, as vertical shafts encasing the usual plumbing supply and waste lines, vent ducts, and electrical conduits, require more free space than can be provided within the usual partition assembly.

Core walls are readily constructed with PYROBAR. Fixtures, such as sinks, shelves, etc., are attached easily (see details).

scale: 1 1/2"=1'-0"



specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.

2. Steel door frames should be fabricated from 16 gauge metal, minimum, shop primed. The opening at the trim return should be accurately formed to the overall thickness of the partition.

Base plates, designed with two anchor holes to prevent rotation, should be securely welded to the flanges to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate.

A minimum of three 5" metal frame ties on each jamb should be provided to anchor the frame in the mortar joints (see detail page 5). Separate bracing should be furnished to keep the frame in alignment.

Grouting by slushing mortar between the tile and the door frame is recommended on all installations and is required where heavy or oversize doors are used.

Door closers are recommended on all doors where the weight of the door (including attached hardware) exceeds 50 lbs.

3. A minimum of two 5" metal frame ties on each jamb of borrowed lights should be provided for anchorage in the mortar joints.

4. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements except the floor, and control joints be specified where:

- a partition abuts any structural element or dissimilar wall or ceiling assembly.
- the partition construction changes within the plane of the partition.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling may be used as control joints. For doors less than ceiling height, a control joint extending from the center or both corners of the frame to the ceiling may be used.

For column isolation apply a 15 lb. asphalt felt across the face of the structural members to prevent bonding of the plaster to the column or beam and then use 3.4 lb. self-furring diamond mesh lath across the asphalt felt, securely stapled to the PYROBAR (see detail page 6).

5. Holes cut for door frames, borrowed lights, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

6. Where a plaster surface is flush with metal, metal bucks, metal windows, or metal base, the plaster should be grooved between the two materials.

7. Fixture attachment (see details, page 6)—Lightweight fixtures (shelves, cabinets, chalkboards, etc.) should be attached to a 3/8" wood nailer strip or USG 8-A Picture Mould which has been secured to the PYROBAR Partition Tile. Medium weight fixtures may be secured with 3/8" steel bolts through the tile, using 2" steel washers on both sides of tile. Heavy fixtures should be attached to self-supporting hangers.

8. Ceramic Tile—Where portland cement plaster is to be applied to PYROBAR partitions as a bedding coat for ceramic tile facing or other purposes, galvanized self-furring metal lath shall be first applied to the face of the PYROBAR. A USG No. 66 Casing Bead (5/8" grounds) or other suitable plaster stop shall be used between the portland cement plaster and gypsum plaster (see detail page 3).

9. Where cement or terrazzo base is used, metal lath should be secured to the first course of PYROBAR. SUPER-TITE® Dampproofing Coating should be applied to the PYROBAR from rough floor up to height of wet terrazzo (concrete) base. Care should be taken to obtain thorough application at joint of PYROBAR with rough floor (see detail page 3).

10. To retain maximum sound isolation, the integrity of the partition should not be voided by openings such as electrical outlets, medicine cabinets, vents, etc. that create sound leaks.

11. When used as a vertical elevator shaft enclosure, the PYROBAR assembly should be laterally restrained at the top with masonry anchors, Cornerite, or continuous angles.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- PYROBAR Gypsum Partition Tile shall be (3") (4") (6").
- RED TOP® Partition Tile Cement.
- Clean, sharp sand, complying with ASTM C35 (not available from U.S.G.).
- USG Metal Base—2 1/2" (18) (20) ga.
- USG Metal Base Splice Plate.
- USG Masonry Base Clip.
- USG Selv-edge Cornerite (2" x 2") (3" x 3").
- USG Striplath.
- USG Self-Furring Junior Diamond Mesh Metal Lath.
- USG Corner Bead (specify type from page 2).
- USG Casing Bead (specify type from page 2).
- USG Control Joint.

partition erection

All mortar shall be mixed in proportions of 1 part Partition Tile Cement to 3 parts sand, by weight. Mortar shall not be retempered.

After door frames are erected and rough plumbing and wiring are in place, the first course shall be laid with core holes horizontal by bedding mortar to a true and straight line according to partition layout as shown on plans. Succeeding courses shall be laid to a line in $\frac{1}{2}$ " thick full mortar beds uniformly level in each course. Vertical joints shall be staggered and head joints shall be filled with $\frac{1}{2}$ " of mortar. Cut all joints flush. Use of broken tile shall be kept to a minimum. Chinks and crevices shall be slushed full with mortar.

Lintels shall be formed as shown in the plans. Partitions shall be well anchored to intersecting masonry walls $1\frac{1}{2}$ " o.c. vertically with corrugated wall ties or 16d or 20d cut nails imbedded in mortar joints.

Wedge partition tightly at ceiling with skew cut tile corners every third tile. Joints between tile and ceiling shall be slushed full with mortar.

PYROBAR shall not be chased or cut out more than half its thickness for conduit or other piping. Metal lath shall be placed flush over the chase and secured in place.

Steel door frames shall be anchored to the PYROBAR with frame ties furnished by door frame manufacturer, minimum three each side (approximately 12" from top and bottom and at center) laid in mortar joints. Space between tile and door frame jamb shall be slushed full with mortar as tile is laid into frame. Lintel construction shall be held at least $\frac{1}{8}$ " above head of frame with mortar.

Borrowed light openings shall be anchored the same as door frames, except only two metal frame ties are required on the jambs (approximately at third points), of openings less than 80" high.

lathing accessories

a. Metal Base $2\frac{1}{2}$ inch, (18) (20) gauge, painted, shall be notched to a neat miter in forming all angles. Masonry Base Clips, spaced 12" to 16" o.c., shall be nailed to masonry. In continuous runs, ends of metal base shall be evenly butted and internally spliced with a splice plate. Base shall be securely held in place by engaging the base clips.

b. Cornerite (2" x 2") (3" x 3") shall be installed in all interior plaster angles. Nail at the edges.

c. Metal Corner Bead No. () shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with nails or galvanized staples, spaced not over 8" o.c.; stagger in two wings.

d. Casing Bead No. () shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Nail in place.

e. Reinforcing—Install a strip of self-furring diamond mesh lath over joints between dissimilar plaster bases. At all openings, reinforce the corners attaching a 12" x 24" piece of self-furring diamond mesh lath diagonally across the corners. Metal lath shall be placed flush over conduit and pipe chases and nailed in place.

f. Control Joint shall be provided as detailed and where indicated. Nail in place.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ROCKLATH (plaster base); PYROBAR (gypsum partition tile); RED TOP (partition tile cement); SUPER-TITE (asphalt coating).

a-1167

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



UNITED
STATES
GYPSUM

partitions

a

TRUSSTEEL* Studs and USG® Metal Lath

1177

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|--|------------|------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | Stl Stud—Metal Lath & Plaster—2½" TRUSSTEEL studs 16" o.c.—3.4# dm met lath—¾" gypsum wood fiber plaster wt 17 width 4¾" | BMS-92 table 31 (f) | N/A | | 210 | Excellent fire performance; highly abrasion resistant | a-1177 |
| 1 hr. | Stl Stud—Metal Lath & Plaster—3¾" TRUSSTEEL studs 16" o.c.—3.4# dm met lath—¾" 100:2-100:2 gypsum sand plaster wt 16 width 4¾" | BMS-92 table 31 (f) NBS-229 F48 (s) | 41 | | 150 | Standard steel stud partition | a-1177 |
| 1 hr. | Stl Stud—Resil Metal Lath & Plaster—3¾" TRUSSTEEL studs—#400 resil clips—¾" pencil rods—3.4# dm met lath—¾" 100:2-100:3 gypsum sand plaster—perimeter caulked wt 19 width 5¾" | T-1263-OSU (f) CK 664-5 (s) | | 50 | 180 | Popular construction with good sound isolation. Fire test based on assembly with 1½" studs | a-1177 |
| 1 hr. | Stl Stud—Resil Metal Lath & Plaster—1½" TRUSSTEEL studs—one side ¼" pencil rods & #400 resil clips—opp side direct—3.4# dm met lath—¾" 100:2-100:3 gypsum sand plaster wt 18 width 3¾" | T-1263-OSU (f) TL-58-8 (s) | 45 | | 159 | Space-saving partition | a-1177 |

For wall furring application, see page 10.

description

These partition assemblies consist of USG Metal Lath, attached to open-web TRUSSTEEL* Studs. The lath is either directly wired to the stud or resiliently attached by means of ¼" Pencil Rods and USG Resilient Clips. By using these specially designed resilient clips, the two lath and plaster diaphragms are not rigidly coupled to the studs or each other. The excellent sound-isolative efficiency of this system results from this resilient mounting of the plaster membranes and the column of air formed within the TRUSSTEEL Studs (see table above).

TRUSSTEEL Studs utilize a truss design for superior strength, are fabricated in five stud widths (see table at right) and are mill cut to job lengths. Studs are attached to the floor and ceiling by means of clips or runner tracks and TRUSSTEEL stud shoes.

Metal Lath for these assemblies is available in three types (see Specifications, page 11). 3.4 lb. Diamond Mesh Metal Lath is used as the plaster base for resilient attachment. The excellent mechanical keying properties and equal distribution of reinforcing provided by this plaster base give assemblies using it high fire resistance and sound transmission loss ratings for their weight (see table above).

function and utility

The open web of the truss design provides a maximum of free space for encasing pipes, conduits or ducts, horizontally, vertically or diagonally, without impairing the structural integrity of the assembly.

Fire Protection—Incombustible components provide systems with 1-hour and 2-hour fire-resistance ratings (see table above).

Strength—TRUSSTEEL Studs are formed of No. 7 gauge cold drawn wire, with a tensile strength of 90,000 psi. The resistance moment computed on the section modulus with the high tensile strength produces an exceptionally strong non-load bearing steel stud.

Economical—The structural integrity, the strength, the sound isolation, the open core wall and fire protection are provided by TRUSSTEEL Stud partitions at a lower cost than by other incombustible assemblies.

Performance—TRUSSTEEL Studs have been used since 1933 and now account for the majority of all non-load bearing steel studs used nationally. The continued high level of use indicates their acceptance based on their performance.


limitations

1. A non-load bearing partition.
2. Stud spacing limited to 16" o.c. for 3.4 lb. Diamond Mesh Lath, 19" o.c. for 3.4 lb. ¼" Z-Riblath, and 24" o.c. for ¾" Riblath (see table below for limiting heights).
3. Door frames must be fabricated and anchored to prevent twisting and impact vibration (see detail, page 7).
4. To retain maximum sound isolation, precautions must be taken to prevent sound leakage (see Specifications, page 11).
5. Where mechanically suspended acoustical tile ceilings are used, finished partitions should extend from structural slab to structural slab, closing all openings (see Notes, page 11).

partition thickness—limiting heights

| stud width | section modulus | finished thickness | | | maximum partition heights(1) | | |
|------------|-----------------|--------------------|----------------------------|------------------------|------------------------------|-----------------|-----------------|
| | | riblath ¾" | diamond mesh or ½" riblath | resilient diamond mesh | studs 16" o.c. | studs 19" o.c.† | studs 24" o.c.‡ |
| 1½" | .0635"³ | 3½" | 3½" | (2) | 9' | — | — |
| 2½" | .1056"³ | 4½" | 4" | 5" | 15' | 14' | 9' |
| 3¼" | .1420"³ | 5¼" | 4¾" | 5¾" | 21' | 18' | 13' |
| 4" | .1825"³ | 6" | 5½" | 6½" | 22' | 20' | 16' |
| 6" | .277"³ | 8" | 7½" | 8½" | 26' | 24' | 20' |


(1) Resilient partition limiting height is 10'. (2) Not recommended for resilient attachment. †¾" 3.4 lb. Z-riblath or ¾" riblath. ‡¾" riblath only.




sound transmission loss

| test no. | method | decibel frequency in cps | | | | | | | | | | | | | | | | | | | | STC | |
|----------|--------|--------------------------|-----|------|-----|-----|-----|------|-----|-----|-----|------|-----|------|------|------|------|------|------|------|------|-----|------|
| | | 125 | 160 | 175 | 200 | 250 | 315 | 350 | 400 | 500 | 630 | 700 | 800 | 1000 | 1250 | 1400 | 1600 | 2000 | 2500 | 2800 | 3150 | | 4000 |
| CK 664-5 | Lab | 35 | 40 | — | 44 | 46 | 47 | — | 48 | 49 | 50 | — | 51 | 51 | 50 | — | 47 | 48 | 51 | — | 53 | 55 | 48 |
| TL-58-8 | Lab | 32.5 | — | 36.5 | — | 42 | — | 45.5 | — | 46 | — | 47.5 | — | 47 | — | 46 | — | 45 | — | 47 | — | 50 | 45 |


components




USG regular runner track



USG snap-in runner track



USG metal base splice plate



USG metal base & splice plate



USG 1-A expanded corner bead



USG 4-R expanded corner bead



USG 5-A bull nose corner bead


see "plaster bases" product catalog for full description on accessories & sizes



TRUSSTEEL stud



USG stud base clip



USG control joint



USG 6-A plain base screed




USG 7-A curved point base screed



USG 8-A picture mould



TRUSSTEEL stud shoe




#400 resilient clip




USG 10-A expanded bull nose corner bead




USG 3-A expanded base screed




USG casing beads (expanded or short flange)



#66 square casing bead




#60 semi-square edge



#4 or #138 quarter round

approx.




approx.

USG cold rolled channels





USG selv-edge cornerite





details | resilient attachment

scale: 3" = 1'-0"

ceiling attachments











floor attachments





details | resilient attachment


scale: 3" = 1'-0"




details | direct attachment




intersecting partitions



partition wall intersection




corner




partition intersection


wall control joint




electrical outlet




fixture attachments




light




light



heavy







light




light



details | door frames



wall elevation



jamb anchor inserts/half size




core walls

scale: 3" = 1'-0"


Core walls, as vertical shafts encasing the usual plumbing supply and waste lines, vent ducts and electrical conduits, require more free space than can be provided within the usual partition assembly.

Core walls are easily constructed using TRUSSTEEL Studs and Metal Lath provided proper bracing is used to compensate for the stress skin action of the one side. The non-lathed side of the studs should be braced with $\frac{3}{4}$ " continuous channel girts at the quarter points vertically or 48" o.c. maximum, and $\frac{3}{4}$ " channel bracket mid-girts spaced 36" o.c. horizontally.




TRUSSTEEL stud core wall

details




closet carrier




lavatory carrier

scale: 1 1/2" = 1'-0"



furred wall-jamb return



soffit detail

exterior wall furring

| description | relative cost index | comments | folder reference |
|---|---------------------|---|------------------|
| TRUSSTEEL Studs 16" o.c. cross braced 4' o.c. on the back chord, 3.4# diamond mesh metal lath, 5/8" sanded basecoat plaster, lime putty finish coat | 203 | Free standing; allows for pipe chase clearance; no vapor barrier. | a-1177 |

It is recommended that all exterior masonry walls be furred. Asphaltic or bituminous bonding agents are not recommended as a plaster base. TRUSSTEEL Studs, metal lath and plaster provide an exterior wall furring system that offers a maximum free space for encasement of pipes, ducts or conduits and a finished, readily decorated interior wall surface.




This construction consists of TRUSSTEEL Studs as vertical members braced with horizontal 3/4" channels. A channel at the mid-point between the floor and ceiling is attached to the wall with USG Adjustable Wall Furring Brackets not more than 24" o.c. horizontally. TRUSSTEEL Studs, with spacing determined by the maximum allowable spacing of supports for the type of metal lath used (see table, page 1) are wire-tied to these horizontal channels. Metal lath is wire-tied to the TRUSSTEEL Studs and plastered to 5/8" grounds, over the face of the lath. The Adjustable Wall Furring Brackets and extra channel at mid-height may be omitted to obtain free standing furring.

| TRUSSTEEL stud size | maximum height ¹ | |
|---------------------|-----------------------------|-----------------------|
| | braced furring | free-standing furring |
| 1 1/2" | 9' | 6' |
| 2 1/2" | 15' | 10' |
| 3 1/4" | 21' | 14' |
| 4" | 22' | 15' |
| 6" | 26' | 17' |

(1) Based on 16" spacing between studs.

adjustable wall furring brackets

1. Attach wall furring not more than 24" o.c. horizontally and 48" o.c. vertically.
2. After attachment, bend bracket to horizontal position.
3. Wire-tie plumbed channel to bracket 1/4" min. (2 1/4" max.) from wall.
4. Bend excess of bracket down.





specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.

2. All fire-rated partitions require the TRUSSTEEL Stud attachment to the Regular or Snap-In Runner Track by the TRUSSTEEL Stud Shoes at the ceiling.

3. Snap-In Runner Track with studs cut accurately to length may be used for a floor and ceiling attachment where the construction is non fire-rated. This track may be used at the floor on fire-rated partitions.

4. A TRUSSTEEL Stud Partition used as a sound barrier must have caulking under the floor and ceiling runner track to seal the voids between track and structural slab. Eliminate cutting holes back to back or adjacent to each other such as electrical outlets. Use sand aggregate only. Caulk perimeter of plaster. Door and borrowed light openings are not recommended.

5. Steel door frames should be fabricated from 16 gauge metal, minimum, shop primed. The opening at the trim return should be accurately formed to the overall thickness of the partition.

Base plates, designed with two anchor holes to prevent rotation, should be securely welded to the flanges to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate.

Four jamb anchors should be provided on each jamb, welded to the trim returns. (See detail, page 7.)

Grouting of the door frame is recommended on all installations and is required where heavy or oversize doors are used. The grout shall be raked out to allow the lath and plaster to be inserted into the frame. Under no conditions shall the lath and plaster terminate against the trim return of the door frame.

Door closers are recommended on all oversize doors and doors where the weight of the door (including attached hardware) exceeds 50 lbs.

6. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements, except the floor, and control joints be specified where:

a. a partition abuts any structural element or dissimilar wall or ceiling assembly.

b. the partition construction changes within the plane of the partition.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling may be used as control joints. For doors less than ceiling height, control joints extending from the center or both corners of the frame to the ceiling may be used.

Where finished partitions join structural slabs, the plaster should be cut back or casings installed, and the intersection should be caulked.

7. Holes cut in a thin lath or plaster membrane, such as door frames, borrowed lights, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgement of the architect, for reasons of economy or design, a control joint is not otherwise specified.

8. Where a plaster surface is flush with metal, metal bucks, metal windows, or metal base, the plaster should be grooved between the two materials.

9. **Fixture attachment**—Lightweight fixtures and trim should be installed using plastic plugs or other expandable anchors for screw attachment. Heavy fixture attachment is not recommended on resilient lath and plaster surfaces.

Wood inserts for fixture attachment on non-resilient surfaces must always be wire-tied to the inside of the stud chord to prevent breaking up the stress skin of the lath and plaster.

10. **Ceramic Tile**—Where ceramic tile is required, a portland cement-lime plaster may be applied in scratch and brown coats to $\frac{5}{8}$ " grounds over metal lath as a base. Ceramic tile may also be adhesively attached over the finished gypsum plaster in accordance with adhesive manufacturer's specifications.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. USG Regular Runner Track—widths 1 $\frac{5}{8}$ ", 2 $\frac{1}{2}$ ", 3 $\frac{1}{4}$ ", 4", or 6" (see Note 2).
- b. USG Snap-In Runner Track—widths 1 $\frac{5}{8}$ ", 2 $\frac{1}{2}$ ", 3 $\frac{1}{4}$ " or 4" (see Note 3).
- c. TRUSSTEEL Studs—widths 1 $\frac{5}{8}$ ", 2 $\frac{1}{2}$ ", 3 $\frac{1}{4}$ ", 4", or 6" (see Note 2).
- d. TRUSSTEEL Stud Shoes.
- e. No. 400 Resilient Clip.
- f. USG Stud Base Clip.
- g. USG Metal Base Splice Plate.
- h. USG Metal Base—2 $\frac{1}{2}$ " (18) (20) ga.
- i. USG Corner Bead (specify style from page 2).
- j. USG Casing Bead (specify type from page 2).
- k. USG Base Screed (specify type from page 2).
- l. USG 8-A Picture Mould.
- m. USG Cold Rolled Channels $\frac{3}{4}$ ", 1 $\frac{1}{2}$ ", 2".
- n. 18 ga. tie wire.
- o. $\frac{1}{4}$ " Pencil Rods.
- p. Metal Lath shall be 3.4 lb. (Diamond Mesh) (Z-Riblath) ($\frac{3}{8}$ " Riblath) 27" x 96".
- q. USG Adjustable Wall Furring Bracket.
- r. THERMAFIBER Sound Attenuation Blankets 2" x 24" x 48".

stud system erection

TRUSSTEEL Studs shall be of the size shown on the plans or as herein specified, spaced not to exceed 16" o.c. All partitions shall be aligned accurately according to the partition layouts.

Runner Tracks where required shall be securely attached:

1. **To concrete slabs**—Using concrete stub nail or power-driven anchors, spaced not to exceed 24" o.c.



2. To ceiling grillage—Wire tie, using a double strand of 18 ga. tie wire, spaced not to exceed 16" o.c.

3. To plaster or gypsum lath—Toggle bolt or staple, spaced not to exceed 24" o.c.

Studs shall rest on the floor track and be cut to the nominal ceiling height. With Regular Runner Track and shoes, end of the studs shall be no more than 3" from the ceiling; with Snap-In Runner Track, no more than $\frac{3}{8}$ " from ceiling.

Studs shall be placed vertically, engaging runner tracks. Studs shall be secured to runner tracks at floor and ceiling with a pair of shoes, crimped or wire tied in place using a double strand of 18 ga. tie wire. Two wire ties of double strand 18 ga. wire shall be used at all studs immediately adjacent to door frames or borrowed light frames.

wall furring erection

On partitions designated as vertical furring the back chord of the TRUSSTEEL Stud must be bridged using continuous $\frac{3}{4}$ " channels at the third points or not to exceed 48" o.c. and at mid-height. The channels to be saddle-tied at each stud.

Braced furring requires a rigid, secure attachment at 24" o.c. along the mid-point bridging channel to the masonry back-up.

USG Adjustable Wall Furring Brackets, with serrated edges up, shall be attached to the masonry walls at mid-height of the furred wall and spaced not over 4" from columns or other abutting construction and not over 24" o.c. horizontally and 48" o.c. vertically, and as required above and below windows, using (one 2" cut nail in mortar joints or brick clay tile, or cement block or in the field of light-weight aggregate blocks) ($\frac{5}{8}$ " concrete stub nails or power driven nails or other suitable fasteners in monolithic concrete). Fastenings shall be driven through top hole of bracket. The mid-height furring channels shall be laid horizontally on the furring brackets with the legs down, and wire-tied to the bracket with a double strand of 18 ga. tie wire. Excess bracket length shall be bent down.

door frames

Studs shall be inserted into the steel door frame, nested in the notches of the jamb anchor clips, and each chord of the stud securely wire-tied at each side of each jamb anchor. A second stud shall be installed on each side of the door frame, approximately 2" from the strut stud.

Two $\frac{3}{4}$ " cold rolled channels shall be used over the head of the door, extending out to engage the third stud on each side.

These aligning channels shall be securely tied to the inside of the stud chord at each intersection.

direct plaster base attachment

Metal lath shall be applied with the long dimension of the sheet across the supports. Riblath shall be applied with the rib projections against the support.

The ends of all lath shall be lapped not less than 1". If end laps are made between supports, they shall be adequately laced or tied with 18 ga. tie wire. The sides of diamond mesh lath shall be lapped not less than $\frac{1}{2}$ ". The sides of riblath shall be lapped by nesting outside ribs, and shall be wire-tied to every support, and between supports not to exceed 9" intervals. All metal lath shall be placed so that the lower sheets overlap the upper sheets. Wherever possible, ends of lath in adjacent courses shall be staggered.

Metal lath shall be secured to all supports, except those covered in subsequent sections, with 18 ga. tie wire at intervals not exceeding 6".

At all interior angles, metal lath shall be formed into the corners and carried out onto the abutting surface, and adequately secured.

resilient plaster base attachment

Resilient Clip No. 400 shall be snapped over the chord of the TRUSSTEEL Stud, spaced not to exceed 16" o.c. with a clip located not more than 4" from the floor and ceiling. $\frac{1}{4}$ " Pencil Rods of ceiling height length shall be snapped into the small loop of the 400 Clip.

3.4 lb. Diamond Mesh Metal Lath shall be applied with the long dimension of the sheet across the supports.

(To complete specification add last three paragraphs from "direct plaster base attachment" above.)

lathing accessories

a. Metal Base 2 $\frac{1}{2}$ inch, (18) (20) ga., painted, shall be notched to a neat miter in forming all angles. In continuous runs, ends shall be evenly butted and internally spliced with a splice plate. Base shall be securely held in place by engaging the base clips.

b. Metal Corner Bead No. () shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with wire-ties, etc., spaced not over 8" o.c.; stagger in two wings.

c. Casing Bead No. () shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Wire-tie in place.

d. Base Screed No. () shall be installed 6" above the finish floor, unless otherwise indicated. Set screeds level, true to line, in lengths as long as practical, with joints aligned with a suitable splice. Wire-tie in place.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); TRUSSTEEL (metal studs, accessories); THERMAFIBER (insulating wool).

a-1177

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



partitions

a

TRUSSTEEL* Studs and ROCKLATH*

PLASTER BASE

1187

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|---|----------------|----------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | Stl Stud—Gypsum Lath & Plaster—2½" TRUSSTEEL studs 16" o.c.—¾" perf ROCKLATH—¾" 100:2-100:2 gypsum perlite plaster wt 11 width 5" | T-1813-GA-OSU (f) | N/A | | 132 | Excellent fire rating at a low cost | a-1187 |
| 1 hr. est | Stl Stud—Resil Gypsum Lath & Plaster—2½" TRUSSTEEL studs 16" o.c.—TR-1 clips one side & TL-1 clips opp side—¾" ROCKLATH FIRECODE—½" 100:2 gypsum sand plaster—perimeter caulked wt 12 width 4¾" | CK-664-6 (s) | | 41 | 128 | Can improve STC with THERMAFIBER sound blankets stapled to back of direct-applied side per 125-ft test | a-1187 |
| 1 hr. est | Stl Stud—Resil Gypsum Lath & Plaster—¾" TRUSSTEEL studs 16" o.c.—2" THERMAFIBER sound atten bkts—TR-1 clips one side & TL-1 clips opp side—¾" ROCKLATH—½" 100:2-100:2 gypsum sand plaster—perimeter caulked wt 14 width 5½" | USG-125-FT-G&H (s) CK-664-38 (s) GA-2-3-4-FT-G&H (s) Field Test KSO-1090072-b (s) | 49 50 47 | 52 46 | 150 | Est. fire rating based on perf. ROCKLATH. CK-664-38 based on 1" bkts. 2 caulked outlets on ea. side in field test | a-1187 |
| 1 hr. | Stl Stud—Resil Gypsum Lath & Plaster—2½" TRUSSTEEL studs 16" o.c.—TR-1 clips—¾" perf ROCKLATH—½" 100:2 gypsum sand plaster—perimeter caulked wt 13 width 5" | UL Des 24-1 hr (f) Field Test KSO-1090071-b (s) | | 48 | 138 | Sound test with 6 caulked outlets on 2 sides of assembly | a-1187 |
| 1 hr. | Stl Stud—Resil Gypsum Lath & Plaster—1½" TRUSSTEEL studs 16" o.c.—TR-1 clips—¾" perf ROCKLATH—½" 100:2-100:2 gypsum sand plaster wt 13 width 4¾" | T-1559-OSU (f) USG-20-FT-G&H (s) | 47 | | 131 | Can improve performance with sound attenuation wool | a-1187 |
| 1 hr. | Stl Stud—Gypsum Lath & Plaster—2½" TRUSSTEEL studs 16" o.c.—¾" perf ROCKLATH—½" 100:2-100:2 gypsum sand plaster wt 13 width 4½" | T-309-OSU (f) TL-58-7 (s) | 41 | | 125 | Record of proven performance | a-1187 |
| 1 hr. | Stl Stud—Gypsum Lath & Plaster—1½" TRUSSTEEL studs 16" o.c.—¾" perf ROCKLATH—½" 100:2-100:2 gypsum sand plaster wt 13 width 3¾" | T-887-OSU (f) TL-58-7 (s) | 41 | | 123 | Good alternate for most solid partitions | a-1187 |

For wall furring application see page 9.

description

These partition assemblies consist of ROCKLATH Plaster Base, either plain or perforated types, attached to open-web TRUSSTEEL Studs. The lath is either directly fastened to the stud or resiliently attached by means of USG® Resilient Clips. By using these specially designed resilient clips, the two lath and plaster diaphragms are not rigidly coupled to the studs or each other. The excellent sound-isolative efficiency of this system results from this resilient mounting of the plaster membranes and the column of air formed within the TRUSSTEEL Studs (see table above).

TRUSSTEEL Studs utilize a truss design for superior strength, are fabricated in five stud widths (see table page 10) and mill cut to job lengths. Studs are attached to the floor and ceiling by means of clips or runner tracks and stud shoes.

ROCKLATH, a gypsum core faced on both sides with special paper, forms a rigid base for the economical application of gypsum plasters. For this assembly, ROCKLATH is ¾" thick, available in two types, (Perforated or Plain) and two sizes (see Specifications, page 10). In perforated ROCKLATH, ¾" round holes are punched through the lath 4" o.c. in each direction. This provides a mechanical key in addition to the plaster bond, and generally obtains a higher fire resistance rating than with Plain ROCKLATH Plaster Base (see table above).

function and utility


The open web of the truss design provides a maximum of free space for encasing pipes, conduits or ducts, horizontally, vertically or diagonally, without impairing the structural integrity of the assembly.

Sound Isolation—Very good sound isolation at a low cost. Where greater sound isolation is needed, THERMAFIBER® Sound Attenuation Blankets can be inserted in the space between studs.


Fire Protection—Incombustible components provide systems with 1-hour and 2-hour fire-resistance ratings (see table above).

Strength—TRUSSTEEL Studs are formed of No. 7 gauge cold drawn wire, with a tensile strength of 90,000 psi. The resistance moment computed on the section modulus with the high tensile strength produces an exceptionally strong non-load bearing steel stud.


(continued on page 10)



components




regular
runner track




snap-in
runner track




USG metal base
splice plate



USG metal base
& splice plate



1-A
expanded
flange
corner bead



10-A
bull nose
expanded flange
corner bead




USG
4-R
expanded
flange
corner bead




5-A
bull nose
corner bead




3-A
expanded
base screed




TRUSSTEEL stud




TL-1 TRUS-LOK*
field clip



BRIDJOINT* clip B-1




USG stud base clip



TRUSSTEEL
stud shoe




TL-2 TRUS-LOK
starter clip




TRUS-LOK drive-in
starter clip



1" #12 SM screw




USG control joint



TRUSSTEEL
stud shoe

tie wire

regular
runner
track




TRUSSTEEL
stud


snap-in
runner
track



R-SF resilient
starter-finisher




TR-1 resilient
stud clip




USG
6-A
plain
base
screed

USG casing beads
(expanded or short flange)




#66 square edge




USG 7-A
curved point
base screed

#4 or #138
quarter round



#60 semi-square edge



USG cold
rolled channels



USG
8-A
picture
mould




USG
selv-edge
cornerite

see "plaster bases" product catalog for
full description on accessories & sizes


details/resilient attachment

scale: 3" = 1'-0"

ceiling attachments





cross section transverse to furring channel








cross section parallel to furring channel

floor attachment





details


scale: 3" = 1'-0"




isometric




partition wall intersection



borrowed light or cabinet frame



corner




**partition
intersection**


details/direct attachment

ceiling attachments


scale: 3" = 1'-0"




cross section transverse to furring channel



cross section transverse to furring channel






cross section parallel to furring channel



attachment to concrete ceiling slab


floor attachments




details/direct attachment

scale: 3" = 1'-0"


intersecting partitions



partition wall intersection




corner




partition intersection





wall control joint



electrical outlet




fixture attachments




details/door frames


scale: 3" = 1'-0"




**jamb section
resilient partition**



**head section
resilient partition**




**head section
direct attachment**





**jamb section
direct attachment**

wall elevation




jamb anchor inserts/half size




core walls

Core walls, as vertical shafts encasing the usual plumbing supply and waste lines, vent ducts and electrical conduits, require more free space than can be provided within the usual partition assembly.


Core walls are easily constructed using TRUSSTEEL Studs and ROCKLATH, provided proper bracing is used to compensate for the stress skin action of the one side. The non-lathed side of the studs should be braced with $\frac{3}{4}$ " continuous channel girts at the quarter points vertically or 48" o.c. maximum, and $\frac{3}{4}$ " channel bracket mid-girts spaced 36" o.c. horizontally.



TRUSSTEEL stud core wall



closet carrier



lavatory carrier

scale: $1\frac{1}{2} = 1'-0"$

exterior wall furring


| description | relative cost index | comments | folder reference |
|--|---------------------|--|------------------|
| TRUSSTEEL® Studs 16" o.c. cross braced 4' o.c. on the back chord, 3/8" Insulating ROCKLATH attached with TL-1 Clips, 1/2" sanded basecoat plaster, lime putty finish | 185 | Free standing; allows for pipe chase clearance; good vapor barrier | a-1187 |

It is recommended that all exterior masonry walls be furred. Asphaltic or bituminous bonding agents are not recommended as a plaster base. TRUSSTEEL Studs, ROCKLATH and plaster provide an exterior wall furring system that offers a maximum free space for encasement of pipes, ducts or conduits and a finished, readily decorated interior wall surface.


This construction consists of TRUSSTEEL Studs as vertical members braced with horizontal 3/4" channels. A channel at the mid-point between the floor and ceiling is attached to the wall with USG Adjustable Wall Furring Brackets not more than 24" o.c. horizontally. TRUSSTEEL Studs spaced 16" o.c. are wire-tied to these horizontal channels. 3/8" ROCKLATH, 16" x 96", is clipped to the TRUSSTEEL Studs and plastered to 1/2" grounds. The Adjustable Wall Furring Brackets and extra channel at mid-height may be omitted to obtain free-standing furring.

| TRUSSTEEL stud size | maximum height ¹ | |
|---------------------|-----------------------------|-----------------------|
| | braced furring | free-standing furring |
| 1 1/2" | 9' | 6' |
| 2 1/2" | 15' | 10' |
| 3 1/4" | 21' | 14' |
| 4" | 22' | 15' |
| 6" | 26' | 17' |

(1) Based on 16" spacing between studs.




free standing furring



braced furring

adjustable wall furring brackets

1. Attach wall furring brackets not more than 24" o.c. horizontally and 48" o.c. vertically.
2. After attachment, bend bracket to horizontal position.
3. Wire-tie plumbed channel to bracket 1/4" min. (2 1/4" max.) from wall.
4. Bend excess of bracket down.



USG



adjustable wall furring bracket

adjustable wall furring bracket and attachment to TRUSSTEEL studs

details/specifications

scale: 3" = 1'-0"

miscellaneous details



function and utility (continued from page 1)

Economical—The structural integrity, the strength, the sound isolation, the open core wall and fire protection are provided by TRUSSTEEL Stud partitions at a lower cost than by other incombustible assemblies.

Performance—TRUSSTEEL Studs have been used since 1933 and now account for the majority of all non-load bearing steel studs used nationally. The continued high level of use indicates their acceptance based on their performance.

limitations

1. A non-load bearing partition.
2. Stud spacing limited to 16" o.c. (See table for limiting heights.)
3. Door frames must be fabricated and anchored to prevent twisting and impact vibration (see details, page 7).
4. To retain maximum sound isolation, precautions must be taken to prevent sound leakage (see Specifications, below).

finished partition thickness—limiting heights

| stud width | section modulus | direct attach. | resil. attach. | max. partition heights studs 16" o.c. (2) |
|------------|---------------------|----------------|----------------|---|
| 1½" | .0635" ³ | 3¾" | (1) | 9' |
| 2½" | .1056" ³ | 4½" | 5" | 15' |
| 3¼" | .1420" ³ | 5¼" | 5¾" | 21' |
| 4" | .1825" ³ | 6" | 6½" | 22' |
| 6" | .277" ³ | 8" | 8½" | 26' |

(1) Not recommended for resilient attachment. (2) Resilient partition limiting height is 10'.

5. Where mechanically suspended acoustical tile ceilings are used, finished partitions should extend from structural slab to structural slab, closing all openings.

specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55° F. Before lathing, ventilation should be provided to carry off excess moisture.
2. 16" x 96" ROCKLATH Plaster Base is preferred on all TRUSSTEEL Stud installations, and particularly over door frames or other openings.
3. All fire-rated partitions require that TRUSSTEEL Studs be attached to the Regular or Snap-In Runner Track with TRUSSTEEL Stud Shoes at the ceiling.
4. Snap-In Runner Track with studs cut accurately to lengths may be used for floor and ceiling attachment where the construction is non fire-rated. This track may be used at the floor on fire-rated partitions.
5. Except when resilient clips are used, a TRUSSTEEL Stud Partition used as a sound barrier must have a resilient gasket or caulking under the floor and ceiling runner track to seal the voids between track and structural slab. Eliminate cutting holes back to back or adjacent to each other such as electrical outlets. Use sand aggregate only. Caulk perimeter of ROCKLATH and plaster and seal electrical boxes. Door and borrowed light openings are not recommended.
6. THERMAFIBER Sound Attenuation Blankets, stapled to

sound transmission loss

| test no. | method | decibel frequency in cps | | | | | | | | | | | | | | | | | | | | STC | |
|-----------------|--------|--------------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|------|------|------|------|------|------|------|-----|------|
| | | 125 | 160 | 175 | 200 | 250 | 315 | 350 | 400 | 500 | 630 | 700 | 800 | 1000 | 1250 | 1400 | 1600 | 2000 | 2500 | 2800 | 3150 | | 4000 |
| USG-20FT-G&H | Lab | 30 | — | 33 | — | 37 | — | 41 | — | 47 | — | 50 | — | 54 | — | 54 | — | 45 | — | 53 | — | 52 | 47 |
| USG-125FT-G&H | Lab | 35 | — | 49 | — | 49 | — | 52 | — | 56 | — | 56 | — | 59 | — | 49 | — | 48 | — | 54 | — | 60 | 49 |
| KSO-1090072-b | Field | 35 | — | 37 | — | 46 | — | 46 | — | 49 | — | 53 | — | 55 | — | 47 | — | 47 | — | 54 | — | 60 | 47 |
| | | 34 | 37 | — | 40 | 46 | 46 | — | 44 | 48 | 52 | — | 53 | 55 | 47 | — | 42 | 47 | 51 | — | 56 | 60 | 46 |
| CK-664-6 | Lab | 31 | 33 | — | 41 | 40 | 41 | — | 44 | 48 | 48 | — | 50 | 50 | 47 | — | 37 | 43 | 49 | — | 51 | 54 | 42 |
| GA-2-3-4-FT-G&H | Lab | 39 | — | 49 | — | 49 | — | 53 | — | 57 | — | 56 | — | 54 | — | 50 | — | 58 | — | 61 | — | 63 | 50 |
| CK-664-38 | Lab | 36 | 44 | — | 47 | 48 | 49 | — | 50 | 50 | 50 | — | 51 | 52 | 51 | — | 50 | 52 | 53 | — | 55 | 56 | 50 |

the inside face of the ROCKLATH, will improve the sound classification. (See USG Folder on Insulating Wool Products.)

7. Steel door frames should be fabricated from 16 gauge metal, minimum, shop primed. The opening at the trim return should be accurately formed to the overall thickness of the partition.

Base plates, designed with two anchor holes to prevent rotation, should be securely welded to the flanges to dampen door impact vibrations. Floor anchorage should be by two power driven anchors or equivalent per plate.

Four jamb anchors should be provided on each jamb, welded to the trim returns. (See detail page 7.)

Grouting of the door frame is recommended on all installations and is required where heavy or oversize doors are used. The grout shall be raked out to allow the lath and plaster to be inserted into the frame. Under no conditions shall the lath and plaster terminate against the trim return of the door frame.

Door closers are recommended on all oversize doors and doors where the weight of the door (including attached hardware) exceeds 50 lbs.

8. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements, except the floor, and control joints be specified where:

- a. a partition abuts any structural element or dissimilar wall or ceiling assembly.
- b. the partition construction changes within the plane of the partition.

In long partition runs without openings, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling may be used as control joints. For doors less than ceiling height, control joints extending from the center or both corners of the frame to the ceiling may be used.

9. Holes cut in a thin lath and plaster membrane, such as door frames, borrowed lights, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

10. Where a plaster surface is flush with metal, metal bucks, metal windows, or metal base, the plaster should be grooved between the two materials.

11. Fixture attachment—Lightweight fixtures and trim shall be installed by drilling set dry plaster to a minimum depth of ¾" and inserting plastic plugs or other expandable anchors for screw attachment. Heavy fixture attachment is not recommended on resilient lath and plaster surfaces.

Wood inserts for fixture attachment on non-resilient surfaces must always be wire-tied to the inside of the stud chord to prevent breaking up the stress skin of the lath and plaster.

12. Ceramic tile surfaces where required may be installed:

- a. By changing the plaster base from ROCKLATH to Metal Lath (see separate USG Systems Folder).
- b. By adhesive application over the level brown coat gypsum plaster in accordance with the adhesive manufacturer's specifications.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. USG Regular Runner Track — widths 1 5/8", 2 1/2", 3 1/4", 4", or 6" (see Note 3).
- b. USG Snap-In Runner Track—widths 1 5/8", 2 1/2", 3 1/4", or 4" (see Note 4).
- c. TRUSSTEEL Studs—widths 1 5/8", 2 1/2", 3 1/4", 4", or 6" (see Note 3).
- d. TRUSSTEEL Stud Shoes.
- e. R-SF Resilient Starter—Finisher Clip.
- f. TRUS-LOK® Drive-in Starter Clip.
- g. TR-1 Resilient Field Clip.
- h. TL-1 TRUS-LOK Field Clip.
- i. BRIDJOINT® B-1 Field Clip.
- j. USG Stud Base Clip.
- k. USG Metal Base Splice Plate.
- l. USG Metal Base—2 1/2" (18) (20) ga.
- m. USG Corner Bead (specify style from page 2).
- n. USG Self-Furring Junior Diamond Mesh Metal Lath.
- o. USG Selv-edge Cornerite (2" x 2") (3" x 3").
- p. USG Striplath.
- q. USG Casing Bead (specify type from page 2).
- r. USG Base Screed (specify type from page 2).
- s. USG 8-A Picture Mould.
- t. USG Adjustable Wall Furring Bracket.
- u. USG Cold Rolled Channels ¾", 1 1/2", 2".
- v. 18 ga. tie wire.
- w. ROCKLATH Plaster Base shall be (¾" x 16" x 48") (¾" x 16" x 96") regular or perforated.
- x. THERMAFIBER Sound Attenuation Blankets (1") (2") x 24" x 48".

stud system erection

TRUSSTEEL Studs shall be of the size shown on the plans or as herein specified, spaced not to exceed 16" o.c. All partitions shall be aligned accurately according to the partition layouts.

Runner Tracks where required shall be securely attached:

1. **To concrete slabs**—Using concrete stub nail or power driven anchors, spaced not to exceed 24" o.c.
2. **To ceiling grillage**—Wire tie, using a double strand of 18 ga. tie wire, spaced not to exceed 16" o.c.
3. **To plaster or gypsum lath**—Toggle bolt or staple, spaced not to exceed 24" o.c.

Studs shall rest on the floor track and be cut to the nominal ceiling height. With Regular Runner Track and shoes, end of the studs shall be no more than 3" from the ceiling; with Snap-In Runner Track, no more than 3/8" from ceiling.

Studs shall be placed vertically, engaging runner tracks. Studs shall be secured to runner tracks at floor and ceiling with a pair of shoes, crimped or wire-tied in place using a double strand 18 ga. tie wire. Two wire ties of double strand 18 ga. wire shall be used at all studs immediately adjacent to door frames or borrowed light frames.

wall furring erection

On partitions designated as vertical furring the back chord of the TRUSSTEEL Stud must be bridged using continuous 3/4" channels at the third points or not to exceed 48" o.c. and at mid-height. The channels to be saddle-tied at each stud.

Braced furring requires a rigid, secure attachment at 24" o.c. along the mid-point bridging channel to the masonry back-up.

USG Adjustable Wall Furring Brackets, with serrated edges up, shall be attached to the masonry walls at mid-height of the furred wall and spaced not over 4" from columns or other abutting construction and not over 24" o.c. horizontally and 48" o.c. vertically, and as required above and below windows, using (one 2" cut nail in mortar joints of brick clay tile, or cement block or in the field of lightweight aggregate blocks) (5/8" concrete stub nails or power driven nails or other suitable fasteners in monolithic concrete). Fastenings shall be driven through top hole of bracket. The mid-height furring channels shall be laid horizontally on the furring brackets with the legs down, and wire tied to the bracket with a double strand of 18-ga. tie wire. Excess bracket length shall be bent down.

door frames

Studs shall be inserted into the steel door frame, nested in the notches of the jamb anchor clips, and each chord of the stud securely wire tied at each side of each jamb anchor. A second stud shall be installed on each side of the door frame, approximately 2" from the strut stud.

Two 3/4" cold rolled channels shall be used over the head of the door, extending out to engage the third stud on each side. These aligning channels shall be securely tied to the inside of the stud chord at each intersection.

direct plaster base attachment

ROCKLATH (Plain) (Perforated) shall be applied starting at the

bottom with long dimension at right angle to the studs. The lath shall be butted together and clipped in place using (TRUS-LOK Starter Clips TL-2) or (Drive-in Clips) TRUS-LOK Field Clips TL-1, spaced not to exceed 16" o.c. Finishing course of ROCKLATH shall be fastened with 1" #12 flat head self-tapping sheet metal screws driven between vertical stud wires and spaced 8" from ceiling. End joints of lath shall be staggered between studs and aligned using the BRIDJOINT B-1 Field Clips at all lath corners. The lath shall be cut accurately and fitted neatly around all electrical outlets, openings, etc.

resilient plaster base attachment

ROCKLATH (Plain) (Perforated) shall be applied starting at the bottom with long dimension at right angle to the studs. The lath shall be butted together and resiliently clipped in place using Resilient Starter-Finisher Clip R-SF and Resilient Field Clip TR-1, spaced not to exceed 16" o.c. End joints of lath shall be staggered between studs and aligned using the BRIDJOINT B-1 Field Clips at all lath corners.

lathing accessories

a. **Metal Base** 2 1/2 inch (18) (20) gauge, painted, shall be notched to a neat miter in forming all angles. In continuous runs, ends shall be evenly butted and internally spliced with a splice plate. Base shall be securely held in place by engaging the base clips.

b. **Cornerite** (2" x 2") (3" x 3") shall be installed in all interior plaster angles. Staple at the edges.

c. **Metal Corner Bead No.** () shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with galvanized staples, etc., spaced not over 8" o.c.; stagger in two wings.

d. **Casing Bead No.** () shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Staple in place.

e. **Reinforcing.** Install a strip of self-furring diamond mesh lath over joints between dissimilar plaster bases. At all openings, reinforce the corners attaching a 12" x 24" piece of self-furring diamond mesh lath diagonally across the corners. Staple in place.

f. **Base Screed No.** () shall be installed 6" above the finish floor, unless otherwise indicated. Set screeds level, true to line, in lengths as long as practical, with joints aligned with a suitable splice. Staple in place.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ROCKLATH, FIRECODE (plaster base); TRUSSTEEL (metal studs); BRACE-TITE, BRIDJOINT, TRUS-LOK (metal clips); THERMAFIBER (insulation products).

a-1187

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



partitions

a

Metal Studs and ROCKLATH*

PLASTER BASE

1197

A.I.A. File No. 20-B-21

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|----------------|------------|------|---------------------|----------|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. | Met Stud—Gypsum Lath & Plaster—2½" USG studs 24" o.c.—2" THERMAFIBER ins wool bkts—¾" perf ROCKLATH screw att—½" gypsum sand plaster wt 13 width 4¼" | T-1974-OSU (f) | | | | | |
| | | TL-63-268 (s) | 38 | | 141 | | a-1197 |
| 1 hr. est | Met Stud—Gypsum Lath & Plaster—2½" USG studs 16" o.c.—¾" ROCKLATH—MS-1 clips both sides—½" 100:2½ gypsum sand plaster—perimeter caulked wt 14 width 4¼" | CK-664-17 (s) | | 42 | 125 | | a-1197 |
| 1 hr. est | Met Stud—Gypsum Lath & Plaster—2½" USG studs 16" o.c.—¾" ROCKLATH—MS-1 clips both sides—1" THERMAFIBER sound atten bkts—½" 100:2½ gypsum sand plaster—perimeter caulked wt 15 width 4¼" | CK-664-18 (s) | | 48 | 138 | | a-1197 |

wall furring applications

| | | | | | | | |
|---|---|---|---|---|-----|---|--------|
| — | 3½" USG Studs 16" o.c., ¾" Insulating ROCKLATH screw attached, ½" basecoat plaster, lime putty finish (free standing furring) | — | — | — | 175 | Has pipe chase clearance; 9' limiting height; good vapor barrier | a-1197 |
| — | USG Metal Furring Channels 24" o.c., ¾" Insulating ROCKLATH screw attached, ½" sanded basecoat plaster, lime putty finish | — | — | — | 140 | Does not isolate surface from structural stresses. No limiting height | a-1197 |

description

This incombustible non-load bearing partition assembly consists of ROCKLATH Plaster Base, either plain or perforated types, attached to lightweight steel channel studs. The USG Metal Studs, roll-formed in four stud widths (see table at right) from 25-ga. galvanized steel, have punched holes to facilitate electrical installation. Studs, set in steel runner track at the floor and ceiling, are screw-attached or rapidly pierced and crimp-locked in place using the USG Metal Lock Fastener. The ROCKLATH Plaster Base is clip-attached or screw-attached using specially designed MS-1 clips or power-driven, self-drilling steel screws. Stud spacing is 16" o.c. for regular two-coat plaster application. Stud spacing may be 24" o.c. for the screw attachment system but requires 3-coat plaster application for this wider stud spacing.

ROCKLATH, a gypsum core faced on both sides with special paper, forms a rigid base for the economical application of gypsum plasters. For this assembly, ROCKLATH is ¾" thick, available in two types (Perforated or Plain) and two sizes (see Specifications, page 7). In perforated ROCKLATH, ¾" round holes, punched through the lath 4" o.c. in each direction, provide a mechanical key for additional plaster bond.

With Insulating (foil-back) ROCKLATH Plaster Base screwed to USG Metal Studs or Metal Furring Channels, the construction provides an excellent vapor barrier and offers significant insulating value as exterior wall furring (see details, page 6).

function and utility

This assembly provides a simple, easy-to-erect, incombustible, non-load bearing assembly. The stud construction allows vertical chaseways for pipes, conduits and ducts, with some horizontal chaseways through web cutouts.

Fire Resistance—All components are incombustible; 1-hour fire rating available (see table above).

Sound Isolation—The assembly provides up to 48 sound transmission class at low cost (see table above).

Lightweight—The partition has a dead load of approximately 13 psf.

Strength—This assembly with studs spaced 24" o.c. provides adequate strength for normal partition usage.

Economical—Low material costs, speed of erection and versatility of the system provide a cost comparable to or lower than wood frame construction.

limitations


1. A non-load bearing partition.

2. Limiting heights of the partition must be reduced by 15% if a lightweight aggregate basecoat is used.
3. Plaster must be applied by the 3-coat method (see USG Folder on Gypsum Plasters) when 24" stud spacing or perforated lath is used.

partition thickness—limiting heights

| stud width | section modulus | partition thickness | maximum partition height (1) (2) |
|------------|---------------------|---------------------|----------------------------------|
| 1½" | .049 ⁽³⁾ | 3¾" | 10'-0" |
| 2½" | .086 ⁽³⁾ | 4¼" | 13'-6" |
| 3½" | .142 ⁽³⁾ | 5¾" | 17'-0" |
| 4" (3) | .156 ⁽³⁾ | 5¾" | 18'-0" |


(1) Reduce ceiling height by 15% if lightweight aggregate basecoat is used. (2) For 16" stud spacing. Corresponding limiting heights for 24" stud spacing are 9', 12', 16' and 17'3". (3) West Coast only.




A.I.A. File No. 20-B-21

components


see "plaster bases" product catalog for full description on accessories & sizes



USG metal stud




USG runner track




USG metal furring channel




USG 1-A expanded corner bead



TRUS-LOK drive-in starter clip



USG control joint



BRIDJOINT* B-1 field clip




USG 4-R expanded flange corner bead




USG MS-1 clip



USG selv-edge cornerite



USG metal base splice plate




USG metal base & splice plate




USG 3/4" screw-type S


USG casing beads (expanded or short flange)



#4 or #138 quarter round




#60 semi-square




#66 square-edge



USG 5-A bull nose corner bead



pierces & folds light metal



positive & permanent lock

USG metal lock fastener





USG 10-A expanded bull nose corner bead

details


scale: 3" = 1'-0"

ceiling attachments


ROCKLATH edge joint




partition terminal




floor attachments & bases



intersecting walls





scale: 3" = 1'-0"



floor anchor clips
(secure with no less than
two suitable fasteners)—

elevation
cross section thru frame



attachment of runner
track as header or sill




details


core walls

Core walls, as vertical shafts encasing the usual plumbing supply and wastelines, vent ducts and electrical conduits, require more free space than can be provided within the usual partition assembly.


The Metal Stud core wall may be formed of two USG Studs bracketed together with 12"x12" gussets of $\frac{3}{8}$ " ROCKLATH plaster base (see detail). Gussets should be spaced not to exceed 36" o.c. and securely attached to USG Studs using three $\frac{3}{4}$ " Type S Screws. Limiting height for this core wall is 10'.



core wall



closet carrier



lavatory carrier

details

scale: 3"=1'-0"
elevation-no scale

exterior wall furring


It is recommended that all exterior walls be furred. Asphaltic or bituminous bonding agents are not recommended as a plaster base. $\frac{3}{8}$ " square edge Long Length Insulating ROCKLATH and plaster may be used with three different framing methods to provide structural and economic advantages for special furring conditions.

Attached Furring—In this system Long Length Insulating ROCKLATH is screwed to USG Metal Furring Channels erected vertically 24" o.c. direct to unit masonry or monolithic concrete. Plaster is applied to $\frac{3}{4}$ " grounds by the 3-coat method. No limiting height.

Adjustable Furring—In this system Insulating ROCKLATH is furred out up to 3" with brackets and $\frac{3}{4}$ " channels to provide additional pipe chase capacity. Limiting height is 12'. See separate USG Systems Folder, Solid Gypsum Lath & Plaster, for details.


Free-Standing Furring—In this system $3\frac{5}{8}$ " USG Metal Studs are erected vertically 24" o.c. in floor and ceiling runner tracks. Insulating ROCKLATH is attached to the studs by special screws, and plaster is applied by the 3-coat method to $\frac{1}{2}$ " grounds. The assembly allows ample chase width for pipes, conduits or ducts. Limiting height is 8'6".

ceiling attachment



wall elevation—attached furring


floor attachment



attached furring


attached furring

attached furring




metal window—jamb
furred wall plan section

free standing furring




ceiling attachment



base attachment

adjustable wall furring bracket and attachment of ROCKLATH plaster base



specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.

2. Steel door frames should be fabricated from 16 gauge metal, minimum, shop primed. The opening at the trim return should be accurately formed to the over-all thickness of the partition.

Base plates, designed with two anchor holes to prevent rotation, should be securely welded to the flanges to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate.

Four jamb anchors should be provided on each jamb, welded to the trim returns (see detail page 4) and screw attached to the stud. Separate bracing shall be furnished to keep the frame in alignment.

Grouting of the door frame is recommended on all installations and is required where heavy or oversize doors are used. The grout shall be raked out to allow the lath and plaster to be inserted into the frame. Under no conditions shall the lath and plaster terminate against the trim return of the door frame.

Door closers are required on all doors where the weight of the door (including attached hardware) exceeds 50 lbs.

3. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements except the floor, by control joints or other means where:

- a. a partition abuts a structural element or dissimilar wall or ceiling assembly.
- b. the partition construction changes within the plane of the partition.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

4. Holes cut in a thin diaphragm of lath and plaster, such as door frames, borrowed lights, etc., cause a concentration of stresses in the plaster diaphragm. The use of cornerite, striplath and self-furring diamond mesh lath is recommended at the weakened area to distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

5. Where a plaster surface is flush with metal, metal bucks, metal windows, or metal base, the plaster should be grooved between the two materials.

6. Fixture Attachment—Lightweight fixtures and trim shall be installed by drilling set dry plaster to a minimum depth of 3/4" and inserting a plastic plug or other expandable anchor for anchorage of attachment screws. Wood or metal mounting strips for cabinets and shelving should be toggle bolted through the lath and plaster, locating fasteners as near the studs as possible.

7. Ceramic Tile—(Where portland cement plaster base for ceramic tile is specified; self-furring diamond mesh metal lath shall be stapled over the ROCKLATH plaster base with staples, spaced approximately 8" o.c. horizontally and vertically, and portland cement-lime plaster shall be applied in scratch and brown coats to 3/8" grounds over the metal lath as the ceramic tile base). (Ceramic tile may be adhesively applied over the finished gypsum plaster in accordance with adhesive manufacturer's specifications.)

8. Where this partition is used as a sound barrier, it must have caulking under the floor and ceiling runner track to seal the voids between track and structural slab. Eliminate cutting holes back to back or adjacent to each other such as electrical outlets. Use sand aggregate only. Caulk perimeter of plaster. Door and borrowed light openings are not recommended.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. ROCKLATH Plaster Base shall be (3/8"x16"x48") (3/8"x16"x96") Regular or Perforated ROCKLATH for Metal Stud partition; 3/8" Insulating ROCKLATH, 16"x96" for exterior wall furring.
- b. USG Metal Studs (1 5/8", 2 1/2", 3 5/8"); lengths as required.
- c. USG Metal Runner for (1 5/8", 2 1/2", 3 5/8") USG Metal Studs.
- d. USG 3/4" Screws—Type S.
- e. BRIDJOINT* B-1 Field Clips for 3/8" ROCKLATH.
- f. USG Metal Base—2 1/2" (18) (20) ga.
- g. USG Metal Base Splice Plate.
- h. USG Selv-edge Cornerite (2"x2") (3"x3").
- i. USG Striplath.
- j. USG Self-Furring Junior Diamond Mesh Metal Lath.
- k. USG Corner Bead (specify type from page 2).
- l. USG Casing Bead (specify type from page 2).
- m. USG MS-1 Clip.
- n. TRUS-LOK Drive-in Starter Clip.

stud system erection

USG Studs shall be of the size shown on the plans or as herein specified, spaced not to exceed 24" o.c. All partitions shall be aligned accurately according to the partition layout.

USG Runner Tracks where required shall be securely attached:

1. To concrete slabs—Using concrete stub nails or power-driven anchors, spaced not to exceed 24" o.c.
2. To ceiling grillage—Wire tie, using a double strand of 18 ga. tie wire, spaced not to exceed 16" o.c.
3. To plaster or gypsum lath—Toggle bolt or staple, spaced not to exceed 24" o.c.

Studs shall be placed vertically, engaging both floor and ceiling runner tracks. When necessary, studs may be spliced by nesting two studs with a minimum lap of 8" and attaching flanges together with two screws in each flange.

Studs shall be spaced not to exceed (16") (24") o.c. and a stud shall be placed 2" from abutting partitions, internal corners, partition terminals, and other similar locations.

door frames

Studs shall be inserted into the steel door frame, accurately centered, and attached to the anchor clips securely, using a bolt or screw attachment.

1. Where lightweight doors are used a second stud shall be nested to form a box section and anchored together by a pair of screws at each anchor clip.

2. Where heavy doors or oversize doors are used the single stud shall be grouted in place.

Over the metal frames a cut-to-length section of track, with the flanges slit and web bent to allow flanges to overlap adjacent vertical studs, shall be installed as a header to receive studs above the frame.

plaster base attachment

ROCKLATH Plaster Base shall be applied face out starting at the bottom with the long dimension at right angles to the studs. All joints shall be butted together and lath shall be cut accurately and fitted neatly around all electrical outlets, openings, etc. End joints shall be staggered in successive courses. Ends of lath shall fall between studs and be aligned and engaged using the BRIDJOINT B-1 Field Clip. Lath shall be held tightly in place at floor and ceiling runner with TRUS-LOK Drive-in Starter Clips spaced 16" o.c.

For clip attachment—Lath shall be attached to studs with MS-1 Clips, spaced not to exceed 16" o.c., at every intersection of lath edges and studs. Ends of lath at butt joints shall be supported at top, center and bottom with BRIDJOINT B-1 Field Clips.

For screw attachment—Lath shall be attached to each stud with two 3/4" USG Type S screws, placed 2" from lath edges.

wall furring application

USG Metal Furring Channels spaced 24" o.c. maximum, shall be attached to masonry or concrete surfaces vertically with power driven anchors or concrete stub nails spaced 24"

o.c. and staggered on alternate furring channel flanges. End splices shall be provided by nesting channels no less than 8" and securely anchoring to masonry with two fasteners in each flange.

ROCKLATH Plaster Base shall be applied face out with the long dimension at right angles to the furring channels. All joints shall be butted together with end joints staggered on successive courses. All abutting end joints shall occur over the channel web surface and be screw-attached or shall fall between channels and be aligned and engaged using the BRIDJOINT B-1 Field Clip. The lath shall be cut accurately and fitted neatly around all openings. Lath shall be attached to each furring channel with two 3/4" USG Type S screws placed 2" from each lath edge.

lathing accessories

a. **Metal Base 2 1/2" (18) gauge**, painted, shall be notched to a neat miter in forming all angles. In continuous runs, ends shall be evenly butted and internally spliced with a splice plate. Base shall be securely held in place by engaging the base clips.

b. **Cornerite (2"x2") (3"x3")** shall be installed in all interior plaster angles. Staple at the edges.

c. **Metal Corner Bead No. ()** shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with galvanized staples, etc., spaced not over 8" o.c.; stagger in two wings.

d. **Casing Bead No. ()** shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed.

e. **Reinforcing**—Install a strip of self-furring diamond mesh lath over joints between dissimilar plaster bases. At all openings, reinforce the corners attaching a 12"x24" piece of self-furring diamond mesh lath diagonally across the corners.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ROCKLATH (plaster base); THERMAFIBER (insulation products); BRIDJOINT, TRUS-LOK (metal clips).

a-1197

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See USG Construction Section for Sales Offices

partitions

a

USG® Metal Stud Drywall

1207



A.I.A. File No. 20-B-21

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|---|------------|------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | Met Stud—2 layers ½" SHEETROCK FIRECODE "C" gypsum wallbd—1½" USG studs 24" o.c.—2 layers ea side vert appl & screw att joints fin wt 9 width 3½" | U of C 6-15-65 (f) | N/A | | 156 | Most economical 2-hour metal stud drywall partition | a-1207 |
| 2 hrs. | Met Stud—2 layers ⅝" SHEETROCK FIRECODE gypsum wallbd plain or vinyl faced ea side—3½" USG studs 24" o.c.—base layer screw att—face layer lamin or screw att—joints fin or unfin—perim caulked wt 12 width 6½" | UL Des 11-2 hr (f) TL-60-113 (s) | 43 | | 157 | Excellent for corridors | a-1207 |
| 2 hrs. est | Met Stud—2 layers ⅝" SHEETROCK FIRECODE "C" gypsum wallbd—3½" USG studs 24" o.c.—base layer screw att—face layer lamin—1½" THERMAFIBER sound atten blkts—joints fin—perimeter caulked wt 12 width 6½" | USG-109-FT-G&H (s) Field Test KSO-109006-a (s) | 53 55 | | 176 | Highest stc value of metal stud drywall party walls tested | a-1207 |
| 2 hrs. est | Met Stud—⅝" SHEETROCK FIRECODE gypsum wallbd—3½" USG studs 24" o.c.—2 layer—base layer ½" USG min fiber sound dead bd ea side screw att—wallbd face layer lamin & screw att—joints stag & fin—perimeter caulked wt 8 width 5½" | USG-103-FT-G&H (s) Field Test KSO-109006-b (s) | 52 50 | | 186 | | a-1207 |
| 2 hrs. est | Met Stud—2 layers ½" SHEETROCK FIRECODE "C" gypsum wallbd ea side—2½" USG studs 24" o.c.—1½" THERMAFIBER sound atten blkts stapled—wallbd appl vert & joints stag—base layer screw att—face layer strip lamin & Type G screws centered betw studs—joints fin—perimeter caulked wt 10 width 4½" | USG-114-FT-G&H (s) | 54 | | 173 | Best value of drywall metal stud party walls in 50-54 stc range | a-1207 |
| 2 hrs. est | Met Stud Chase Wall—2 layers ½" SHEETROCK FIRECODE "C" gypsum wallbd ea side—1½" USG studs 24" o.c. in 2 rows spaced 6½" apart—½" wallbd gussets spanning chase att to studs at qtr points—wallbd appl vert & screw att—1½" THERMAFIBER sound atten blkts one side—joints stag & fin—perimeter caulked wt 11 width 12" | USG-134-FT-G&H (s) | 55 | | 189 | | a-1207 |
| 1 hr. est | Met Stud—½" SHEETROCK FIRECODE "C" gypsum wallbd—3½" USG studs 24" o.c.—single layer wallbd one side appl vert & screw att—1" THERMAFIBER sound atten blkts one side—2 layers wallbd opp side appl vert & screw att—joints stag & fin—perimeter caulked wt 7 width 5½" | TL-65-252 (s) | 51 | | 156 | | a-1207 |
| 1 hr. | Met Stud—½" SHEETROCK FIRECODE "C" gypsum wallbd—2½" USG studs 24" o.c.—single layer wallbd ea side appl vert & screw att—1½" THERMAFIBER sound atten blkts one side—joints fin—perimeter caulked wt 5 width 4½" | T-3362-OSU (f) TL-65-158 (s) | 47 | | 138 | Sound test based on 3½" studs & 1" wool thickness | a-1207 |
| 1 hr. | Met Stud—½" SHEETROCK FIRECODE "C" gypsum wallbd—1½" USG studs 24" o.c.—2 layer—base layer ½" USG min fiber sound dead bd screw att—wallbd face layer strip lamin & screw att—joints stag & fin—perimeter caulked wt 7 width 3½" | UL Des 23-1 hr (f) USG-57-FT-G&H (s) | 48 | | 167 | Min. value metal stud drywall party wall—sound test made on 3½" studs | a-1207 |
| 1 hr. | Met Stud—⅝" SHEETROCK FIRECODE gypsum wallbd—3½" USG studs 24" o.c.—wallbd single layer screw att 12" o.c.—joints fin—perim caulked wt 6 width 4½" | T-1174-OSU (f) USG-17-FT-G&H (s) | 42 | | 109 | Basic 1-hr. corridor—fire test based on screws 8" o.c. at vert. joints | a-1207 |
| 1 hr. | Met Stud—⅝" SHEETROCK FIRECODE gypsum wallbd—1½" USG studs 24" o.c.—wallbd single layer screw att 12" o.c.—joints fin—perimeter caulked wt 5 width 2½" | U of C 7-31-62 (f) TL-64-29 (s) | 38 | | 108 | Min. 1-hr. drywall partn.—fire test based on screws 8" o.c. at vert. joints | a-1207 |

description

For resilient application, see page 2.

These lightweight non-load bearing partition assemblies consist of steel channel studs, set in floor and ceiling runner tracks and faced each side with one or two layers of SHEETROCK® Gypsum Wallboard. A specially designed self-tapping steel screw with a rust-inhibitive coating is used to attach the wallboard to the studs. The studs, available in four widths (see Specifications, page 7) and lengths to suit job requirements, have holes punched 12" from each end to facilitate electrical installation. The partitions are completed with the PERF-A-TAPE® Joint System and DUR-A-BEAD® Corner Reinforcement.

SHEETROCK for these assemblies is available in three thicknesses and two types (see Specifications). In two-layer con-


(continued on page 6)

double layer
SHEETROCK
gypsum wallboard

THERMAFIBER
sound attenuation
batls to one side

USG metal stud

caulking
(non-hardening)
under face layers
and USG metal runner track



components



USG metal stud

see "gypsum wallboard & joint treatment" product catalogs for full description on accessories



USG metal runner



$\frac{3}{8}$ " USG drywall screw—type S—pan head



$\frac{3}{8}$ " USG drywall screw—type S-12—pan head



1" USG drywall screw—type S—bugle head



$1\frac{5}{16}$ " USG drywall screw—type S—bugle head



$1\frac{5}{8}$ " USG drywall screw—type S—bugle head




$2\frac{1}{4}$ " USG drywall screw—type S—bugle head




$2\frac{1}{4}$ " USG drywall screw—type S—trim head



$1\frac{1}{2}$ " USG drywall screw—type G—bugle head




positive & permanent lock



pierces & folds light metal
USG metal lock fastener




USG control joint #093



no. 100 PERF-A-BEAD* reinforcement




DUR-A-BEAD corner reinforcement



no. 200-A USG metal trim



no. 200-B USG metal trim



PERF-A-TRIM* reinforcement



USG metal trim


resilient application

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|-----------|------------|------|---------------------|----------|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. est | Met Stud—2 layers $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd— $\frac{3}{8}$ " USG studs 24" o.c.—3" THERMAFIBER ins wool blkts—2 layers wallbd lamin one side—opp side 2 layers wallbd separ by RC-1 chan spaced horiz 24" o.c. screw att—face joints fin wt 12 width $6\frac{1}{2}$ " | TL-62-212 | (s) | 51 | 187 | | a-1207 |
| 2 hrs. est | Met Stud—2 layers $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd— $\frac{3}{8}$ " USG studs 24" o.c.—2 layers wallbd screw att one side—opp side 2 layers wallbd separ by RC-1 chan spaced horiz 24" o.c. screw att—face joints fin wt 12 width $6\frac{1}{2}$ " | TL-62-180 | (s) | 50 | 173 | | a-1207 |


details

scale: 3" = 1'-0"


ceiling attachments



floor attachments & bases





wall plan sections




details

scale: 3" = 1'-0"


intersecting walls



partition corner




partition intersection




partition relief column intersection


fixture attachment



light




medium




heavy

metal door frame



jamb



elevation cross section through frame




metal stud chase wall


The USG Metal Stud Chase Wall construction consists of a double row of metal studs with gypsum board cross braces between the rows. Double layer $\frac{1}{2}$ " SHEETROCK Wallboard is screw-applied both sides of studs and $\frac{1}{2}$ " THERMAFIBER Sound Attenuation Blankets are stapled to the back side of one base layer. The construction offers a 55 STC suitable for party walls, and a 2-hour fire-resistance rating is estimated when $\frac{1}{2}$ " SHEETROCK FIRECODE "C" Wallboard is used.

This construction is designed for use where greater core widths are needed for pipe chase enclosures and other service installations. It provides the same advantages as the USG Metal Stud Partition System such as speed of erection and low cost, and permits the use of one component system throughout a building.


The limiting thickness for this chase wall is 15"; limiting height is 10'. The minimum size of the SHEETROCK Gypsum Wallboard face panels or base panels should be $\frac{1}{2}$ " x 4' x ceiling height.




elevation



closet carrier



lavatory carrier



drywall soffit


The USG Drywall Soffit assembly consists of electro-galvanized steel channel runners and studs faced with SHEETROCK Gypsum Wallboard, screw attached. It is a lightweight, fast and economical method of filling over cabinets or lockers and of housing overhead ducts, pipes or conduits. The system permits constructing soffits with depths of 48" and widths to 72" without supplementary vertical studs.

Construction recommendations—Maximum dimensions (1):

| gypsum board thickness (2) | metal stud size | maximum width | max. depth for max. width shown |
|----------------------------|-----------------|---------------|---------------------------------|
| 1/2" | 1 5/8" | 60" | 48" |
| 1/2" | 2 1/2", 3 3/8" | 72" | 36" |
| 5/8" | 1 5/8" | 60" | 30" |
| 5/8" | 2 1/2", 3 3/8" | 72" | 18" |

(1) The construction is not designed to support loads other than its own dead weight and should not be used where it may be subjected to excessive abuse.

(2) The double-layer wallboard system and 3/8" thick wallboard are not recommended for this construction.



description (continued from page 1)

struction USG Mineral Fiber Sound Deadening Board or BAXBORD* Gypsum Backing Board may be used as a base layer. SHEETROCK FIRECODE* Gypsum Wallboard, with a specially formulated core, obtains higher fire resistance ratings than plain SHEETROCK Wallboard (see table on page 1).

function and utility

Adaptable for use as party walls, corridor walls and interior partitions in virtually every type of new construction—commercial, institutional, industrial and residential—or alteration work for permanent space division. With single layer SHEETROCK, applied horizontally or vertically, the system offers very economical partitioning. With double-layer construction, excellent resistance to fire and sound transmission is available.

Fire Resistant—Constructed of incombustible components. Established fire ratings: 1 hour, with single-layer 5/8" SHEETROCK FIRECODE Wallboard; 2 hours, with double-layer 1/2" FIRECODE "C" or 5/8" FIRECODE Wallboard applied each side of USG Metal Studs.

Sound Isolation—STC ratings available up to 55 for double-layer, 42 for single-layer. Where greater sound isolation is desired for party walls, THERMAFIBER* Sound Attenuation Blankets are inserted in the stud cavity (see table, page 1).

Lightweight—With 3 5/8" studs and single-layer 5/8" SHEETROCK applied each side, the partition weighs approx. 6 psf; with double-layer 1/2" FIRECODE "C" each side and 1 5/8" studs, only 9 psf—making possible savings in structural requirements.

Economical—Low material cost and speed of erection provide realistic and competitive construction costs.

limitations

(1) Non-load bearing. (2) The partitions should not be used where normally exposed to excessive moisture or humidity. (3) Limiting heights: 1 5/8" stud, 9'; 2 1/2" stud, 12'; 3 3/8" stud, 16'; 4" stud, 17' 3". (4) Maximum stud spacing is 24" o.c. Exception: Where single layer 3/8" board is applied each side, maximum stud spacing is 16" o.c.

specifications — notes to architect

1. Metal door and borrowed light frames should be formed from 18-ga. steel minimum, shop primed. The opening between the trim returns should be accurately formed to the overall thickness of the partition.

Floor anchor plates should be 14-ga. steel minimum, designed with two anchor holes to prevent rotation and welded to trim flanges to dampen door impact vibrations. Floor anchorage should be by two power driven anchors or equivalent per plate. Jamb anchor clips should be formed of 18-ga. steel minimum, welded in the jamb and head (see detail page 4), and screw attached to the stud.

Door frame struts, when required, should be 1/4" minimum thickness, hot rolled steel bar stock and of sufficient width to completely fill doorstop void, anchoring jamb securely. All door frame struts should be supplied as an integral part of the door frame.

All one-piece metal door and borrowed light frames should be spot grouted at the jamb anchor clips, after the stud and before the wallboard is installed. A grouting of DURABOND or USG

sound transmission loss

| test no. | method | decibel frequency in cps | | | | | | | | | | | | | | | | | | | | STC | |
|----------------|--------|--------------------------|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|------|------|------|------|------|------|------|------|------|
| | | 125 | 160 | 175 | 200 | 250 | 315 | 350 | 400 | 500 | 630 | 700 | 800 | 1000 | 1250 | 1400 | 1600 | 2000 | 2500 | 2800 | 3150 | | 4000 |
| TL-60-113 | Lab | 35 | — | 37.5 | — | 43 | — | 48 | — | 50 | — | 50 | — | 50 | — | 47.5 | — | 43.5 | — | 49 | — | 54.5 | 43 |
| KSO-109006-a | Field | 36 | — | 47 | — | 47 | — | 49 | — | 51 | — | 53 | — | 57 | — | 59 | — | 57 | — | 55 | — | 62 | 55 |
| | | 36 | 41 | — | 48 | 47 | 46 | — | 50 | 51 | 52 | — | 54 | 57 | 58 | — | 58 | 57 | 55 | — | 57 | 62 | 54 |
| USG-109-FT-G&H | Lab | 35 | — | 42 | — | 47 | — | 47 | — | 50 | — | 50 | — | 58 | — | 61 | — | 61 | — | 58 | — | 61 | 53 |
| USG-103-FT-G&H | Lab | 34 | — | 36 | — | 44 | — | 46 | — | 52 | — | 56 | — | 57 | — | 60 | — | 53 | — | 53 | — | 55 | 52 |
| USG-57-FT-G&H | Lab | 30 | — | 33 | — | 43 | — | 42 | — | 50 | — | 57 | — | 56 | — | 57 | — | 59 | — | 51 | — | 51 | 48 |
| USG-17-FT-G&H | Lab | 26 | — | 32 | — | 36 | — | 38 | — | 42 | — | 49 | — | 53 | — | 53 | — | 40 | — | 41 | — | 47 | 42 |
| TL-64-29 | Lab | 22 | — | 27 | — | 32 | — | 36 | — | 40 | — | 42 | — | 42 | — | 49 | — | 42 | — | 35 | — | 45 | 38 |
| KSO-109006-b | Field | 31 | — | 37 | — | 42 | — | 44 | — | 51 | — | 54 | — | 59 | — | 59 | — | 58 | — | 55 | — | 63 | 50 |
| | | 31 | 32 | — | 39 | 42 | 42 | — | 47 | 51 | 52 | — | 56 | 59 | 59 | — | 59 | 58 | 56 | — | 58 | 63 | 52 |
| USG-114-FT-G&H | Lab | 32 | — | 39 | — | 44 | — | 48 | — | 55 | — | 56 | — | 57 | — | 59 | — | 62 | — | 58 | — | 56 | 54 |
| USG-134-FT-G&H | Lab | 33 | — | 43 | — | 48 | — | 49 | — | 56 | — | 57 | — | 60 | — | 60 | — | 63 | — | 60 | — | 60 | 55 |
| TL-65-252 | Lab | 32 | — | 36 | — | 39 | — | 45 | — | 50 | — | 54 | — | 54 | — | 56 | — | 57 | — | 50 | — | 50 | 51 |
| TL-65-158 | Lab | 27 | — | 31 | — | 37 | — | 41 | — | 48 | — | 53 | — | 52 | — | 55 | — | 54 | — | 46 | — | 47 | 47 |

Ready-Mixed Joint Compound should be applied just before the face layer is inserted to securely adhere the wallboard to the frame. Under no conditions should the wallboard terminate against the trim return of the door frame.

Door closers and bumpers are required on all doors where the weight of the door (including attached hardware) exceeds 50 lbs.

2. Non-load bearing drywall partitions will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements except the floor by control joints or other means where: (a) A partition abuts any structural element or dissimilar wall or ceiling assembly; (b) The partition construction changes within the plane of the partition.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

3. Holes cut in a thin wallboard membrane such as door frames, borrowed lights, etc., cause a concentration of stresses in the wallboard. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

4. Additional chases for electrical conduit or pipe can be provided by cutting round holes no greater in size than 75% of the stud width, located in the center of the stud web and spaced at least 12" apart. Additional holes should not be cut where a fire rating is required.

5. Ceramic Tile—The use of SHEETROCK W/R Gypsum Wallboard is recommended as a base for the adhesive application of ceramic, metal and plastic tile.

6. Where wood base is required it should be applied with trim head screws placed at each stud location and midway between stud locations (12" o.c.) and at other points where required.

7. Where this partition is used as a sound barrier, the use of non-hardening caulking material to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure is recommended. Eliminate cutting holes back to back and adjacent to each other. Door and borrowed light openings are not recommended when this partition is used as a party wall.

8. The addition of 3" x 23" x 96" THERMAFIBER Insulation Blankets or 1" or 1½" x 24" x 48" THERMAFIBER Sound Attenuation Blankets in the stud cavity, pressed tightly in place and stapled to the back side of one face of the partition will increase the sound transmission loss of the partition.

9. Fixture attachment—Wood or metal mounting strips for cabinets or shelving should be toggle bolted through the wallboard locating fasteners as near studs as possible.

10. The 1½" USG Drywall Screw Type G is not recommended for use as temporary fastening when laminating two-ply ¾" SHEETROCK (or BAXBORD) Double Wall. In this assembly use scaffold nails through gypsum blocks at third points vertically.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 70°F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period. All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Joint Treatment Folder for PERF-A-TAPE Joint System Specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. USG Metal Studs—Nos. 158 (1 ⅝"), 212 (2 ½"), 358 (3 ⅝"), 400 (4").
- b. USG Metal Runner—Nos. 158 (1 ⅝"), 212 (2 ½"), 358 (3 ⅝"), 400 (4").
- c. Faceboards—(⅜"), (½") (⅝") thick, 48" wide Tapered Edge SHEETROCK (Regular) (FIRECODE) (FIRECODE "C"), lengths as required.
- d. Backing Board—(⅜") (½") (⅝") thick, (24") (48") wide BAXBORD (Regular) (FIRECODE), 8' lengths; or ½" USG Mineral Fiber Sound Deadening Board.
- e. Insulation—THERMAFIBER Sound Attenuation Blankets (1½" x 24" x 48") (1" x 24" x 48").
- f. Laminating Material—PERF-A-TAPE Joint Compound (embedding type) or USG Laminating Adhesive.
- g. Joint Treatment—PERF-A-TAPE or DURABOND* Joint System.
- h. Fasteners (specify type from page 2).
- i. USG Metal Trim (specify type from page 2).
- j. USG Corner Bead—DUR-A-BEAD, PERF-A-BEAD* (specify type from page 2).
- k. USG Control Joint No. 093.
- l. Caulking—Presstite 579.64 Mastic as manufactured by Presstite Division of Interchemical Corporation or equal.

stud system erection

All partitions shall be aligned accurately according to the partition layout. Floor and ceiling runners shall be securely attached 24" o.c. to concrete slabs with concrete stud nails or power driven anchors, to suspended ceilings with toggle or molly bolts, to wood framing with suitable fasteners.

Studs shall be positioned vertically in the runners, spaced no greater than (16") (24") o.c. Anchor all studs located adjacent to door and window frames, partition intersections and corners to runner flanges with USG Metal Lock Fastener or by positive screw engagement with ⅜" Type S, pan head screws through each stud flange and runner flange. When necessary, studs shall be spliced by nesting two studs with a minimum lap of 8" and attaching flanges together with two screws in each flange.

Studs shall be located no more than 2" from all door frame jambs, abutting partitions, partition corners and other construction. Studs shall be securely anchored to the jamb and head anchor clips of each door or borrowed light frame by bolt or screw attachment. Over metal door and borrowed light frames install a cut-to-length section of runner with the flanges slit and web bent to allow flanges to overlap adjacent vertical studs and securely screw-attach to adjacent studs. A cut-to-length stud extending from door frame header to ceiling runner shall be positioned at vertical joints over door frame.

panel erection

Gypsum wallboard shall be applied with long dimension (parallel) (at right angles) to framing members, and all abutting ends and edges (except in horizontal application) shall occur over stud flanges. Wallboard of the maximum practical length shall be used to minimize end joints. All end joints shall be neatly fitted and staggered. Joints on opposite sides of the



partition shall be so arranged as to occur on different studs. Wallboard shall be cut neatly to fit around all outlets and switch boxes. Work done by this contractor shall be coordinated properly with that done by other trades.

Screw spacing shown below is for non-rated construction. For fire-rated construction obtain screw spacing from test report.

For vertical single-layer wallboard application 1" USG Drywall Screws Type S shall be spaced a maximum of 12" o.c. in the field of the board and 8" o.c. staggered along the vertical abutting edges.

For horizontal single-layer wallboard application, 1" USG Drywall Screws Type S shall be spaced a maximum of 12" o.c. in the field of the board and 12" o.c. along the abutting end joints.

For two-layer job laminated construction, apply the base layer vertically with 1" USG Drywall Screws Type S spaced 12" o.c. in the field of the board and 8" o.c., staggered at the vertical joints of the board. Apply the face layer vertically with vertical joints, laminate and hold in place with supplemental fastening until adhesive is dry.

For two-layer construction with screw attachment of the face layer, apply the base layer vertically with vertical joints staggered on opposite sides of the partition and screw-attach with 1" USG Drywall Screws Type S spaced 16" o.c. in the field and vertical joints of the board. Apply the face layer vertically with vertical joints offset 24" from base layer joints and staggered on opposite sides of the partition. Attach with (1 5/16") (1 3/8") USG Drywall Screws Type S spaced 16" o.c. in the field and vertical joints of the board.

mineral fiber sound deadening board erection

For two layer construction with mineral fiber sound deadening board, the base layer of sound deadening board shall be applied vertically with joints staggered on opposite sides of the partition. Board shall be attached to each side of metal studs with 1" USG Drywall Screws Type S spaced not to exceed 27" o.c. along vertical joints and at quarter and mid-points of panel height along intermediate stud. Place two screws at each end of board through runner 1" from each vertical edge. Face layer shall be applied vertically with joints staggered from base layer joints and laminated to base layer using PERF-A-TAPE Joint Compound (embedding type). Face boards shall be fastened around perimeter with (1 5/16") (1 3/8") USG Drywall Screws Type S spaced 12" o.c.

chase wall erection

Chase wall partitions shall be aligned accurately according to the partition layout. A double row of floor and ceiling runners shall be securely attached 24" o.c. to concrete slabs with concrete stub nails or power-driven anchors, to suspended ceilings with toggle bolts or staples, or to wood framing with suitable fasteners.

A double row of No. 158 metal studs shall be positioned vertically in the runners so that studs are opposite each other in pairs with the flanges pointing in the same direction. Space no greater than 24" o.c. Anchor all studs to runner flanges with

USG Metal Lock Fastener or by positive screw engagement through each stud flange and runner flange.

Cross bracing between the rows of studs shall be cut from (1/2") (3/8") SHEETROCK into minimum 12" by chase width pieces and screw-attached to the stud webs at quarter points in the partition height, with USG Drywall Screws Type S—spaced 8" o.c. in each stud web or a minimum of three screws per stud web.

drywall soffit erection

Drywall soffits shall be aligned accurately according to the partition layout. USG No. (158) (212) (358) metal runners shall be securely attached 24" o.c. to concrete slabs with concrete stub nails or power driven anchors, to suspended ceilings with toggle bolts or staples, or to wood framing with suitable fasteners. On stud walls, space fasteners to engage each stud. On ceilings, place fastener close to outside face of runner.

Face panels shall be (1/2") (3/8") SHEETROCK Gypsum Wallboard. Fasten vertical face panel to web of face corner runner and flange of ceiling runner with 1" USG Drywall Screws Type S spaced 12" o.c. Insert USG No. (158) (212) (358) Metal Studs between face corner runner and sidewall runner and attach alternate studs to runners with the USG Metal Lock Fastener. Bottom face panel shall be attached to metal studs and runners with 1" USG Drywall Screws Type S spaced 12" o.c. Screws in the face corner runner shall be at least 1" from the edge of the SHEETROCK panel.

wallboard accessories

a. **PERF-A-TAPE or DURABOND Joint System** shall be used on all face board joints and internal angles formed by the intersections of walls and ceilings.

b. **Laminating Material** shall be PERF-A-TAPE Joint Compound (embedding type) mixed according to manufacturer's directions spread to provide adhesive beads 1/2" high x 3/16" wide at the base and spaced 4 1/2" o.c., or USG Laminating Adhesive applied in strips, 2" o.c., running continuously from floor to ceiling. Each strip shall consist of four beads 1/2" high and 3/8" wide at the base and spaced 1 1/2" to 2" o.c.

c. **Metal Corner Bead No. ()** shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.

d. **Metal Trim No. ()** shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.

e. **Fasteners** shall be as shown on drawings or as herein specified. Fasteners shall be driven not less than 3/8" from ends or edges of wallboard to provide uniform dimple not over 1/32" deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

f. **Control Joints** shall be provided in the face layer as indicated and where detailed. Staple in place.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products, adhesives); SHEETROCK, FIRECODE (gypsum wallboard); BAXBORD (gypsum backing board); PERF-A-TAPE, DURABOND, (joint treatment); DUR-A-BEAD, PERF-A-BEAD, PERF-A-TRIM (corner reinforcement); THERMAFIBER (insulation products).

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

a-1207



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Specifier
for
Sales
Offices



partitions & wall furring

a**STRUCTICORE* Systems**

PRE-ASSEMBLED GYPSUM PANELS

1257

| fire rating | description | test no. | sound rating |
|-------------|--|---|--------------|
| 1-1/2 hrs. | Double Wall Drywall--two rows 134 STRUCTICORE panels spaced 2-1/2" apart--1" THERMAFIBER* sound attenuation blankets stapled to back side of one row--steel runners--joints finished. weight 9 width 6" | U of C 5-13-66(f) TL-66-68(s) | 51 stc |

A.I.A. File No. 20-B-21

description

These systems are incombustible, lightweight, non-load bearing assemblies of STRUCTICORE Gypsum Panels screw attached to metal floor and ceiling runners. 134 STRUCTICORE Panels are 1-3/4" thick, 4' wide, and available in standard lengths. One part of the panel consists of a 3/8" thick (nom.) tapered edge gypsum wallboard with seven integrally formed gypsum ribs spaced 6-1/2" o.c. This 1-1/4" thick face layer is factory-laminated to a 1/2" thick gypsum wallboard back layer completing the panel. The panels are quickly and easily erected as either sound-resistant double wall partitions or free-standing wall furring.


Double Wall System--For 1-1/2-hour fire rated construction, 134 STRUCTICORE Panels are attached with 2-1/4" USG Brand Screws-Type S to both sides of #212 USG Metal Runners. 1" THERMAFIBER Sound Attenuation Blankets are stapled to the back of one panel row. A 3/4"x3" gypsum spline is inserted in the core cavity at each panel joint. Panel edges are secured to the spline with 1-1/2" Type G Screws. With 1-3/8"x7/8" Metal Angle Runners, the panels may be spaced to provide additional core width for plumbing chases and mechanical installations without destroying the sound control properties of the assembly. The partition when caulked and completed with a U.S.G. joint compound and PERF-A-TAPE* Reinforcement is recommended for party walls and corridor walls. Where these fire and sound resistance properties are not required, wool may be omitted or wood runners used.

Wall Furring System--A single row of 134 STRUCTICORE Panels is screw-attached to metal angle floor and ceiling runners spaced at least 1/2" from the exterior wall. This free-standing furring has these thermal resistance values: 1.71 for Regular Panels, 2.67 for Regular Panels with 3/4" or more still air space, 4.51 for Foil-Back Panels with 3/4" or more foil-faced still air space. Vertical panel joints are reinforced with gypsum splines and concealed with a U.S.G. joint treatment system (see page 4 for details).


function and utility

These systems are suitable for use with concrete, steel or wood framing in all types of buildings--commercial, institutional, industrial as well as multi-family dwellings--where they offer the following features:

Fire Resistant--The STRUCTICORE double wall system with its incombustible components



double partition



wall furring

*Reg. U. S. Pat. Off.

offers a 1-1/2-hour fire resistance rating.

Sound Control--The 51 STC provided by the double wall system with wool makes this assembly ideally suited for party and corridor walls.

Simplified Erection--Factory-fabricated panels are delivered ready for installation. Erection is fast, requiring simple tools, established techniques and few components.

Lightweight--Finished partition weighs only 9 psf.

Easily Decorated--Construction eliminates fasteners and end joints in field of panels. Panels are ideal for any type of decoration.

Economical--The low material cost, elimination of conventional wood or metal stud framing and fast erection combine to make this one of the most economical fire and sound-resistant party wall constructions.

limitations

1. A non-load bearing construction.
2. Limiting height is 10'.
3. When used in such applications as shower stalls and tub enclosures, to provide protection against moisture, 1/2" SHEETROCK* W/R Gypsum Wallboard shall be job-laminated to the STRUCTICORE Panels as a base for ceramic, metal and plastic tile or other suitable finishes.

tools required

- (1) Circular power saw with 8" carbide-tipped saw blades; (2) four-foot level; (3) screw gun.


| <u>sound transmission loss</u> | | | | | | | | | | stc 51 |
|--------------------------------|------|------|------|------|------|------|------|-----|-----|-----------|
| frequency, cps | 125 | 160 | 200 | 250 | 315 | 400 | 500 | 630 | 800 | |
| transmission loss, db | 35 | 39 | 40 | 42 | 47 | 49 | 51 | 51 | 48 | |
| frequency, cps | 1000 | 1250 | 1600 | 2000 | 2500 | 3150 | 4000 | | | |
| transmission loss, db | 50 | 54 | 56 | 53 | 53 | 55 | 55 | | | |

STRUCTICORE Systems


details/double wall partition

scale: 3" = 1'-0"


ceiling attachment




typical joint detail





floor attachment



electrical outlet



wall plan sections





STRUCTICORE Systems


scale: 3" = 1'-0"

details/double wall partition


metal door frame



section B




section A




core wall

miscellaneous details



masonry intersection





closet carrier

details/wall furring

scale: 3" = 1'-0"



STRUCTICORE Panels offer an excellent free-standing exterior wall furring with the necessary open space for encasement of pipes, ducts or conduits and a finished, easily decorated wall surface. With Foil-Back STRUCTICORE Panels, the system is effective as a vapor barrier and offers significant insulating value. Since there is no contact with the exterior wall, possibilities for photographing of joints and fastener heads are minimized. Limiting height is 10'.

ceiling attachment




metal window jamb


floor attachment



outside corner



inside corner



typical control joint

specifications

notes to architect

1. Where this partition is used as a sound barrier, the integrity of the partition should not be voided by doors and borrowed lights. Metal door frames if required should be three-piece knockdown type installed according to manufacturers' directions (see details page 3).

2. Non-load bearing partitions will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that the panels be isolated from all structural elements, except the floor, by control joints or other means where: (a) a partition abuts any structural element or dissimilar wall or ceiling assembly; (b) the partition construction changes within the plane of the partition.

In long runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

3. Electrical Fixtures -- Electrical boxes should be gangable, equipped with ears and should be secured to panel faces with sheet metal drywall box supports or integral clamps on receptacle boxes.

4. Fixture Attachment -- Lightweight fixtures and trim should be installed using plastic plugs or other expandable anchors for screw attachment. Medium and heavyweight fixtures should be supported from blocking inserted in the panel cavity.

5. Where this partition is used as a sound barrier, the use of caulking to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure is recommended. Eliminate cutting holes back to back and adjacent to each other.

general conditions

In cold weather during the period of joint treatment, temperatures within the building shall be maintained uniformly within the range of 55° to 70°F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. Gypsum Panels--134 STRUCTICORE Partition Panels (Regular) (Foil-Back) 1-3/4" thick x 48" wide--lengths as required.
- b. USG Metal Studs--No. 212 (2-1/2").
- c. USG Metal Runner--No. 212 (2-1/2"), 1-1/4" legs.
- d. Metal Angle Runners--1-3/8" x 7/8" x 22 ga.
- e. DUR-A-BEAD* Corner Bead--No. (101)(102)(103).
- f. USG Metal Trim--No. (200-A) (200-B).
- g. USG Brand Screws--2-1/4" Type S, Bugle Head; 1-1/2" Type G.
- h. Joint Treatment--USG Ready Mixed Joint Compound--All Purpose and PERF-A-TAPE Reinforcing Tape.
- i. Insulation--1" THERMAFIBER Sound Attenuation Blankets, 24" x 48".
- j. Caulking--Presstite 579.64 Mastic as manufactured by Presstite Division Interchemical Corporation or equal.
- k. Splines--3/4" x 3" formed by folding 3/8" gypsum wallboard.
- l. Control Joint--USG Control Joint No. 093.

partition erection

All partitions shall be aligned accurately according to the partition layout.

Floor and ceiling runners shall be shaped as detailed in the drawings and securely attached to floor and ceiling constructions with suitable fasteners spaced 24" o.c. Panels shall be cut to fit accurately between floor and ceiling runners and installed vertically with the ribbed board facing out.

Panels shall be fastened to ceiling and floor runners with 2-1/4" USG Brand Screws - Type S driven through the panel ribs 13" o.c. (Note: rib positions are marked on panel face with small dots.)

Panel joints shall be offset 24" on opposite sides of the partition and have 3/4" x 3" full-length gypsum splines, made from two pieces 3/8" gypsum board, inserted in the panel core. Panels shall be attached to splines with 1-1/2" Type G Screws spaced 16" o.c. A 3/4" thick gypsum spline shall be inserted in panel core to back-up face layer for screw fastening at partition intersections, corners and around door frames.

Panels shall be cut neatly to fit around all outlets and switch boxes. Suitable fastener anchorage shall be provided as required for the attachment of shelves and cabinets.

Work done by this contractor shall be coordinated properly with that to be done by other trades.

wall furring erection

Floor and ceiling metal angle runners shall be accurately aligned according to the partition layout and securely fastened with suitable fasteners not less than 24" o.c.

Panels shall be cut to fit accurately between floor and ceiling runners and installed vertically with the ribbed board facing out. Panels shall be fastened to ceiling and floor runners with

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

100-1-100-1-100-1

2-1/4" USG Brand Screws - Type S driven through panel ribs 13" o.c. Panel joints and corners shall have 3/4" x 3" full-length gypsum splines inserted in the panel core. Panels shall be attached to splines with 1-1/2" Type G Screws spaced 16" o.c. A 1 x 2 wood spline may be used as an alternate to the gypsum spline and shall be attached with 1-1/4" USG Screws Type W, 16" o.c. or with 4d cement coated cooler nails, 10" o.c.

Panels shall be cut neatly to fit around all outlets and switch boxes. Suitable fastener anchorage shall be provided as required for the attachment of shelves and cabinets.

Work done by this contractor shall be coordinated properly with that to be done by other trades.

accessories

- a. A U.S.G. joint compound and PERF-A-TAPE reinforcement shall be used on all face panel joints and internal angles formed by the intersections of walls and ceilings.
- b. DUR-A-BEAD Corner Reinforcement No. () shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.
- c. Metal Trim No. () shall be securely installed where indicated. Finish with a U.S.G. joint compound, as required.
- d. Fasteners, as shown on drawings or as herein specified, shall be driven not less than 3/8" from edges and ends of panels to provide uniform dimple not over 1/32" deep.
- e. Control Joints shall be provided in the face layer as indicated and where detailed. Staple in place.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: **STRUCTICORE** (gypsum panels), **USG** (metal products); **PERF-A-TAPE** (reinforcement); **DUR-A-BEAD** (corner reinforcement); **THERMAFIBER** (insulation products); **SHEETROCK** (wallboard).

a-1257

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

partitions

a

12a
Ub
SHEETROCK® Demountable System
 GYPSUM WALLBOARD

1287

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|---|------------|----------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. | Mov Demountable Partn—½" vinyl faced SHEETROCK FIRECODE "C" gypsum wallbd & battens screw att—2½" USG met studs 24" o.c.—2" THERMAFIBER sound atten blkts wt 6 width 3½" | UL Des 21-1 hr (f) TL-63-127 (s) | 49 | | 187 | Low cost—movable by owner's crew—only met. stud movable partn. with high sound & fire rating | a-1287 |
| N/A | Mov Demountable Partn—½" vinyl faced SHEETROCK FIRECODE gypsum wallbd & battens screw att—2½" USG met studs 24" o.c. wt 5½ width 3½" | TL-63-126 (s) | 42 | | 172 | Same as TL-63-127 without wool—note stc difference | a-1287 |

description

The SHEETROCK Demountable Partition is a non-load bearing movable wall system designed for use in all types of commercial, industrial and institutional construction. This partition is a structurally sound, virtually 100% reusable wall that offers complete design freedom for ceiling, cornice or bank rail height.

Individual wall sections are erected from lightweight 2½" USG® Metal Studs spaced 24" o.c., set in USG Metal Runners, and faced both sides with screw attached Regular, Vinyl Panel, or Custom Vinyl SHEETROCK Gypsum Wallboard. Fasteners and abutting SHEETROCK edges are concealed with anodized aluminum battens and exterior corners fabricated to accommodate a vinyl insert giving the wall a modern, attractive appearance. Matching aluminum base, wall-ceiling trim, door assembly components and glazed opening components are the only other accessories required to complete this highly versatile partition system.

By using predecorated SHEETROCK Vinyl Panel or Custom Vinyl wallboard, available in a wide range of rich decorator colors, finishing time is reduced. The durable, washable surface of this material is easy to maintain and complements any commercial interior.

function and utility

Versatile—Suitable for use in modernization or in all types of new construction. The simplicity of design offers a completely flexible, virtually 100% reusable, movable partition. Utilities such as electrical outlets or communications wiring are easily installed, relocated and augmented. Vinyl Panel, Custom Vinyl and Regular SHEETROCK Gypsum Wallboard satisfies every design requirement and provides complete flexibility of finish. Available in ceiling height, cornice height and bank rail height assemblies.

Fire Resistant—Constructed of incombustible components; a 1-hour fire resistance rating has been established.

Sound Control—The construction described (see table above) has a 49 sound transmission class rating.

Lightweight—5.5 lbs. per sq. ft. when faced each side with ½" SHEETROCK.


Economical—The small number of components required for this movable partition permits fast erection and saves job material costs. The ease of dismantling and relocation saves costly business interruptions and inconvenience during remodeling.

sound transmission loss

| test no. | method | decibel frequency in cps | | | | | | | | | | STC | |
|-----------|--------|--------------------------|-----|-----|-----|-----|-----|------|------|------|------|-----|------|
| | | 125 | 175 | 250 | 350 | 500 | 700 | 1000 | 1400 | 2000 | 2800 | | 4000 |
| TL-63-127 | Lab | 34 | 38 | 40 | 46 | 47 | 47 | 50 | 51 | 53 | 49 | 54 | 49 |
| TL-63-126 | Lab | 22 | 28 | 32 | 38 | 43 | 44 | 46 | 48 | 46 | 41 | 45 | 42 |

limitations


1. Non-load bearing.
2. Not recommended for use where normally exposed to excessive moisture.
3. Limiting height (Ceiling Height Partition): 12'.
4. Because cornice and bank rail height movable partitions are more flexible than permanent partitions, certain precautions must be taken to resist lateral and impact loads (see Specifications, page 6).
5. Not recommended for use with full height glass panels.





details—ceiling height

scale: 3" = 1'-0"






ceiling attachment






suspended ceiling attachments



wall plan sections



electrical outlets














details


12a
Ub

door frames

borrowed light opgs.




floor anchor clips secured with a minimum of two suitable fasteners














details—cornice height

scale: 3" = 1'-0"





partitions

a**SHEETROCK® Demountable System**
GYPSUM WALLBOARD**1287****details—bank rail****12a**
Ub**post cap ①****base ②****glazed rail ④****mullion ⑤****base ③****base ⑥****internal;
external corner ⑦****wall
intersection ⑧**hold SHEETROCK
back 1/8" from
face of studUSG metal stud
(must be plumb and
correctly spaced
for rough opg.)**finished
end ⑨****finished
end ⑩**

specifications

notes to architect

1. Door frames constructed with the USG Rail A-06 and the USG Door Frame Assembly are recommended. USG Aluminum Door Framing Assembly will accommodate 1¾" hollow core doors only.

On cornice height partitions, one-piece and three-piece door frames should not be used.

On ceiling height partitions, door frames other than the USG Aluminum Door Assembly may be used if desired. One-piece metal door frames should be formed from 18-ga. steel minimum, shop primed. The opening between the trim returns should be accurately formed to the overall thickness of the partition. The trim returns should be a minimum of ¼" to allow the USG Aluminum Base to abut properly.

Floor anchor plates should be 14-ga. steel minimum, designed with two anchor holes to prevent rotation and welded to trim flanges to dampen door impact vibrations. Floor anchorage should be by two power-driven anchors or equivalent per plate. Jamb anchor clips should be formed of 18-ga. steel minimum, welded in the jamb and head (see detail page 3) and screw attached to the stud.

Door frame struts, when required, should be ¼" minimum thickness, hot rolled steel bar stock and of sufficient width to completely fill doorstop void, anchoring jamb securely. All door frame struts should be supplied as an integral part of the door frame.

Three-piece knock down steel door frames may be used on ceiling height partitions and should be installed according to manufacturer's directions.

Door closers and bumpers are required on all doors where the weight of the door (including attached hardware) exceeds 50 lbs.

2. On cornice height partitions, the limiting unrestrained length between supports, including cornice height with door openings joined by continuous top rail, should not exceed 14'0". Rails should not be spliced within 14'0" unrestrained lengths.

3. On bank rail partitions a continuous Rail A-06 must be used to cap the partition. Maximum recommended partition length: 14' with both ends terminating against a perpendicular wall or column or corner section; 8' with one end terminating against a perpendicular wall, column or corner section.

4. Holes cut in a thin wallboard membrane such as door frames, borrowed lights, etc., cause a concentration of stresses in the wallboard. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses.

5. Additional chases for electrical conduit or pipe can be provided by cutting round holes no greater in size than 75% of the stud width, located in the center of the stud web and spaced at least 12" apart. Additional holes should not be cut where a fire rating is required.

6. Where this partition is used as a sound barrier, the use of caulking to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure is recommended. Eliminate cutting holes back to back and adjacent to each other.

For maximum sound isolation the partition should extend from structural slab to structural slab, closing all openings.

7. The addition of 2" x 24" x 2½ lb. density THERMAFIBER® Sound Attenuation Blankets to the stud cavity, pressed tightly in place, stapled to the back side of one face of partition, will increase the sound transmission loss of the partition.

8. Fixture Attachment—Lightweight fixtures and trim should be installed using plastic plugs or other expandable anchors for screw attachment. Medium and heavy weight fixtures should be supported from the primary framing.

9. Where partitions are non-fire rated, attachment of the stud to the runner by piercing and crimping the flanges with the USG Metal Lock Fastener may be used.

10. Electrical Fixtures—The depth of electrical boxes should not exceed 2⅞". Boxes may be attached with suitable fasteners directly to adjacent vertical metal studs or to horizontal electrical straps spanning between studs.

11. Do not use any solvent-based adhesive for application of SHEETROCK Standard Vinyl Panel Wallboard over metal studs or treated wood framing. DWA-14 Adhesive by U.S.G. may be used for this application with SHEETROCK Custom Vinyl Panel Wallboard, and SHEETROCK VICRTEX A, B, C & T and VICRWALL Vinyl Panel Wallboard.

Because of the potential incompatibility between vinyl-surfaced wallboard and solvent-based adhesives, United States Gypsum cannot be responsible for problems arising from the use of either its adhesives with vinyl-surfaced wallboard manufactured by others, or its vinyl-surfaced wallboard applied with adhesive manufactured by others.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather, the building shall be heated well in advance of and during the application of SHEETROCK Gypsum Wallboard and adhesives to maintain a temperature in the range of 55° to 70° F., and ventilation shall be provided to eliminate excessive moisture.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage, moisture and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Paint Products Folder for Paint Specifications.

Gypsum Wallboard Folder and WB-765 Brochure for information on Wallboard System Components.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- Studs—25 ga. electro-galvanized steel USG Metal Stud No. 212 (2½").
- Metal Runners—Floor and Ceiling, 25 ga. electro-galvanized steel USG Metal Runner, No. 212 (2½"), with 1¼" flange.
- Gypsum Board—½" x 48" wide, square edge SHEETROCK Gypsum Wallboard (Regular or FIRECODE*); ½" x 48" wide SHEETROCK Vinyl Panel Gypsum Wallboard (Regular or FIRECODE); ½" x 48" wide SHEETROCK Custom Vinyl Gypsum Wallboard (Regular or FIRECODE).
- Fasteners—1" USG Drywall Screws, Type S; ⅜" USG Drywall Screws, pan head, Type S (for attachment of



USG Metal Studs to door jamb, or head, anchor inserts); $\frac{7}{8}$ " Oval-Head (cadmium plated) USG Drywall Finishing Screws; $1\frac{1}{8}$ " USG Drywall Bugle-Head Finishing Screws.

- e. Adhesives—Water-based contact bond adhesive, such as 3-M Contact Bond Drywall Adhesive; SHEETROCK Brand DWA-14 Adhesive (for use around one piece steel door frames only).
- f. Plastic Accessories Adhesive—Sears Vinyl Household Adhesive, General Electric Silicone Rubber Adhesive, RTV-102 or equal.
- g. Steel Accessories—
- | | | | |
|---------------|------|------------|------|
| Post Plate | S-71 | Rail Clip | S-70 |
| Post Assembly | S-36 | Floor Clip | S-11 |
- h. Aluminum Accessories—(Anodized)
- | | | | |
|-----------------------|------|--------------------|-------|
| $2\frac{1}{2}$ " Base | A-01 | Picture Mold | A-45 |
| 4" Base | A-37 | Glazing Rail | A-56 |
| Ceiling Trim | A-02 | Glazing Rail Cover | A-68 |
| Drive-In Ceiling Trim | A-46 | Plain Rail Cover | A-70 |
| Exterior Corner | A-03 | Post | A-73 |
| Interior Corner | A-38 | Post Channel | A-73A |
| Batten | A-04 | Door Stop | A-72 |
| Rail | A-06 | Pedestal | A-74 |
- i. Vinyl (Plastic) Accessories—Batten Insert P-05 (grey), P-06 (black); Glazing Spline P-10 (black); Post Cap P-69 (grey), P-70 (black); $2\frac{1}{2}$ " Base Closure Cap P-75, 4" Base Closure Cap P-76.

stud system erection

All partitions shall be of the type herein specified and shall be aligned accurately according to the partition layout. Floor runners shall be securely anchored with suitable fasteners, spaced not more than 24" o.c., and at corners and runner ends. On bank rail raised above floor, the bottom runner shall be centered within Rail A-06 and the assembly securely fastened to floor through Pedestal A-74 with a $\frac{3}{8}$ " threaded rod.

Top runners shall be securely anchored to ceiling, Rail A-06, or Glazing Rail A-56 with suitable fasteners, spaced not more than 24" o.c., and at corners and runner ends.

Metal studs shall be positioned vertically between top and bottom runners and spaced no greater than 24" o.c. Install metal studs at corners, intersections and partition terminals, and anchor by attaching each stud flange to the runner flange with $\frac{3}{8}$ " USG Drywall Screws, pan head, Type S. When necessary, studs shall be securely spliced with a minimum 8" nested lap. At partition terminals, the web of the stud shall be at the terminal end with the flanges directed into the partition.

door and borrowed light frames

Door and borrowed light frames shall be rough framed with metal studs and runners. Studs shall be positioned vertically adjacent to door and borrowed light frames where wallboard is attached and shall be anchored securely to top and bottom runners at each opening. Sill and header sections fabricated from metal runners shall be provided over less than ceiling height door frames and above and below borrowed light frames where wallboard is attached. Fabricate from a cut-to-length section of runner with flanges slit and web bent to allow flanges to overlap adjacent vertical studs and securely attach to adjacent studs. Cut-to-length studs shall be positioned in the center above the door opening and above and below borrowed light openings no greater than 24" o.c. At door openings anchor floor runner with two suitable fasteners at the jamb termination. Studs adjacent to one-piece door and borrowed frames shall be securely screwed or bolted to jamb and head anchor clips.

wallboard application

Gypsum wallboard shall be applied vertically with edges centered on the stud flanges and shall be attached with 1" USG Drywall Screws, Type S, to both the top and bottom runners 12" o.c., and at third points along vertical board edges. Screw attachment along vertical board joints at originating and terminating studs and around door and borrowed light frames shall be 12" o.c.

Water-based contact bond adhesive shall be used to attach the center of the board to those studs where the wallboard is not mechanically attached.

Where a one-piece steel door frame is used the gypsum wallboard shall be attached with a $\frac{3}{8}$ " bead of DWA-14 Adhesive applied to the full length of the metal stud.

On glazed cornice height and bank rail height partitions, wallboard shall be horizontally installed in as long lengths as possible.

cornice cap installation

The cornice cap shall be positioned horizontally on top of the partition and shall be Rail A-06 on the unglazed and Glazing Rail A-56 on the glazed cornice height partition. Corners shall be neatly mitered.

sill cap installation

The sill cap shall be positioned horizontally on top at the wainscot portion of the glazed ceiling height partition and shall be Rail A-06. Corners shall be neatly mitered.

partition terminal installation

Ceiling height partition—Terminal shall be finished by fitting Rail A-06 over the end of the partition and fastening securely at top and bottom with two $\frac{7}{8}$ " USG Drywall Oval-Head Finishing Screws.

Cornice height partition—Terminal shall be a continuous Rail A-06 fitted over the partition, attached at the floor with two $\frac{7}{8}$ " USG Drywall Oval-Head Finishing Screws, and attached at the ceiling by engaging two Rail Clips S-70 secured with appropriate fasteners to Glazing Rail A-56.

Bank rail partition—Floor Clip S-11 shall be positioned over runner and securely fastened to floor with two suitable anchors to prevent rotation. (Floor Clip is not required when bank rail is raised above floor.) A continuous Rail A-06 with corner coped and bent shall be used for the top rail and the terminal cap.

Bottom of vertical Rail A-06 shall be fastened to stud with two $1\frac{1}{4}$ " USG Drywall Bugle-Head Finishing Screws. Rail Cap A-06 shall be secured with Glazing Post Assembly.

door assembly installation

Ceiling height partition—The rough door opening shall be trimmed at both sides and at head with sections of Rail A-06. Screw-attach Rail A-06 and Door Stop A-72 to Rail A-06 with $\frac{7}{8}$ " USG Drywall Oval-Head Finishing Screws.

For full-height door openings, the rough opening shall be trimmed at ceiling line and at jambs with continuous sections of USG Rail A-06. Screw attach Rail A-06 and Door Stop A-72 as described above. Rubber door buttons shall be inserted in predrilled holes which are located on strike side of Door Stop A-72. Fixed transoms when required shall be set in place and securely attached to the Door Stop A-72 (ceiling line and jambs) with $1\frac{5}{8}$ " USG Type S Wood Trim Screws.



Cornice height partition—The rough door opening shall be trimmed on both sides with Rail A-06 positioned vertically, fastened at bottom with two $\frac{7}{8}$ " USG Drywall Oval-Head Finishing Screws and attached at the top by engaging two Rail Clips S-70 secured with appropriate fasteners to Glazing Rail A-56. Door Stop A-72 shall be fastened to vertical Rail A-06 and Glazing Rail A-56 with $\frac{7}{8}$ " USG Drywall Oval-Head Finishing Screws.

borrowed light assembly installation

Borrowed light openings shall be trimmed with Glazing Rail A-56 or Glazing Rail Cover A-68 for vertical and head sections and Rail A-06 for horizontal sill sections.

Intermediate mullions shall be assembled using Post Assembly S-36 and Post Plate S-71 positioned vertically between cap and sill, tightened in place and trimmed with Glazing Rail A-56 and Glazing Rail Cover A-68 snapped in place. Two Rail Clips S-70, positioned to engage each end of the Glazing Rail, shall be screwed to cap and sill with two $\frac{3}{8}$ " USG Pan Head Screws per clip.

glazing corner post installation

Post A-73 shall be installed plumb and fastened to Rail A-06 (and Glazing Rail) with Post Assembly S-36 and Post Plate S-71. Post Channel A-73A shall be cut-to-length and inserted in groove in Post A-73.

partition accessories

a. Aluminum Ceiling Trim A-02 shall be installed to ceiling runner and studs where indicated on the drawings with the USG Metal Lock Fastener spaced 24" o.c. Punchouts shall not interfere with wallboard placement.

b. Drive-In Ceiling Trim A-46 shall be installed where indicated on the drawings *after* wallboard is erected.

c. Picture Mold A-45 shall be applied horizontally at the ceiling line where indicated on the drawings, with 1" USG Drywall Screws, Type S, spaced 12" o.c.

d. Metal Base Splice Plates shall be installed 24" o.c. and at corners, partition terminals and base splices, with 1" USG Drywall Screws, Type S.

e. Aluminum Base (A-01, 2½") (A-37, 4") shall be notched to a neat miter in forming exterior corners, evenly butted at interior corners and held in place by engaging splice plates. In continuous runs ends shall be evenly butted and internally spliced with a splice plate.

f. Base Cap (P-75, 2½") (P-76, 4") shall be adhesively attached over ends of metal base with caps snugly abutting vertical rails.

g. Interior Corner A-38 shall be installed in one piece over wallboard at all interior corners with 1" USG Drywall Screws, Type S, spaced 12" o.c.

h. Exterior Corner A-03 shall be installed in one piece over wallboard at all exterior corners with 1" USG Drywall Screws, Type S, spaced 12" o.c.

i. Batten A-04 shall be installed to cover screw heads at vertical board joints and at intermediate studs when adhesive attachment is not used. Fasten with 1" USG Drywall Screws, Type S, spaced 12" o.c.

j. Batten Insert (P-05) (P-06) shall be installed in all Battens, Exterior and Interior Corners, and Picture Moldings.


k. Post Caps (P-69) (P-70) shall be adhesively attached to ends of Post A-73 on bank rail partition.

l. Glazing Accessories—Post Channels A-73A with counter-bored holes to receive $\frac{7}{8}$ " USG Drywall Oval-Head Finishing Screws spaced 1" from ends of channel and no more than 16" o.c. and appropriate screws shall be provided as required for glazing.

*TRADEMARKS: The following trademarks are owned and/or registered in the U. S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products, adhesives); SHEETROCK, FIRECODE (gypsum wallboard); THERMAFIBER (insulation products).

a-1287

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Specimen
for
Sales
Office

partitions

a

VAUGHAN WALLS®
 MOVABLE GYPSUM PARTITIONS

1297



A.I.A. File No. 35-H-6

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|--------------------------------------|------------|------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | Mov VAUGHAN WALLS pre-chased dbl sound wall—spec 5/8" USG gypsum wallbd face panels lamin to 5/8" gypsum core strips placed to form panel joints—2 rows 1 1/8" thick spaced 1 1/2" or 3" apart—alum trim wt 13 width 5 1/8" or 6" | UL Des 24-2 hr (f) | | | | Ideal for library, conference rooms. 50 stc based on 6" wid. with wool; 45 stc on 5 1/8" wid. without wool | a-1297 |
| | | TL-65-72 (s) | 50 | 52 | 250 | | |
| | | TL-64-189 (s) | 45 | | 210 | | |
| 1 hr. | Mov VAUGHAN WALLS pre-chased sound wall—spec 5/8" USG gypsum wallbd face panels lamin to 5/8" gypsum core strips—2 rows 1 1/4" thick separ by spec met Sound Atten Spacer (pat. pend.) placed vert at joints—2" insul wool in core space wt 7.5 width 3" | U of C 6-23-66 (f) | | | | Excellent space saving features. Special sound seals | a-1297 |
| | | WEAL 7-12-66 (s) | 44 | | 250 | | |
| 1 hr. | Mov VAUGHAN WALLS standard solid partn—spec 5/8" USG gypsum wallbd face panels lamin to spec 1" USG gypsum core units 24" wide wt 9 width 2 1/4" | T-1235-OSU (f) U of C 5-24-65 (f) | | | | Aluminum trim with steel inserts used in U of C fire test. Fine corridor, tenant wall | a-1297 |
| | | TL-64-213 (s) | 36 | | 166 | | |
| 1 hr. | Mov VAUGHAN WALLS pre-chased partn—spec 5/8" USG gypsum wallbd face panels lamin to spec 1" gypsum core strips placed to form panel joints wt 7 width 2 1/4" | UL Des 22-1 hr (f) | | | | Panel edges screw att. at qtr. points on fire test. Excellent corridor or tenant wall | a-1297 |
| | | TL-64-212 (s) | 36 | | 150 | | |

description

VAUGHAN WALLS® are high-performance interior partitions for office, industrial and school buildings that combine movable wall flexibility with permanent wall appearance and service. Constructed at the building site from special USG® gypsum panels and architectural aluminum runners and trim, these high-strength, versatile assemblies offer 1 and 2-hour fire-resistance ratings and up to 52 STC. Newly available is a 45-min. fire rated ceiling height door frame assembly with aluminum jamb and architectural wood door and transom that bears an Underwriters' Label for use in fire rated partitions (see table above).

Four basic walls are available for use either singly or in combination:

- (1) **Solid core wall**, 2 1/4" thick, excellent corridor partition or tenant wall.
- (2) **Chase (semi-solid core) wall**, 2 1/4" thick, corridor or tenant wall, preferred when electrical or telephone raceways required.
- (3) **Sound wall**, 3" thick, excellent party or privacy wall for library and conference rooms.
- (4) **Double sound wall**, 5 1/4" to 6 3/4" thick, maximum sound isolation for conference, music practice or recording rooms.

The special gypsum panels are produced to strict Vaughan specifications. They provide walls with either modular V-joints or continuous smooth surfaces to which a wide range of materials, paint, wood veneers, vinyl, fabric or wallpaper may be applied for unlimited architectural expression. Aluminum trim, buffed and satin anodized (Alcoa #204 C1 R1 or one of the lightfast anodic colors) provides an attractive accent to partition perimeters.

VAUGHAN WALLS are available in ceiling, cornice and bank-rail heights and have the flexibility of combining glass with all of these types. No studs or intermediate posts are necessary. Without these restrictions, door openings may be cut and walls intersect anywhere to allow complete freedom in space planning and design. Electrical and telephone services are easily carried vertically in chaseways through the core; outlets readily placed where needed. These factors assure architects and owners that all partitions are relocatable to meet future traffic patterns and space delineation.

Installation is performed by a nationwide network of licensed VAUGHAN WALLS contractors who are carefully selected and trained for quality craftsmanship in Vaughan's specialized methods. These contractors provide complete projects from consultation to finished interiors for original installations and relocation to meet future needs. They will assist in preparing architectural details and furnish shop drawings. Their stocks of aluminum parts, together with quick delivery of gypsum panels from strategically located U.S.G. plants, make VAUGHAN WALLS systems available without costly delays.


function and utility

Sound Control—The sound transmission loss rating of the standard 2 1/4" VAUGHAN WALL is better than that possible to obtain in most movable partitions without costly modifications. Vaughan Sound Walls further improve isolation.


Fire Resistance—1 and 2-hour fire-resistance ratings have been established for VAUGHAN WALLS with special USG gypsum panels (see table above).

Appearance—VAUGHAN WALLS have the visual qualities of permanence: handsome architectural aluminum trim with

(continued on page 7)




elevations & details



details

scale: 3" = 1'-0"




















* 1/8" Polyurethane Gasket


Note: Substitute 301V door mute for 300VR on butt side

details

scale: 3"=1'-0"













elevations & details



details

scale: 3" = 1'-0"



5 1/4" to 6 3/4" double sound wall—horizontal cross section

function and utility (continued from page 1)

either modular V-joints or smooth continuous surfaces that offer a complete latitude of finish selection.

Performance—VAUGHAN WALLS are sturdy and solid like fixed partitions; will support bookshelves and fixtures. They offer fire and sound characteristics equivalent to permanent partitions, yet, when space requirements change, VAUGHAN WALLS may be relocated promptly on short notice with minimum disturbance.

Service—All components of VAUGHAN WALLS are ready for immediate installation. No inventory by building owner is required. Fast erection permits early occupancy. Unexpected changes in layout are easily handled without costly delay in job progress.

Economy—Job-fabricated from low cost panel materials. Easily and speedily erected using Vaughan's time-tested methods and labor-saving installation devices. Cost is usually much less, for equivalent fire and sound performance, than other movable partitions. Low maintenance costs provide extended savings. When partitions are moved, materials are in many cases virtually 100% salvageable.

limitations

1. VAUGHAN WALLS are intended to be used only as non-load bearing walls.
2. Maximum height is 14' for solid wall; 12' for chase wall and sound wall.
3. Maximum unsupported run for less than ceiling height and glazed cornice height partition is 14'.
4. VAUGHAN WALLS should not be used where normally exposed to moisture or excessive humidity.

specifications

notes to architect

The most expedient way to obtain additional information on fire ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices, a VAUGHAN WALLS licensed contractor or VAUGHAN WALLS, INC., 11681 San Vicente Blvd., Los Angeles, Calif. 90049.

partition contractor

All Movable VAUGHAN WALLS shall be installed by a VAUGHAN WALLS Licensed Contractor employing skilled craftsmen under close supervision of experienced foremen who have had on-the-job training by VAUGHAN WALLS, INC.

work included

The partition contractor shall furnish all labor, materials and equipment necessary to complete all VAUGHAN WALLS: laminated gypsum panels, aluminum components, glass sections including glass and glazing, door frames, window frames, doors, transoms, wood veneers, vinyl wall covering, painting of walls and finishing of wood and, upon request, other items (topset base and finish hardware) as may be required to complete the VAUGHAN WALLS installation.

work not included

1. Ceilings and construction thereof.
2. Electrical and plumbing work.
3. Hoisting facilities including operating engineer.

shop drawings

Submit for architect's approval details of all metal components showing attachments to adjacent work and to each other when so required by the architect or owner, or a full size mock-up when the job warrants.

general conditions

Temperatures within the building shall be above a constant minimum of 55° during lamination and erection of partition panels. When required, heat shall be furnished by (building owner) (general contractor). Erection of partition panels shall not begin until erection of exterior walls and glazing or temporary covering of exterior openings provide complete protection from outside weather. Gypsum panels shall not be stored where they will be subjected to temperature, moisture or humidity extremes.

materials

- a. **Partition panels** shall be jig-laminated to form (24" wide panels, nom.) (widths designated for the job).

1. Solid panels shall consist of VAUGHAN WALLS 1" Gypsum Coreboard faced both sides with $\frac{5}{8}$ " VAUGHAN WALLS (regular) (FIRECODE*) Gypsum Panels manufactured within tolerances for this system by United States Gypsum.

2. Chase wall panels shall be semi-solid and consist of VAUGHAN WALLS 1" x 6" (nom.) Gypsum Coreboard strips spaced 12" apart (nom.) and faced both sides with $\frac{5}{8}$ " VAUGHAN WALLS (regular) (FIRECODE) Gypsum Panels.

3. 3" sound wall panels shall consist of $\frac{5}{8}$ " x 24" VAUGHAN WALLS FIRECODE Gypsum Panels laminated to $\frac{5}{8}$ " x 6" (nom.) VAUGHAN WALLS Coreboard. The Sound Attenuation Spacer (Patent Pending) shall be attached to the gypsum coreboard 18" o.c. using adhesive and Type S drywall screws. A 2" x 12" width of Sound Blanket as constructed for VAUGHAN WALLS shall be installed in each modular panel.

4. $5\frac{1}{4}$ " sound wall panels shall consist of $\frac{5}{8}$ " x 6" (nom.) VAUGHAN WALLS Coreboard spaced 12" apart and faced both sides with $\frac{5}{8}$ " VAUGHAN WALLS Gypsum Panels. The two laminated panels shall be set $1\frac{1}{2}$ " apart to form a sound wall $5\frac{1}{4}$ " wide.

- b. **Adhesive** shall be VAUGHAN WALLS Brand Neoprene Base Contact Adhesive, or other formulations as approved by VAUGHAN WALLS, INC. Water soluble adhesives shall not be used.

- c. **Metal Components** shall be furnished by the partition contractor and shall comply with standards approved by VAUGHAN WALLS, INC.

1. **Aluminum** shall be extruded from 6063-TS alloy and shall have a buffed and satin anodized finish, Alcoa 204

sound transmission loss

| test no. | method | decibel frequency in cps | | | | | | | | | | | | | | | | | | | | STC | |
|--------------|--------|--------------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|------|------|------|------|------|------|------|-----|------|
| | | 125 | 160 | 175 | 200 | 250 | 315 | 350 | 400 | 500 | 630 | 700 | 800 | 1000 | 1250 | 1400 | 1600 | 2000 | 2500 | 2800 | 3150 | | 4000 |
| TL 65-72 | Lab | 37 | 39 | — | 41 | 37 | 42 | — | 49 | 54 | 55 | — | 56 | 56 | 57 | — | 58 | 56 | 59 | — | 60 | 62 | 52 |
| | | 37 | — | 40 | — | 37 | — | 46 | — | 54 | — | 56 | — | 56 | — | 57 | — | 56 | — | 59 | — | 62 | 50 |
| TL-64-189 | Lab | 36 | — | 35 | — | 35 | — | 39 | — | 45 | — | 50 | — | 51 | — | 56 | — | 53 | — | 56 | — | 57 | 45 |
| WEAL 7-12-66 | Lab | 21 | 29 | — | 34 | 39 | 46 | — | 49 | 52 | 52 | — | 51 | 51 | 50 | — | 49 | 47 | 49 | — | 52 | 54 | 44 |
| TL-64-212 | Lab | 31 | — | 31 | — | 24 | — | 35 | — | 38 | — | 37 | — | 41 | — | 40 | — | 38 | — | 41 | — | 45 | 36 |
| TL-64-213 | Lab | 34 | — | 35 | — | 34 | — | 37 | — | 37 | — | 39 | — | 38 | — | 36 | — | 39 | — | 43 | — | 45 | 36 |

C1 R1. Commercial tolerances shall apply. Fasteners shall be cadmium plated.

2. Steel

a. Runners shall be roll formed from paint lock type steel of not less than 18 ga.

b. Door frames shall be two-piece hollow metal construction, fabricated of steel of not less than the following gauges: Frames—16 ga.; Closures—14 ga.; Hinge Reinforcement—9 ga.; Strike Reinforcement—12 ga. All door frames shall receive a factory prime coat.

d. **Finishing Accessories** (reinforcing tape, joint finishing compound, filling compound and metal corner beads) shall be as manufactured by United States Gypsum Company or equal.

e. Finishes

(1) **Wood** shall be 1/8" x 24" wide architectural veneers applied directly to VAUGHAN WALLS with VAUGHAN WALLS Brand Contact Adhesive. (*Specify type of wood and finish desired.*)

(2) **Vinyl**. Supported vinyl wall coverings as selected shall be wrapped on Vaughan Face Panels at the job site prior to erection of VAUGHAN WALLS. Adhesive shall be as supplied by vinyl manufacturer.

(*Alternate: factory applied supported vinyl panels also available from U.S.G., upon request.*)

(3) **Paint**. One coat of SHEETROCK* Sealer and 1 coat of GRAND PRIZE* paint, or 1 coat of TEXOLITE* Alkyd Latex, or 1 coat of flat oil paint is recommended. Apply in accordance with manufacturer's directions.

installation

1. **Partitions** shall be accurately laid out, and the floor and ceiling runners securely anchored. Such attachment shall assure complete security of the partition and future removal and relocation without excessive damage to the floor or ceiling construction.

2. **Gaskets** (1/8" thick foam type polyurethane or similar) shall be installed between all ceiling runners and ceiling surfaces and elsewhere as required by job conditions.

3. **Filler Strips** (*for steel runners only*) shall be of 5/8" gypsum wallboard cut to size and laid out in floor runners where required.

4. **Partition Panels** shall be formed and laminated in special jigs to insure a constant dimension at the tongue and groove. The coreboard shall be offset from the face panels to form a groove 1 1/2" deep. Panels shall be installed in floor and ceiling runners to form tight joints with true vertical and horizontal alignment.

5. **Aluminum Door Frames** shall be assembled plumb and square. Frames shall be fastened with wood screws into 1" x 4" long dowels set into coreboard. Five dowels per jamb shall be used as required. Bottom of frames shall be anchored to the floor runner.

6. **Closure Plates** shall be screwed securely to short legs of floor and ceiling runners. Full-length closure plates shall be used where practical. Cut ends shall be square and clean, fitting neatly to adjacent plates, trim, door frames, etc.

7. **Joint Compound** shall be applied to beveled joints of panels, to insure proper bridging of paint. Excess cement shall be wiped from the joint, leaving the true "V" bevel.

8. **Metal Corner Bead** shall be securely installed at all external corners. At least two coats of joint compound shall be applied over beads and each coat feathered out into panel faces.

9. **Tape and Joint Compound** shall be applied as recommended by United States Gypsum Company, to all internal corners and intersections where flush finishing is desired or metal trim is not specified.

10. **Electrical Outlets** shall be positioned as detailed. For solid walls the one-inch core panel shall be chased during the job-lamination process to accept electrical wiring and outlet boxes.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG, FIRECODE (gypsum wallboard); PERF-A-TAPE (joint system); DUR-A-BEAD (corner reinforcement); GRAND PRIZE, SHEETROCK, TEXOLITE (paint products). VAUGHAN WALLS is Reg. U.S. Pat. Off. by Vaughan Interior Walls, Inc.

a-1297

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, any warranties of FITNESS and MERCHANTABILITY, as well as any other warranties, express or implied, made in connection with any components sold for use in VAUGHAN WALLS systems, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS such components are erected, used and applied in strict accordance with applicable directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Systems
for
Sales
Offices



partitions

a

E-Z WALL MOVABLE PARTITION SYSTEM**1307**

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|--------------------|------------|------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| N/A | Mov E-Z WALL Drywall Partn—concealed "H" studs 24" o.c.—2" THERMAFIBER sound atten blkts— $\frac{3}{4}$ "x24" bevel edge panels mill lamin—joints unfin wt 7 width 3 $\frac{3}{8}$ " | USG-93-FT-G&H (s) | 45 | | 180 | Versatile movable partn.—variety of style combinations | a-1307 |
| 1 hr. | Mov E-Z WALL Drywall Partn—concealed "H" studs 24" o.c. bridged—1 $\frac{1}{2}$ " THERMAFIBER sound atten blkts— $\frac{3}{4}$ "x24" bevel edge FIRECODE panels mill lamin—joints unfin wt 7 width 3 $\frac{3}{8}$ " | U of C 12-9-65 (f) | 45 est | | 186 | | a-1307 |

description

The E-Z WALL Movable Partition is a non-load bearing, flush-panel-type construction, 3 $\frac{3}{8}$ " thick, with four basic components. This simplified design, available in ceiling, cornice or bank rail height, offers a fast solution to space control and re-location problems in offices, commercial buildings and institutions.

The partition is constructed of strong, incombustible laminated USG® gypsum board panels set in continuous runners and held in place with concealed open web steel H-studs spaced 24" o.c. The openings in the roll-formed H-shaped stud and the hollow construction provide ample accommodations for electrical wiring. The E-Z WALL panels, with edges beveled and integrally grooved to engage the stud, are mill laminated using two pieces of $\frac{3}{8}$ " thick gypsum board. The laminated panels, $\frac{3}{4}$ " thick by 24" wide and mill cut to stock lengths are available in a choice of finishes—mill-laminated vinyl-faced panels (including Walnut pattern) or plain panels ready for painting or other decoration. Openings for door and borrowed lights are neatly formed and trimmed flush with E-Z WALL extruded aluminum accessories. All exposed aluminum members are etched and anodized a neutral gray finish to assure long life and little maintenance.

E-Z WALL Movable Partitions are installed by experienced partition contractors.

function and utility

These modern movable partitions are designed for sound and space control in remodeling or in all types of new commercial, industrial, and institutional construction. They fit all standard ceiling grid modules, and offer all the advantages of permanent partitions plus the following features:

Simplicity—E-Z WALL has simplified multi-purpose components that assure faster, easier, more economical assemblies and relocations.

Flexibility—E-Z WALL Panels allow relocation of all units without need for special panel sizes and fillers.

Sound Control—E-Z WALL construction, exclusive of openings, has a 45 sound transmission class (STC) with 2"x24" THERMAFIBER® Sound Attenuation Blanket inserted in the partition cavity. The standard partition, without blankets, has a 39 STC.

| test no. | method | decibel frequency in cps | | | | | | | | | | | | STC |
|---------------|--------|--------------------------|-----|-----|-----|-----|-----|------|------|------|------|------|----|-----|
| | | 125 | 175 | 250 | 350 | 500 | 700 | 1000 | 1400 | 2000 | 2800 | 4000 | | |
| USG-93-FT-G&H | Lab | 26 | 27 | 38 | 44 | 46 | 49 | 47 | 48 | 43 | 44 | 45 | 45 | |

Easy Maintenance—Vinyl-faced E-Z WALL panels, etched and anodized aluminum members, and recommended vinyl top set base provide easy maintenance. Optional plain E-Z WALL panels may be painted and washed time after time.

Neat Appearance—Structural attachments concealed within partition—no visible fasteners are used.


Fire Protection—Fire-resistant gypsum board panels; every component part is incombustible. Choice of 30-min. or 1-hr. fire rated floor-to-ceiling partition.

Economy—Simplicity of erection and re-location, lower initial cost plus lower maintenance expense, provide greater long-range economy.

limitations


1. Non-load bearing.
2. Not recommended where exposed to excessive moisture.
3. Limiting height: 12' for Ceiling Height Partitions; 48" for unglazed Railing Height. When the rigidity of a permanent partition is desired, maximum height shall be 10' and perimeter restraint must be provided.
4. Limiting unrestrained length between supports of Cornice Height Partitions, including those with door openings joined by continuous top rail, shall not exceed 14'0".

The E-Z WALL partition construction is covered by Patent No. 3,027,605.




elevations & details


scale: 3" = 1' - 0"








ceiling height


















ceiling-cornice height



cornice height



details



specifications

notes to architect

1. Door frames should be formed with the E-Z WALL extruded aluminum door assembly.
2. In certain areas where seismic design code requirements govern, consult local building codes for partition limitations.
3. Where this partition is used as a sound barrier, the use of caulking to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure is recommended. Eliminate cutting holes back to back and adjacent to each other.
4. The addition of 2" x 24" x 48" THERMAFIBER Sound Attenuation Blankets to the stud cavity, pressed tightly in place, stapled to the back side of one face of partition, will increase the sound transmission loss of the partition.
5. Fixture Attachment—Lightweight fixtures and trim should be installed using plastic plugs or other expandable anchors for screw attachment. Medium and heavy weight fixtures should be supported from the primary framing.
6. Electrical Fixtures—The depth of electrical boxes should not exceed 2½". Standard conduit and boxes may be used.
7. See USG Paint Products Folder for complete Paint Specifications.

The most expedient way to obtain additional information on fire ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

scope

Furnish and erect E-Z WALL partitions as indicated on the plans and specified hereunder. Partitions are to be flush-panel-type, 3½" thick, (railing, cornice, and/or ceiling height) as supplied by the United States Gypsum Company.

shop drawings

Shop drawings showing layout and details of construction by partition contractors, when required, shall be submitted for approval.

materials

- a. E-Z WALL Panels shall be formed from mill-laminated gypsum board panels (plain) (vinyl-faced—specify color) ¾" thick by 24" wide by appropriate height. The panels shall have accurately formed off-set edges for concealed attachment to steel H-studs.

- b. Steel H-studs shall be one-piece open web type, roll-formed from 23-ga. electro-galvanized steel, isolated from floor and ceiling runners.
- c. Floor runners shall be formed from 23-ga. electro-galvanized steel. Ceiling runners shall be one-piece extruded aluminum. Floor and ceiling runners shall have formed-in spacers to hold panels in alignment. (Ceiling runners shall have integral trim to conceal top edges of panels.)
- d. Top set base trim shall be adhesively applied after panels have been erected and finished. Alternate: Rigid base trim shall be 18-ga. prime painted, 2½" high, with ¼" projection. Base trim shall be snapped on over 18-ga. base trim clips, provided at maximum spacing of 24".
- e. Door frames shall be formed of an extruded aluminum door buck and an extruded aluminum insert. Door bucks shall provide a finished opening into which an insert is fitted to provide door stops and hardware mortises. Wood doors, furnished by partition contractor, shall be 1¾" thick by appropriate width up to 3'0" by 7'0" high. Continuous removable plastic strikes shall be provided for quiet operation of doors and to lessen impact sound transmission.
- f. Door hardware consisting of (three 4"x4" butts for 1¾" thick doors) and key-in-knob lock shall be furnished in US 28 finish by the door supplier.
- g. Window frames shall be of sizes indicated on the plans and shall be built up from standard E-Z WALL extruded aluminum parts. Glass shall be furnished by the partition contractor and shall be set in E-Z WALL vinyl plastic glazing channels.
- h. Exposed aluminum members shall be etched and anodized to provide a permanent finish of neutral gray color.

installation

Lay out the partition. Securely attach floor and ceiling runners. Accurately plumb strut studs at door openings and terminals.

Install E-Z WALL Panels, H-studs, and trim members in accordance with United States Gypsum Company installation methods.

workmanship

The finished partition shall be rigid, plumb, with horizontal lines leveled; neat in appearance, and free from defects in workmanship. All connections to walls, floors, ceilings, cornice sections, and connections between gypsum board panels shall be concealed. If doors are hung by the partition contractor, hardware shall be adjusted to proper working order.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (gypsum wallboard); THERMAFIBER (insulation products).

a-1307

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Selling
Offices



partitions

a

IMPERIAL* Plaster and Wood Framing

HIGH-STRENGTH VENEER

1337

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|------------------------------------|------------|------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. est | Wd Stud—Resil $\frac{3}{8}$ " IMPERIAL plaster base & thin coat plaster—2x4 16" o.c.—2 layers pl base one side screw att & lamin—single layer opp side screw att to RC-1 chan spaced 24" o.c.—3" THERMAFIBER ins wool blkts— $\frac{1}{16}$ " IMPERIAL plaster both sides—perimeter caulked wt 11 width 6 $\frac{1}{8}$ " | CK-654-38 (s) | | 53 | 160 | | a-1337 |
| 1 hr. est | Wd Stud—Resil $\frac{3}{8}$ " IMPERIAL plaster base & thin coat plaster—2x4 16" o.c.—3" THERMAFIBER ins wool blkts—RC-1 chan one side spaced 24" o.c.—base att with 1" Type S screws—opp side att direct with 1 $\frac{1}{2}$ " Type W screws— $\frac{1}{16}$ " IMPERIAL plaster fin both sides—perimeter caulked wt 8 width 5 $\frac{1}{2}$ " | CK-664-4 (s) USG-111-FT-G&H (s) | | 49 | 142 | Good sound isolation combined with highly abrasion-resistant surface. CK-664-4 based on $\frac{1}{2}$ " plaster base | a-1337 |
| 1 hr. | Wd Stud— $\frac{1}{2}$ " IMPERIAL plaster base Type X att direct & thin coat plaster—2x4 16" o.c.—base att 6d nails 7" o.c.— $\frac{1}{16}$ " IMPERIAL plaster fin—joints taped wt 7 width 4 $\frac{3}{4}$ " | U of C 8-27-64 (f) | N/A | | 113 | Excellent surface hardness and abrasion resistance | a-1337 |

ceiling applications

| | | | | | | | |
|----------------------|---|----------------------------------|-----|---------------------|--------------|--|--------|
| 1 $\frac{1}{2}$ hrs. | Resil 2 layers $\frac{1}{2}$ " IMPERIAL gypsum pl base Type X & thin coat plaster ceiling—wd joist 2x10 16" o.c.—1" nom wd sub & fin flr—RC-1 chan spaced 24" o.c. screw att over base layer pl base—face layer screw att to chan 12" o.c.— $\frac{1}{16}$ " IMPERIAL plaster—joints taped clg wt 9 | UL Des 22-1 $\frac{1}{2}$ hr (f) | | 49 est (INR)—10 est | clg matls 63 | | a-1337 |
| 1 hr. | $\frac{1}{2}$ " IMPERIAL gypsum pl base Type X & thin coat plaster ceiling—wd joist 2x10 16" o.c. fire stopped—1" nom wd sub & fin flr—pl base att 5d nails 6" o.c.— $\frac{1}{8}$ " IMPERIAL plaster fin—joints taped clg wt 7.5 | UL Des 42-1 hr (f) | N/A | | clg matls 27 | | a-1337 |
| 1 hr. | Resil $\frac{1}{2}$ " IMPERIAL gypsum pl base Type X & thin coat plaster ceiling—wd joist 2x10 16" o.c.—1" nom sub & fin flr—RC-1 chan spaced 16" o.c. and at end joints—pl base att with Type S screws 12" o.c.— $\frac{1}{16}$ " IMPERIAL plaster fin—joints taped clg wt 7 | UL Des 41-1 hr (f) | N/A | | clg matls 38 | | a-1337 |

description

In the IMPERIAL Plaster Systems a thin veneer ($\frac{1}{16}$ " to $\frac{3}{32}$ " thick) of specially formulated, high-strength gypsum plaster is applied over IMPERIAL Plaster Base. Either IMPERIAL Plaster Finish is applied in a single-coat system, or IMPERIAL Plaster Basecoat is used in a two-coat application as a superior base for DIAMOND* Finish, STRUCTO-GAUGE* Gauging Plaster and lime, or Keene's-lime-sand-float finish.

IMPERIAL Plaster Base, 4' wide, has a high-strength, high-density core, either regular or Type X fire-rated, covered with special absorption face paper designed for thin-coat plastering.

Versatile IMPERIAL Plaster Base is directly attached to wood framing with screws or nails or resiliently attached using the RC-1 Resilient Channel to provide superior sound transmission loss. In the latter method IMPERIAL Plaster Base is fastened to the resilient channels with power-driven 1" USG® Type S Screws spaced 12" o.c. These specially designed self-tapping steel screws with a rust-inhibitive coating provide superior holding power and reduced core fracturing.

This system, with the lath and plaster resiliently attached over one side of wood studs, directly attached to the other and with THERMAFIBER* Insulating Blanket stapled in the stud cavity, provides one of the most economical party walls. IMPERIAL Plaster Base and Plaster may also be used with metal studs, metal furring channels or in laminated gypsum construction to meet incombustibility requirements for interior partitions, party walls, chase walls and furring (see separate IMPERIAL Plaster Systems Folder for details).

function and utility

IMPERIAL Plaster Systems are designed for interior partitions and ceilings wherever conventional plaster or drywall systems are used. Perfectly integrated components provide exceptionally hard surfaces ready for next-day decoration.

Durability—The high-strength (approx. 3,000 psi), abrasion-

and crack-resistant features of IMPERIAL Plaster offer the durability needed in high traffic areas, and obtainable with few other materials.

Fire Resistance ratings of 1 hour are available using Type X plaster base in both walls and ceilings (see table above).


Sound Control—The systems offer sound isolation up to 53 STC with the use of resilient channels and insulating wool; suitable for party walls (see tables above).

Versatility—Adaptable to most dimensions or modules in virtually all types of buildings, these systems meet all normal design and job conditions.

Light Weight—The completed systems weigh 7 to 8 psf; appreciably less than masonry partitions of the same thickness.

Economy—Simple, inexpensive components erect quickly at a

(continued on page 3)



components/data

see "plaster bases" product catalog for full description on accessories & sizes




$\frac{1}{2}$ " or $\frac{5}{8}$ "
IMPERIAL plaster base



1" USG screw—type S—bugle head



1 1/4" USG screw—type W—bugle head



IMPERIAL joint reinforcement tape



ring shank nail



barbed shank nail



800 series corner bead




700 series metal trim



fastener spacing—IMPERIAL Plaster Base


| thickn. of base | framing | type fastener | max. fastener spacing |
|--------------------------------------|---------|--|-------------------------|
| $\frac{1}{2}$ " | wood | Nails (for regular base)— $1\frac{1}{4}$ ", 13 ga., $1\frac{5}{64}$ " head, ring or barbed shank, blued, polished or cement coated | 7" ceilings 8" walls |
| | | Nails (for Type X base)— $1\frac{1}{8}$ " 5d cooler type cement coated | 6" ceilings 7" walls |
| | | Screws—USG $1\frac{1}{4}$ " Type W | 12" |
| | | Screws—USG 1" Type S | 12" |
| with RC-1 channel $\frac{5}{8}$ " | wood | Nails (for regular base)— $1\frac{1}{4}$ ", 13 ga., $1\frac{5}{64}$ " head, ring or barbed shank, blued, polished or cement coated | 7" ceilings 8" walls |
| | | Nails (for Type X base)— $1\frac{1}{8}$ " 6d cooler type cement coated | 6" ceilings 7" walls |
| | | Screws—USG $1\frac{1}{4}$ " Type W | 12" |
| | | Screws—USG 1" Type S | 12" |




RC-1 resilient channel

details


ceiling attachment



floor attachment & base




floating interior angle system




details/specifications

miscellaneous




door jamb

SHEETROCK W/R wallboard installation – tub and shower areas



tub



shower pad

function and utility (continued from page 1)

lower cost than conventional plaster systems. Plaster is rapidly applied; both IMPERIAL basecoat and finish are available in choice of two formulas—Machine Application or Hand Tool Application.

limitations

1. These constructions should not be used where exposed to abnormal moisture or excessively high humidity or temperature.
2. 1" USG Type S Screws must be used for attachment of single layer base to RC-1 Resilient Channels.
3. RC-1 Resilient Channels must be attached to framing only with 1 1/4" USG Type W Screws. Nails should not be used.
4. Resilient ceilings should not be installed beneath highly flexible floor joists. Install only to framing meeting "Wood Framing Requirements" (see Specifications).
5. Max. Framing Spacing: 16" for 1/2" thick base; 24" for 5/8" thick base.

specifications—notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.
2. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements, except the floor, by control joints or other means where:
 - a. a partition abuts a structural element or dissimilar wall or ceiling assembly.
 - b. the partition construction changes within the plane of the partition.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

Expansive ceiling areas should have control joints, spaced not to exceed 50' in either direction. The continuity of both lath and plaster should be broken under control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

3. Holes cut in a thin diaphragm of lath and plaster, such as door frames, borrowed lights, etc., cause a concentration of stresses in the plaster diaphragm. The use of additional reinforcement is recommended at the weakened area to distribute concentrated stresses where, in the judgment of the architect,

for reasons of economy or design, a control joint is not otherwise specified.

4. Where contact or furred ceilings occur under roof construction, the plenum or attic space should be vented according to recommended engineering practice.

5. Where this partition is used as a sound barrier, the use of non-hardening caulking material to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure, is recommended. Eliminate cutting holes back to back and adjacent to each other. Door and borrowed light openings are not recommended when this partition is used as a party wall.

6. **Wood Framing Requirements**—Wood framing meeting the following minimum requirements is necessary for proper performance. Framework shall meet the minimum requirements of FHA and local building codes. Framing members shall be straight, true, of uniform dimension, and framing shall be properly aligned. All framing lumber shall be of a good grade for the intended use, and 2" x 4" nominal size or larger shall bear the grade mark of a recognized inspection agency using grading rules for lumber recommended to American Lumber Standards Committee. All framing lumber shall have a moisture content not in excess of 15% at the time of gypsum base application. Use of kiln dried lumber for joists is recommended. Extremely hard (dense) or soft framing members should not be used for attachment of base.

7. **Ceramic Tile**—IMPERIAL Plaster Base is not recommended as a base for the adhesive application of ceramic, metal and plastic tile unless the edges are protected from wetting and the entire surface is sealed with adhesive or other material recommended by the tile manufacturer. SHEETROCK* W/R Gypsum Wallboard is recommended for this use (see details).

8. Proper sealing of IMPERIAL Plaster surfaces before painting is essential (see USG Paint Products Folder).

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather, the building shall be maintained above 55°F. for an adequate period prior to, during, and after installation of systems including the application of IMPERIAL Plaster. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period. All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

specifications (continued)

materials

See USG product folders in this series:

Gypsum Plaster Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. **IMPERIAL Plaster Base**—($\frac{1}{2}$ ") ($\frac{3}{8}$ ") thick, 48" wide, (Regular) (Insulating) (Type X), lengths as required.
- b. **IMPERIAL Plaster**—(Finish) (Basecoat) (Machine Application) (Hand Tool Application) used in accordance with manufacturer's directions.
- c. **RC-1 SHEETROCK Resilient Channel**.
- d. **THERMAFIBER Insulating Wool Blankets** (thickness) (choose from USG Insulating Wool Products Folder).
- e. **Fasteners**—(choose from page 2).
- f. **IMPERIAL Tape**—for joint reinforcement.
- g. **Accessories**—(800-A) (800-B) Corner Bead, (700-A) (700-B) Metal Trim, USG #093 Control Joint.

direct attachment of plaster base

The **IMPERIAL Plaster Base** shall be applied (vertically) (horizontally). All ends and edges of the base shall occur over framing members, except when joints are at right angles to framing members as in horizontal application.

The **Plaster Base** shall be applied first to the ceilings and then to the walls. To minimize end joints, use maximum practical lengths. The base shall be brought into contact, but shall not be forced into place. Where ends or edges abut they shall be fitted neatly.

End joints shall be staggered. Joints on opposite sides of partitions shall be so arranged as to occur on different studs. Interior vertical and horizontal angles shall be floated by not fastening to the framing members in the angles. In the case of framing members at right angles to the interior angle, fasten approximately 8" away from the angle.

Fastening should proceed from the central portion of the base toward the ends and edges. While the fasteners are being driven, the base shall be held in firm contact with the underlying support. Nails shall be spaced 7 to 8" o.c., screws 12" o.c. and not less than $\frac{3}{8}$ " from edges and ends of the base. The head of the fasteners shall be set flush with the surface of the paper but not breaking the paper. Where base appears too loose from the stud or joist, a second fastener within $1\frac{1}{2}$ " of the first, shall be used.

Base shall be neatly cut and fitted for pipes, electrical outlets, medicine cabinets, etc. Holes for electrical outlet boxes shall be cut from the base by a special outlet box cutting tool. For circular holes the adjustable circular cutting tool shall be used.

Remove any loose face paper at cut and use a quick setting plaster to fill any holes or openings.

resilient attachment of plaster base

RC-1 SHEETROCK Resilient Channels shall be positioned at right angles to the wood framing, spaced (16") (24") o.c. and attached to the supports with $1\frac{1}{4}$ " USG Type W Screws driven through the pre-punched holes provided in the attachment flange. On walls resilient channels shall be positioned with the plaster base attachment flange up and shall be located at the floor, (16") (24") up from the floor line, a maximum of 6" down from the ceiling line, and extended into all corners and connected to corner framing. Channels shall not be cantilevered more than 6". Channels shall be spliced directly over a framing member by spacing channels $\frac{1}{8}$ " apart and screwing both end attachment flanges to framing. Splices shall be staggered and not be made directly under plaster base edge joints.

IMPERIAL Plaster Base shall be applied first to the ceiling and then to the partitions. Plaster base of maximum practical length shall be applied with the long dimension at right angles to the channels and with end joints centered over the channel, staggered and neatly fitted. Plaster base shall be fastened to channels with USG 1" Type S screws spaced 12" o.c. in the field of the base and along abutting ends. Screws shall be driven at least $\frac{3}{8}$ " from ends or edges of base. Base shall be properly supported around all cut-outs and openings.

accessory application

a. **IMPERIAL Tape** shall be applied over all **IMPERIAL Plaster Base** joints with a spring-driven stapler using $\frac{3}{8}$ " staples. Tape shall be applied over the full length of all joints but shall not overlap at intersections. Tape shall be affixed with two staples at the top of the tape—one on each side of the joint, 24" o.c. along the length of the tape, alternating from side to side with two staples at the bottom.

At wall-ceiling intersections, the tape shall be stapled every 24" along the ceiling edge only; for wall and partition interior corners, stapled every 24" on one edge only, working from top to bottom. All interior corners shall have tape positioned to bridge the joint. For fire-rated assemblies, tape shall be stapled 8" o.c.

b. **Corner Bead**—All vertical and horizontal exterior corners shall be reinforced with 800-A or B Corner Bead fastened with nails or staples 12" o.c. on both flanges along the entire length of the bead.


c. **Casing Bead**—When an **IMPERIAL** wall or partition terminates against masonry or other dissimilar material, 700-A or B Metal Trim shall be applied over the **IMPERIAL Plaster Base** and fastened on the perforated side with nails or staples spaced 12" o.c. The trim shall firmly abut the dissimilar material forming a neat joint.

d. **Screws** shall be power-driven with an electric screwdriver and set so that the screwhead provides a slight depression below the surface of the **IMPERIAL Plaster Base** without tearing through the face paper.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured and/or sold by that company. **IMPERIAL**, **DIAMOND**, **STRUCTO-GAUGE** (plaster); **USG** (metal products); **SHEETROCK** (gypsum wallboard, metal channel); **THERMAFIBER** (insulation products).

a-1337

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of **FITNESS** and **MERCHANTABILITY** as well as any other warranties, express or implied, made in connection with the sale of these products, **SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS** the products are applied according to United States Gypsum Company's directions and specifications.




UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Director
for
Sales
Offices



UNITED
STATES
GYPSUM

direct attachment

partitions

a

USG* Metal Lath and Wood Framing

1346

| fire rating | description | test no. | sound rating | | relative cost index | comments | folder reference |
|-------------|--|-------------------------------|--------------|---------|---------------------|----------|------------------|
| | | | stc | 9-f avg | | | |
| 1 hr. | Wd Stud—Metal Lath & Plaster—2x4 16" o.c.—3.4# dm met lath— $\frac{3}{4}$ " 100:2-100:3 gypsum sand plaster wt 20 width $5\frac{3}{8}$ " | BMS-92 (f) NBS-228 F43 (s) | 41 | | 146 | | a-1346 |
| 1 hr. | Wd Stud—Metal Lath & Plaster—2x4 16" o.c.—3.4# dm met lath— $\frac{3}{8}$ " 100:2-100:2 gypsum sand plaster wt 18 width $5\frac{3}{8}$ " | BMS-92 table 30 (f) | 39 est | | 146 | | a-1346 |

ceiling application

| | | | | | | |
|-------|---|---------------------|-----------|--------------|--|--------|
| 1 hr. | Wd Joist—Metal Lath & Plaster Ceiling—1" nom wd sub & fin flr—3.4# dm met lath att with $1\frac{1}{2}$ " nails 6" o.c.— $\frac{3}{8}$ " 100:2-100:3 gypsum sand plaster clg wt 10 | BMS-92 table 42 (f) | 35 db est | clg matls 55 | | a-1346 |
|-------|---|---------------------|-----------|--------------|--|--------|

description

In these fire-resistant assemblies USG Metal Lath is attached directly to wood studs or joists with nails or staples spaced 6" o.c. The metal lath is applied across the supports with end joints staggered and occurring over supports. The sides and ends of adjacent sheets are lapped and secured together with 18 ga. tie wire. At interior angles the lath is carried around the corner to provide reinforcement. The assembly when completed with metal accessories and plaster provides an economical, versatile, crack-resistant construction for walls and ceilings.

Metal lath, expanded from rust-resisting sheet steel, is a versatile, lightweight base for the economical application of gypsum plasters. The excellent mechanical keying properties and equal distribution of reinforcing give assemblies using it high fire resistance (see table above).

Metal lath for this assembly is available in three types. USG Junior Diamond Mesh Lath is a general all-purpose lath, and recommended for ornamental, contour plastering. USG $\frac{1}{8}$ " Z-Ribblath, more rigid than Diamond Mesh Lath, is an excellent nail-on lath. USG $\frac{3}{8}$ " Ribblath is a self-furring type lath with exceptional rigidity that is suitable for support spacings up to 24" o.c. (see table below).

function and utility

Versatile—These systems are easily adapted for use in all types of new construction and remodeling to provide fire protection for wood framing. They are suited for use in contoured or decoratively plastered walls and ceilings.

Fire Resistance—One-hour fire-resistance ratings have been established, acceptable for both walls and ceilings.

Crack Resistance—The metal lath reinforcing in the plaster resists cracking and failure due to structural movement of the frame.

Sound Control—The basic partition is acceptable as a divider within units. With $\frac{3}{4}$ " of gypsum sand plaster a 39 db sound rating (9 freq. average) has been established.

limitations

Maximum support spacing should not be exceeded (see table below).


spacing of supports

| type of lath | weight per sq. yd. (lbs.) | maximum allowable spacing | |
|----------------------------|---------------------------|---------------------------|-------------|
| | | wood studs | wood joists |
| diamond mesh | 2.5 | 16" | (1) |
| diamond mesh | 3.4 | 16" | 16" |
| $\frac{1}{8}$ " Z-ribblath | 2.75 | 16" | 16" |
| $\frac{1}{8}$ " Z-ribblath | 3.4 | 19" | 19" |
| $\frac{3}{8}$ " ribblath | 3.4 | 24" | 24" |
| $\frac{3}{8}$ " ribblath | 4.0 | 24" | 24" |


(1) not recommended

attachment spacing


| framing | attachment | fastener spacing c. to c. |
|-------------|--|---------------------------|
| wood studs | nails—4d common, driven to $\frac{3}{4}$ " penetration and bent over to engage 3 strands or through the rib. | 6" |
| | nails—1" roofing nail $\frac{1}{16}$ " head, engaging 2 strands or through the rib. | 6" |
| | staples—1", 14 ga. wire staples, engaging 2 strands or a rib. | 6" |
| wood joists | nails—1 $\frac{1}{2}$ ", 11 ga. barbed roofing nail, $\frac{1}{16}$ " head, engaging 2 strands or a rib. | 6" |



USG junior diamond mesh lath





USG 4-mesh z-ribblath








USG $\frac{3}{8}$ " ribblath

components

see "plaster bases" product catalog for full description on accessories & sizes



USG casing beads (expanded or short flange)





direct attachment

partitions


a

USG* Metal Lath and Wood Framing


1346

details


scale: 3" = 1'-0"




ceiling attachment



base attachment



partition corner



wood door frames

specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.
2. Lath and plaster surfaces will not resist stresses imposed by structural movement, and are subject to dimensional variations

due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from the following structural elements by control joints, or other means where:

- a. a partition or ceiling abuts any structural elements, dissimilar wall or partition assembly, or other vertical penetration.
- b. the construction changes within the plane of the partition or ceiling.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling



direct attachment

partitions

a

USG* Metal Lath and Wood Framing

1346

may be used as control joints. For doors less than ceiling height, control joints extending from the center or both corners of the frame to the ceiling may be used.

Expansive ceiling areas should have control joints, spaced not to exceed 50' in either direction. The continuity of both lath and plaster should be broken under control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

3. Holes cut in a thin lath and plaster membrane such as door frames, borrowed lights, vents, grilles, access panels, light troffers, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy and design, a control joint is not otherwise specified.

4. Where contact or furred ceilings occur under roof construction, the plenum or attic space should be vented according to recommended engineering practice.

5. To retain maximum sound isolation, the integrity of the partition or ceiling should not be voided by openings, such as doors, electrical outlets, medicine cabinets, vents, etc., so as to create sound leaks. Use sand aggregate only; do not use lightweight aggregates.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architect Service Department, 101 S. Wacker Dr., Chicago, Illinois 60606.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. Metal Lath shall be (2.5) (3.4) (Diamond Mesh) (2.75) (3.4) ($\frac{1}{8}$ " Z-Riblath) (3.4) (4.0) ($\frac{3}{8}$ " Riblath) 27"x96".
- b. USG Corner Bead (specify style from page 2).

c. USG Casing Bead (specify type from page 2).

d. USG 8-A Picture Mould.

e. 18 ga. Tie Wire.

f. Nails—(4d common) (1" roofing nail, $\frac{7}{16}$ " head) (1 $\frac{1}{2}$ ", 11 ga. barbed roofing nail, $\frac{7}{16}$ " head) (not available from U.S.G.).

g. Staples—1", 14 ga. Wire Staples (not available from U.S.G.).

plaster base attachment

Metal lath shall be applied with the long dimension of the sheet across the supports. Riblath shall be applied with the rib projections against the support.

The ends of all lath shall be lapped not less than 1". If end laps are made between supports, they shall be adequately laced or tied with 18 ga. tie wire. The sides of diamond mesh lath shall be lapped not less than $\frac{1}{2}$ ". The sides of riblath shall be lapped by nesting outside ribs, and shall be wire-tied between supports not to exceed 9" intervals. On walls metal lath shall be placed so that the lower sheets overlap the upper sheets. Wherever possible, ends of lath in adjacent courses shall be staggered.

At all interior angles, metal lath shall be formed into the corners and carried out onto the abutting surface.

Metal lath shall be secured to all supports at intervals not exceeding 6" with nails or staples providing at least $\frac{3}{4}$ " penetration. Nails shall be driven through the rib or through the mesh engaging 2 strands. 4d common nails if driven through the mesh shall be bent over to engage 3 strands. Staples shall engage 2 strands or a rib.

lathing accessories


a. Metal Corner Bead No. (000000) shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with wire-ties, etc., spaced not over 8" o.c.; stagger in two wings.

b. Casing Bead No. (000000) shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Wire-tie in place.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products).

NOTE: Since methods and conditions of application and use are beyond our control, the United States Gypsum Company will not be responsible for failure of its products when not used according to our directions and specifications.

a-1346



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

partitions

a

resilient attachment

USG* Metal Lath and Wood Framing

1356



A.I.A. File No. 20-B-1.1

| fire rating | description | test no. | sound rating | | relative cost index | comments | folder reference |
|----------------------------|---|--------------|--------------|---------|---------------------|--|------------------|
| | | | stc | 9-f avg | | | |
| 1 hr. est | Wd Stud—Resil Metal Lath & Plaster—2x4's—3.4# dm met lath— $\frac{1}{4}$ " pencil rod—#200 resil clips— $\frac{3}{4}$ " gypsum sand plaster wt 21 width 5 $\frac{1}{2}$ " | TL-61-86 (s) | 43 | | 177 | Excellent sound isolation for this type construction | a-1356 |
| ceiling application | | | | | | | |
| 1 hr. est | Wd Joist—Resil Metal Lath & Plaster Ceiling—1" nom wd sub & fin flr—3.4# dm met lath att to $\frac{1}{4}$ " pencil rod on #200 resil clips— $\frac{3}{8}$ " 100:2-100:3 gypsum sand plaster clg wt 10 | NBS-710 (s) | 52 | | clg matls 68 | Excellent sound isolation & crack resistance | a-1356 |

description

These fire-resistant assemblies consist of USG Metal Lath and gypsum plaster attached to wood studs or joists to provide a resilient surface that appreciably improves sound control through walls and ceilings. In the construction USG Resilient Clips No. 200, spaced 16" o.c. for walls and 12" o.c. for ceilings, are nailed to the wood framing. $\frac{1}{4}$ " pencil rods are nested into the clips and metal lath is tied to the rods. By using these specially designed resilient clips, the two lath and plaster diaphragms are not rigidly coupled to the framing members. The isolation provided by the clips appreciably reduces the transmission of sound and structural movement to the outer surface of the plaster (see table above).

The assembly, when completed with metal accessories and plaster, provides fire protection to wood framing and outstanding sound and crack resistant features at only a nominal increase in cost over conventional lathing methods (see table above).

Metal lath, expanded from rust-resisting steel, is a versatile, lightweight base for the economical application of gypsum plasters. For these assemblies it is available in two types (see Specifications, page 3). The excellent mechanical keying properties and equal distribution of reinforcing provided by this plaster base gives the assembly its fire resistance.

function and utility

Versatile—Readily adapted to virtually all types of new construction and remodeling to provide fire protection, sound control and hard, abrasion-resistant, easily decorated plaster walls and ceilings. It satisfies most design and job conditions in commercial, industrial and residential applications where wood framing is used. Curved surfaces can be formed more satisfactorily than by any other method.


Fire Resistance—Estimated one-hour fire rating with wood framing members in walls and ceilings.

Sound Control—The Resilient Clips increase the sound-isolative efficiency of the construction to result in a partition with a 43 Sound Transmission Class.

Crack Resistance—The resilient attachment markedly reduces the possible transmission of stresses due to structural movement to the lath and plaster membrane, thereby reducing the incidence of cracking.


limitations

1. Maximum support spacing: 16" for wood studs or joists.
2. 2.5 lb. Diamond Mesh Metal Lath is not recommended for ceiling application.




A.I.A. File No. 20-B-1.1

components



USG junior diamond mesh lath





USG 4-mesh z-rib lath





#200
resilient
clip

USG casing beads
(expanded or short flange)



USG
8-A
corner
bead



USG
1-A
expanded
corner bead




USG
10-A
expanded
bull nose
corner bead

see "plaster bases" product catalog for
full description on accessories & sizes



USG
5-A
bull nose
corner bead






USG
4-R
expanded
corner bead



details

scale: 3" = 1'-0"



specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.

2. Lath and plaster surfaces will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended

that lath and plaster surfaces be isolated from the following structural elements by control joints, or other means where:

- a partition or ceiling abuts any structural elements, dissimilar wall or partition assembly, or other vertical penetration.
- the construction changes within the plane of the partition or ceiling.

In long partitions runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling



may be used as control joints. For doors less than ceiling height, control joints extending from the center of both corners of the frame to the ceiling may be used. Expansive ceiling areas should have control joints, spaced not to exceed 50' in either direction. The continuity of both lath and plaster should be broken under control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

3. Holes cut in a thin lath and plaster membrane such as door frames, borrowed lights, vents, grilles, access panels, light troffers, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy and design, a control joint is not otherwise specified.

4. Where contact or furred ceilings occur under roof construction, the plenum or attic space should be vented according to recommended engineering practice.

5. To retain maximum sound isolation, the integrity of the partition or ceiling should not be voided by openings, such as doors, electrical outlets, medicine cabinets, vents, etc., so as to create sound leaks. Use sand aggregate only; do not use lightweight aggregates.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architect Service Department, 101 S. Wacker Dr., Chicago, Ill. 60606.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. Metal Lath shall be (2.5) (3.4) (Diamond Mesh) (2.75 1/8" Z-Riblath) 27" x 96".
- b. USG Resilient Clip No. 200.
- c. USG Corner Bead (specify style from page 2).
- d. USG Casing Bead (specify type from page 2).
- e. USG 8-A Picture Mould.
- f. 1/4" Pencil Rod.

g. 18 ga. Tie Wire.

h. Nails—13 ga., 1 1/8" Lathing Nails (not available from U.S.G.).

plaster base attachment

USG Resilient Clips No. 200 shall be nailed to wood framing spaced not to exceed 16" o.c. on walls and 12" o.c. on ceilings. Clips shall provide 1/2" furring for metal lath from supports. Clips shall be located not more than 4" from floor, wall-to-wall and wall-to-ceiling intersections, and abutting dissimilar construction and as required above and below openings. On walls 1/4" pencil rods of ceiling height length shall be erected vertically spaced no more than 16" o.c. by engaging the clip projection. On ceilings 1/4" pencil rods spaced no more than 12" o.c. shall be erected across the supports by threading through the clip holes.

Metal lath shall be applied with the long dimension of the sheet across the supports. Riblath shall be applied with the rib projections against the support.

The ends of all lath shall be lapped not less than 1". If end laps are made between supports, they shall be adequately laced or tied with 18 ga. tie wire. The sides of diamond mesh lath shall be lapped not less than 1/2". The sides of diamond mesh lath shall be lapped not less than 1/2". The sides of riblath shall be lapped by nesting outside ribs, and shall be wire-tied to every support, and between supports not to exceed 9" intervals. On walls metal lath shall be placed so that the lower sheets overlap the upper sheets. Wherever possible, ends of lath in adjacent courses shall be staggered.

At all interior angles, metal lath shall be formed into the corners and carried out onto the abutting surface, and adequately secured.

Metal lath shall be secured to all supports with 18 ga. tie wire at intervals not exceeding 6". Ends of all ties shall have three full twists, then shall be bent up into the plane of the lath.

lathing accessories


a. **Metal Corner Bead No. (000000)** shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with wire-ties, etc., spaced not over 8" o.c.; stagger in two wings.

b. **Casing Bead No. (000000)** shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Wire-tie in place.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products).


NOTE: Since methods and conditions of application and use are beyond our control, the United States Gypsum Company will not be responsible for failure of its products when not used according to our directions and specifications.

a-1356



UNITED STATES GYPSUM
THE GREATEST NAME IN BUILDING
GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



UNITED
STATES
GYPSUM

direct attachment

partitions

a

ROCKLATH* and Wood Framing

PLASTER BASE

1366

| fire rating | description | test no. | sound rating | | relative cost index | comments | folder reference |
|-------------|---|-------------------|--------------|---------|---------------------|--|------------------|
| | | | stc | 9-f avg | | | |
| 2 hrs. | Wd Stud—Gypsum Lath & Plaster—2x4 16" o.c.— $\frac{3}{8}$ " perf ROCKLATH nailed 5" o.c.—hex wire mesh nailed 8" o.c. over face of lath & held $\frac{1}{16}$ " away from face—1" 100:2½ gypsum perlite plaster wt 12 width 6½" | T-961-OSU (f) | N/A | | 195 | | a-1366 |
| 1 hr. est | Stag Wd Stud—Gypsum Lath & Plaster—stag 2x4 16" o.c.—com top & bottom plates—2" THERMAFIBER ins wool batts— $\frac{3}{8}$ " plain ROCKLATH nailed— $\frac{1}{2}$ " gypsum sand plaster wt 18 width 7½" | TL-58-64 (s) | 50 | | 182 | Excellent party wall—note comparison with test TL-61-232 | a-1366 |
| 1 hr. est | Stag Wd Stud—Gypsum Lath & Plaster—stag 2x3 16" o.c.— $\frac{3}{8}$ " plain ROCKLATH nailed—100:2½ gypsum sand plaster wt 14 width 4¾" min | TL-61-232 (s) | 42 | | 173 | | a-1366 |
| 1 hr. | Wd. Stud—Gypsum Lath & Plaster—2x4 16" o.c.— $\frac{3}{8}$ " perf ROCKLATH nailed 3" o.c.— $\frac{9}{16}$ " 100:2 gypsum perlite plaster wt 9 width 5½" | UL Des 7-1 hr (f) | N/A | | 128 | Extra nailing and lightweight aggregate with extra thickness | a-1366 |
| 1 hr. | Wd Stud—Gypsum Lath & Plaster—2x4 16" o.c.— $\frac{3}{8}$ " perf ROCKLATH nailed 4" o.c.— $\frac{1}{2}$ " 100:2 gypsum sand plaster wt 15 width 5½" | T-948 OSU (f) | | | | | |
| | | TL-58-60 (s) | 41 | | 128 | Same as NBS-148 except perf. lath | a-1366 |
| 1 hr. | Wd Stud—Gypsum Lath & Plaster—2x4 16" o.c.— $\frac{3}{8}$ " plain ROCKLATH—1½" nails 4" o.c.— $\frac{1}{2}$ " 100:2 gypsum sand plaster wt 15 width 5½" | T-1380 OSU (f) | | | | | |
| | | NBS-148 (s) | 40 | | 128 | Standard wood stud partition | a-1366 |

ceiling applications

| | | | | | | | |
|-------|--|---------------------|--------|--|--------------|--|--------|
| 1 hr. | Gypsum Lath & Plaster Ceiling—wd joist—1" nom wd sub & fin flr— $\frac{3}{8}$ " perf ROCKLATH—3" Striplath on joints— $\frac{1}{2}$ " 100:2 gypsum sand plaster clg wt 6 | BMS-92 table 42 (f) | | | | Good method to attain 1-hr. rating—note Striplath use | a-1366 |
| | | NBS-714 (s) | 37 | | clg matls 51 | | |
| 1 hr. | Gypsum Lath & Plaster Ceiling—wd joist—1" nom wd sub & fin flr— $\frac{3}{8}$ " ROCKLATH FIRECODE—3" Striplath along joist— $\frac{1}{2}$ " 100:2 gypsum sand plaster clg wt 6 | FPRI No. 6 (f) | 37 est | | clg matls 40 | Best method to attain 1-hr. rating—standard frame const | a-1366 |
| 1 hr. | Gypsum Lath & Plaster Ceiling—wd joist—1" nom wd sub & fin flr— $\frac{3}{8}$ " ROCKLATH FIRECODE— $\frac{3}{8}$ " 100:2 gypsum perlite or STRUCTO-LITE plaster clg wt 5 | T-2134-1 OSU (f) | N/A | | clg matls 40 | Constr. same as FPRI No. 6 except for Striplath & plast. | a-1366 |
| 1 hr. | Gypsum Lath & Plaster Ceiling—wd joist—1" nom wd sub & fin flr— $\frac{3}{8}$ " perf ROCKLATH— $\frac{1}{2}$ " 100:2½ gypsum perlite plaster clg wt 7 | GA-NBS-258 (f) | N/A | | clg matls 39 | Standard frame construction | a-1366 |

wall furring application

| | | | | | | | |
|---|--|---|---|---|-----|--|--------|
| — | Wood furring strips 16" o.c., Insulating ROCKLATH plaster base, $\frac{1}{2}$ " sanded basecoat plaster, lime putty coat | — | — | — | 138 | Does not isolate surface membrane from structural stresses | a-1366 |
|---|--|---|---|---|-----|--|--------|

description

In these fire-resistant assemblies ROCKLATH Plaster Base is attached directly to wood studs or joists with nails or staples spaced approximately 5" o.c. The ROCKLATH is usually placed with end joints staggered and applied with the long dimension across the framing members by two different methods described below. The assemblies when completed with metal accessories and plaster provide an economical, adaptable, crack-resistant construction for walls and ceilings—also abrasion-resistant and easily decorated.

In the BRIDJOINT* Lathing System for both walls and ceilings, the ROCKLATH is placed so the end joints occur between supports. Specially designed BRIDJOINT B-1 Field Clips are used to hold the ends of the lath together and in alignment. At interior corners the ROCKLATH is partially nailed to each framing member and is held rigidly in place with BRIDJOINT B-2 Corner Clips. This design produces "floating angles" that increase resistance to cracking at these vulnerable junctions. This system assures additional strength because the ends of the lath do not butt on framing members which are subject to movement; provides economies that more than offset the cost of the clips.

In the nail-on method of application, the ROCKLATH is placed so the end joints occur over supports. The end joints must be fastened to the supports and Cornerite reinforcing used in the interior angles. By partially nailing the ROCKLATH and securing the Cornerite only to the ROCKLATH (not the framing), "floating angle" construction may also be employed with this system. Additional waste for cutting Cornerite reinforcing and 33% more nailing are required with the nail-on method than with the BRIDJOINT system.

ROCKLATH Plaster Base and plaster applied to staggered wood studs with THERMAFIBER* Insulating Wool Blankets inserted in the wall cavity provide a partition with very good sound control that is suitable for use as a party wall (see table above). Insulating ROCKLATH and plaster over wood furring strips spaced 16" o.c. offer an economical insulative exterior wall furring assembly with an effective vapor barrier.

ROCKLATH, a gypsum core faced on both sides with special paper, forms a rigid base for the economical application of gypsum plasters. For these assemblies, ROCKLATH is available in two thicknesses, four types (Plain, FIRECODE, Perforated and Insulating) and three sizes (see Specifications, page 2).

(continued on page 2)

A.I.A. File No. 20-B-2.1

description (continued from page 1)

In perforated ROCKLATH, $\frac{3}{4}$ " round holes are punched through the lath 4" o.c. in each direction to provide a mechanical key in addition to the natural plaster bond. Insulating ROCKLATH with bright aluminum foil laminated to the back side provides an effective vapor barrier at no additional labor cost.

function and utility

Versatility—ROCKLATH and plaster assemblies are readily adapted to virtually every type of new construction and remodeling. They satisfy most design and job conditions in commercial, industrial and residential applications where fire protection is required for wood framing. They can be used for interior partitions and ceilings, party walls, and exterior furring.

Fire Resistance—One- and two-hour fire ratings have been established. The systems provide acceptable fire protection for wood framing members on walls and ceilings.

Sound Control—The basic partition has a 41 Sound Transmission Class (STC). With staggered wood studs and THERMAFIBER Blankets, a 50 STC has been obtained.

Crack Resistance—Superior strength and resistance to cracking is offered by the BRIDJOINT system of lathing.

Economy—The flexibility of design, the high utilization of materials, the savings in nailing and reinforcement, all combine to make BRIDJOINT lathing an economical system.

sound attenuation factors

| test no. | method | decibel frequency in cps | | | | | | | | | | | STC |
|-----------|--------|--------------------------|-----|------|-----|-----|-----|------|------|------|------|------|-----|
| | | 125 | 175 | 250 | 350 | 500 | 700 | 1000 | 1400 | 2000 | 2800 | 4000 | |
| TL-58-64 | Lab | 40 | 40 | 41.5 | 44 | 48 | 53 | 53.5 | — | 47 | — | 57 | 50 |
| TL-61-232 | Lab | 33 | 37 | 44 | 45 | 45 | 45 | 58 | 43 | 42 | 48 | 54 | 42 |
| NBS-148 | Lab | 33 | 28 | 31 | 35 | 39 | 44 | 46 | — | 49 | — | 66 | 40 |
| NBS-714 | Lab | 33 | 32 | 26 | 32 | 33 | 39 | 41 | 45 | 48 | 56 | 62 | 37 |

limitations

Maximum support spacing: 16" o.c. for $\frac{3}{8}$ " ROCKLATH; 24" o.c. for $\frac{1}{2}$ " ROCKLATH.

specifications

notes to architect


1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55° F. Before lathing, ventilation should be provided to carry off excess moisture.

2. Lath and plaster surfaces will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from the following structural elements by control joints, "floating angles," or other means where:


a. a partition or ceiling abuts any structural elements, dissimilar wall or partition assembly, or other vertical penetration.

(continued on page 4)

components



BRIDJOINT B-1
field clip




BRIDJOINT B-2
corner clip

see Plaster Bases product catalog for
full description on accessories & sizes



USG
selv-edge
cornerite



USG
1-A
expanded
corner bead




USG
4-R
expanded
flange
corner bead




USG
10-A
expanded
bull nose
corner bead


USG casing beads (expanded or short flange)




#66 square edge




#60 semi-square



#4 or #138 quarter round



wood frame BRIDJOINT clip attachment



wood frame nail-on attachment



direct attachment

partitions





a

ROCKLATH* and Wood Framing
PLASTER BASE


1366

details

scale: 3" = 1'-0"




wood door frame




alt. wood door frame


bath and shower details



steel tub



precast shower receptor



hot mopped sub-pan

specifications (continued from page 2)

- b. the construction changes within the plane of the partition or ceiling.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling may be used as control joints. For doors less than ceiling height, control joints extending from the center or both corners of the frame to the ceiling may be used.

Expansive ceiling areas should have control joints, spaced not to exceed 50' in either direction. The continuity of both lath and plaster should be broken under control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

3. Holes cut in a thin lath and plaster membrane such as door frames, borrowed lights, vents, grilles, access panels, light troffers, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy and design, a control joint is not otherwise specified.

4. Where contact or furred ceilings occur under roof construction, the plenum or attic space should be vented according to recommended engineering practice.

5. To retain maximum sound isolation, the integrity of the partition or ceiling should not be voided by openings, such as doors, electrical outlets, medicine cabinets, vents etc., so as to create sound leaks. Use sand aggregate only; do not use lightweight aggregates. Caulk under runners, around openings, and partition perimeter.

6. Gypsum plaster can be satisfactorily used with radiant heating installations; see separate USG Systems Folder on RED TOP* Radiant Heat Plaster and Wood Framing for details.

7. Special precautions should be taken for proper application and use of ROCKLATH and gypsum plaster in bath and shower areas (see details, page 3).

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architect Service Department, 101 S. Wacker Dr., Chicago, Ill. 60606.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. ROCKLATH Plaster Base ($\frac{3}{8}$ ") ($\frac{1}{2}$ ") (Plain) (Perforated) (FIRECODE†) (Insulating) (16"x48"), (16"x96"), (24" x specified lengths).

- b. BRIDJOINT B-1 Field Clip.
c. BRIDJOINT B-2 Corner Clip.
d. USG® Selv-edge Cornerite (2"x2") (3"x3").
e. USG Casing Bead (specify type from page 2).
f. USG Corner Bead (specify type from page 2).
g. USG Self-Furring Junior Diamond Mesh Metal Lath.
h. Nails—13 ga. ($1\frac{1}{8}$ ") ($1\frac{1}{4}$ ") long, $\frac{19}{64}$ " flat head blued (not available from U.S.G.).
i. Staples—16 ga. galvanized flattened wire, flat crown $\frac{7}{16}$ " wide, ($\frac{7}{8}$ ") (1") legs having divergent points (not available from U.S.G.).

plaster base attachment

ROCKLATH Plaster Base shall be applied face out with the long dimension across the framing members and with end joints, staggered in successive courses. Ends of lath shall fall between framing members and be aligned and engaged using the BRIDJOINT B-1 Field Clip. All joints shall be butted together and the lath shall be accurately cut and neatly fitted around all electrical outlets, openings, etc. Apply BRIDJOINT B-2 Corner Clip at all interior angles.

Fasteners shall be (nails) (staples). For $\frac{3}{8}$ " ROCKLATH and maximum support spacing of 16" o.c. use 4 fasteners, 5" o.c., per 16" width of lath; 5 per 24" width of lath. For $\frac{1}{2}$ " ROCKLATH and maximum support spacing of 24" o.c. use 5 fasteners, 4" o.c., per 16" width of lath; 6 per 24" width of lath. Fasteners shall be placed at least $\frac{3}{8}$ " from edges and ends of lath. Staples shall be driven with the crown parallel to the framing member in such a manner that the crown bears tightly against the lath but does not cut the face paper.

All interior plaster angles shall be the floating type and shall have the first fastener spaced nominally 10" from corner. Use specified fastening in the remainder of the wall and ceiling area.

lathing accessories

a. Metal Corner Bead No. (000000) shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with galvanized staples, etc., spaced not over 8" o.c.; staggered in two wings.

b. Casing Bead No. (000000) shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Staple in place.

c. Reinforcing. Install a strip of self-furring diamond mesh lath over joints between dissimilar plaster bases. At all openings, reinforce the corners attaching a 12"x24" piece of self-furring diamond mesh lath diagonally across the corners. Staple in place.

d. Cornerite (2"x2")(3"x3") shall be installed in all interior plaster angles. Staple to the lath only (required for nail-on method only).

†Available on Pacific Coast only.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ROCKLATH, FIRECODE (plaster base); BRIDJOINT (metal clips); THERMAFIBER (insulation products); RED TOP, STRUCTO-LITE (plaster).

NOTE: Since methods and conditions of application and use are beyond our control, the United States Gypsum Company will not be responsible for failure of its products when not used according to our directions and specifications.

a-1366



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



resilient attachment

partitions

a

ROCKLATH* and Wood Framing

PLASTER BASE

1377

A.I.A. File No. 20-B-21

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|-------------------------------------|------------|----------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. | Wd Stud—Resil Gypsum Lath & Plaster—2x4 16" o.c.— 3/4" perf ROCKLATH—R-1 resil clips—1/2" 100:2 gyp- sum sand plaster wt 15 width 6 1/4" | T-1329-OSU (f) TL-60-20 (s) | 47 | | 160 | | a-1377 |
| 1 hr. est | Slot Wd Stud—Gypsum Lath & Plaster—2x4 slotted studs 16" o.c.—3" THERMAFIBER ins wool blkts—3/4" plain ROCKLATH—1/2" plaster wt 14 width 5 3/8" | TL-62-348 (s) | 44 | | 145 | | a-1377 |
| N/A | Wd Stud—Resil Gypsum Lath & Plaster—2x4 16" o.c.— 3/4" plain ROCKLATH appl direct one side—opp side base layer of 1/2" USG wd fiber sound dead bd appl direct & face layer of 3/4" ROCKLATH appl with R-5 resil clips—1/2" 100:2 1/2 gypsum sand plaster both sides —perimeter caulked wt 14.5 width 6 1/4" | USG-119-FT-G&H (s) | 54 | | 160 | Excellent sound attenuation | a-1377 |
| N/A | Wd Stud—Resil Gypsum Lath & Plaster—2x4 16" o.c.— 3/4" plain ROCKLATH—R-1 resil clips both sides—1/2" 100:2 1/2 gypsum sand plaster both sides—perimeter caulked wt 14.5 width 6 1/4" | USG-121-FT-G&H (s) | 54 | | 138 | Excellent sound attenuation at moderate cost | a-1377 |
| N/A | Wd Stud—Resil Gypsum Lath & Plaster—2x4 16" o.c.—3" THERMAFIBER ins wool blkts—3/4" plain ROCKLATH appl direct one side—opp side R-1 resil clips & 3/4" ROCKLATH—1/2" 100:2 1/2 gypsum sand plaster both sides—perimeter caulked wt 14.5 width 5 3/4" | CK-664-37 (s) USG-118-FT-G&H (s) | | 49 56 | | Outstanding sound attenuation through use of clips and insulating wool | a-1377 |

ceiling application

| | | | | | | | |
|-----|--|-------------|----|--|----------------|---|--------|
| N/A | Resil Gypsum Lath & Plaster Ceiling—wd joist—1" nom sub & fin flr—3/4" ROCKLATH appl with R-1 resil clips —1/2" gypsum sand plaster clg wt 6 | NBS-709 (s) | 52 | | clg mats 58 | Good resistance to air- borne sound; excellent crack resistance | a-1377 |
|-----|--|-------------|----|--|----------------|---|--------|

description

These fire-resistant assemblies consist of ROCKLATH Plaster Base and USG® gypsum plaster attached to wood studs or joists to provide a resilient surface that appreciably improves sound control through walls and ceilings. The ROCKLATH is attached (a) resiliently to the wood framing members with specially designed steel spring clips in the Resilient ROCKLATH System, or (b) directly to slotted 2x4 wood studs with the BRIDJOINT® Lathing System.

In the Resilient ROCKLATH System, the lath is placed so the end joints are staggered and occur over supports. R-1 Resilient Clips are nailed to one or both sides of the wood framing and spaced 16" o.c. to engage and align the lath at the end joints. R-2 Resilient Corner Clips are applied at all interior angles to provide floating corner construction. R-5 Resilient Clips are used to apply ROCKLATH over a base layer of 1/2" USG Wood Fiber Sound Deadening Board nailed to wood studs. These resilient clips isolate the lath and plaster from the framing and appreciably reduce the transmission of sound and structural movement to the outer surfaces of the plaster.

ROCKLATH applied to slotted 2x4 wood studs with the BRIDJOINT Lathing System provides a partition that offers sound control by separating the wall surfaces. In this construction 3" THERMAFIBER® Insulating Wool Blankets are inserted in the wall cavity between the studs. A 1/8" wide slot is cut in the center of the 4" dimension of the stud before erection. The slot, cut through the stud and extending to within three inches of each end, does not appreciably impair the stud's load-bearing properties. The use of slotted studs is covered by U.S. Patent No. 2,922,201 owned by United States Gypsum Company. Contractors desiring to use this system should apply to U. S. G. for a license.


The BRIDJOINT System uses a combination of nailing and clipping with specially designed BRIDJOINT Clips to apply the ROCKLATH. For details on this application, see USG Folder on direct attachment ROCKLATH base to wood framing.

ROCKLATH, a gypsum core faced on both sides with special paper, forms a rigid base for the economical application of

gypsum plasters. For these assemblies, ROCKLATH is available in two thicknesses, three types (Plain, Perforated and Insulating) and three sizes (see Specifications, page 3). In perforated ROCKLATH, 3/4" round holes are punched through the lath 4" o.c. in each direction to provide a mechanical key in addition to the natural plaster bond. Insulating ROCKLATH with bright aluminum foil laminated to the back side provides an effective vapor barrier at no additional labor cost.

function and utility

These systems satisfy most design and job conditions in new construction and remodeling to provide fire protection
(continued on page 3)





A.I.A. File No. 20-B-21






components/details




USG casing beads (expanded or short flange)




#4 or #138 quarter round #60 semi-square




resilient ROCKLATH plaster base attachment system




see "plaster bases" product catalog for full description on accessories & sizes



resilient ceiling attachment





wood frame resilient clip attachment



BRIDJOINT system with slotted studs

details



function and utility (continued from page 1)

to wood framing members, sound control and a hard, abrasion-resistant, easily decorated wall and ceiling surface.

Fire Resistance—One-hour fire-resistance ratings have been established. The systems provide acceptable fire protection for wood framing members in walls and ceilings.

Sound Control—The Resilient Clips reduce the transfer of air-borne sounds and produce a partition with up to 56 STC—suitable for party walls.

Crack Resistance—Resilient clip attachment markedly reduces the possible transmission of stresses due to structural movement to the lath and plaster membrane, thereby reducing the incidence of cracking.

Economy—The cost of resilient clips is small compared to the cost of alternate methods of achieving the desired sound isolation and crack-resistant characteristics. Increasing the mass of the construction, or employing staggered studs in partitions, are costly methods of improving sound transmission loss characteristics, and usually do not provide the additional crack resistance of resilient clips.

limitations

1. Maximum support spacing: 16" o.c. for 3/8" ROCKLATH; 24" o.c. for 1/2" ROCKLATH Plaster Base.
2. Three-coat plastering is required on resiliently attached ROCKLATH ceilings.
3. Perforated ROCKLATH is not recommended for resilient ceiling attachment.

sound transmission loss

| test no. | method | decibel frequency in cps | | | | | | | | | | | STC |
|----------------|--------|--------------------------|-----|-----|-----|-----|-----|------|------|------|------|------|-----|
| | | 125 | 175 | 250 | 350 | 500 | 700 | 1000 | 1400 | 2000 | 2800 | 4000 | |
| TL-62-348 | Lab | 39 | 42 | 45 | 49 | 48 | 48 | 50 | 45 | 44 | 48 | 54 | 44 |
| TL-60-20 | Lab | 42 | 43 | 46 | 49 | 51 | 52 | 52 | 48 | 47 | 52 | 56 | 47 |
| USG-119-FT-G&H | Lab | 31 | 46 | 46 | 48 | 54 | 58 | 60 | 60 | 58 | 63 | 66 | 54 |
| USG-121-FT-G&H | Lab | 31 | 42 | 46 | 50 | 54 | 57 | 59 | 57 | 54 | 56 | 63 | 54 |
| USG-118-FT-G&H | Lab | 35 | 45 | 46 | 50 | 55 | 58 | 59 | 59 | 59 | 63 | 63 | 56 |

specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.
2. Lath and plaster surfaces will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from the following structural elements except the floor by control joints, "floating angles", or other means where:
 - a. a partition or ceiling abuts any structural elements, dissimilar wall or partition assembly, or other vertical penetration.
 - b. the construction changes within the plane of the partition or ceiling.
- In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling may be used as control joints. For doors less than ceiling height, control joints extending from the center or both corners of the frame to the ceiling may be used.
- Expansive ceiling areas should have control joints, spaced not to exceed 50' in either direction. The continuity of both lath and plaster should be broken under control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.
3. Holes cut in a thin lath and plaster membrane such as door frames, borrowed lights, vents, grilles, access panels, light troffers, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy and design, a control joint is not otherwise specified.
4. Where contact or furred ceilings occur under roof construction, the plenum or attic space should be vented according to recommended engineering practice.
5. To retain maximum sound isolation, the integrity of the partition or ceiling should not be voided by openings such as doors, electrical outlets, medicine cabinets, vents, etc., so as to

*Reg. U.S. Pat. Off.

create sound leaks. Use sand aggregate only; do not use light-weight aggregates. Caulk under runners, around openings, and partition perimeter.

6. Gypsum plaster can be satisfactorily used with radiant heating installations; see separate Systems Folder on RED TOP* Radiant Heat Plaster Systems.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. ROCKLATH Plaster Base ($\frac{3}{8}$ " ($\frac{1}{2}$ ") (Plain) (Perforated) (Insulating) (16" x 48"), (16" x 96"), (24" x specified lengths).
- b. USG R-1 Resilient Field Clip.
- c. USG R-2 Resilient Corner Clip.
- d. USG R-5 Resilient Clip.
- e. USG R-SF Resilient Starter-Finisher Clip.
- f. BRIDJOINT B-1 Field Clip.
- g. BRIDJOINT B-2 Corner Clip.
- h. USG Casing Bead (specify type from page 2).
- i. USG Corner Bead (specify type from page 2).
- j. USG Self-Furring Junior Diamond Mesh Metal Lath.
- k. $\frac{1}{2}$ " USG Wood Fiber Sound Deadening Board, 4' x 8', 10', 12'.
- l. 3" THERMAFIBER* Insulating Wool Blankets.
- m. Nails—13 ga. ($\frac{1}{8}$ " ($\frac{1}{4}$ ") long, $\frac{1}{64}$ " flat head blued (not available from U.S.G.).
- n. Staples—16 ga. galvanized flattened wire, flat crown $\frac{7}{16}$ " wide, ($\frac{1}{8}$ " ($\frac{1}{4}$ ") legs having divergent points (not available from U.S.G.).

plaster base attachment

a. gypsum base—resilient attachment with R-1 clips

$\frac{3}{8}$ " ROCKLATH Plaster Base shall be applied with end joints staggered and with $\frac{1}{4}$ " space between the lath and the adjacent surfaces around the partition perimeter. R-SF Clips shall be nailed to the framing 16" o.c. at the top and bottom to provide attachment for the first and last courses of ROCKLATH. Gypsum lath shall be attached to the framing members with USG R-1 Resilient Clips nailed to framing and placed at every intersection of ROCKLATH edges with framing members. At corners, attach ROCKLATH with USG R-2 Resilient Clips so it is secured by the clips spaced 16" o.c. in both directions. USG Corner Beads and other specified lathing accessories shall be stapled only to ROCKLATH.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (plaster and metal products); RED TOP (plaster); ROCKLATH (plaster base); BRIDJOINT (metal clips); THERMAFIBER (insulation products).

a-1377

b. sound deadening board—resilient attachment with R-5 clips
 $\frac{1}{2}$ " wood fiber sound deadening board shall be applied with long dimension parallel to studs and with joints occurring over framing. Attach board with $\frac{1}{8}$ " long nails spaced 12" o.c. along the vertical edges and top and bottom plate and 30" o.c. along the intermediate framing.

ROCKLATH plaster base shall be applied face out with the long dimension across the framing members and with the end joints staggered in successive courses. ROCKLATH shall be attached to framing with USG R-5 Resilient Clips placed at every intersection of ROCKLATH edges with framing members. R-5 clips shall be attached with a 5d coated nail driven through the sound deadening board into the framing. $\frac{1}{4}$ " space between the lath and the adjacent surfaces shall be left around the partition perimeter.

c. direct attachment with BRIDJOINT lathing system

ROCKLATH Plaster Base shall be applied face out with the long dimension across the framing members and with end joints staggered in successive courses. Allow $\frac{1}{4}$ " clearance space between lath and the adjacent surfaces around the partition perimeter. Ends of lath shall fall between framing members and be aligned and engaged using the BRIDJOINT B-1 Field Clip. All joints shall be butted together and the lath shall be accurately cut and neatly fitted around all electrical outlets, openings, etc. Apply BRIDJOINT B-2 Corner Clip at all interior angles.

Fasteners shall be (nails) (staples). For $\frac{3}{8}$ " ROCKLATH and maximum support spacing of 16" o.c. use 4 fasteners, 5" o.c., per 16" width of lath; 5 per 24" width of lath. For $\frac{1}{2}$ " ROCKLATH and maximum support spacing of 24" o.c. use 5 fasteners, 4" o.c., per 16" width of lath; 6 per 24" width of lath. Fasteners shall be placed at least $\frac{3}{8}$ " from edges and ends of lath. Staples shall be driven with the crown parallel to the framing member in such a manner that the crown bears tightly against the lath but does not cut the face paper.

lathing accessories

a. Metal Corner Bead No. () shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with galvanized staples, etc., spaced not over 8" o.c., staggered in two wings.

b. Casing Bead No. () shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Staple in place.

c. Reinforcing. Install a strip of self-furring diamond mesh lath over joints between dissimilar plaster bases. At all openings, reinforce the corners attaching a 12" x 24" piece of self-furring diamond mesh lath diagonally across the corners. Staple in place.

d. Caulking—A non-hardening non-skinning resilient caulking compound shall be applied under plates, around outlet boxes and in the $\frac{1}{4}$ " space between the lath and adjacent surfaces around the partition perimeter.

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.




UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



direct attachment

partitions

a

SHEETROCK* GYPSUM WALLBOARD

1-Layer & Wood Framing

1387

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|--|------------|------|---------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. est | Stag Wd Stud— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd—2x3 16" o.c.—2x3 plates 1" apart—wallbd att 1 $\frac{1}{4}$ " Type W screws for 16" o.c.—2" THERMAFIBER ins wool blkts one side—perim caulked wt 8 width 7 $\frac{1}{2}$ " | USG-106-FT-G&H (s) USG-155-FT-G&H (s) | 51 49 | | 153 | Best value in 50 stc range for this type of party wall. 155-FT based on 2x6 common plate | a-1387 |
| 1 hr. | Slot Wd Stud— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd—2x4 slotted studs 16" o.c.—3" THERMAFIBER ins wool blkts—wallbd screw att 12" o.c. or nailed 7" o.c.—joints fin—perim caulked wt 7 width 4 $\frac{1}{2}$ " | UL Des 28-1 hr (f) USG-29-FT-G&H (s) | | 48 | 135 | | a-1387 |
| 1 hr. est | Wd stud— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd—2x4 16" o.c.—2" THERMAFIBER ins wool blkts—wallbd screw att with 1 $\frac{1}{4}$ " Type W screws 16" o.c.—joints fin—perim caulked wt 7 width 4 $\frac{1}{2}$ " | USG-105-FT-G&H (s) | 35 | | 131 | | a-1387 |
| 1 hr. | Wd Stud— $\frac{5}{8}$ " SHEETROCK FIRECODE or W/R FIRECODE "C" gypsum wallbd—2x4 16" o.c.—wallbd nailed 7" o.c.—1 $\frac{1}{2}$ " cem ctd nails—joints exp or fin—perim caulked wt 7 width 4 $\frac{1}{2}$ " | UL Des 5-1 hr (f) USG-30-FT-G&H (s) | | 34 | 111 | Sound rating obtained with joints taped | a-1387 |

ceiling applications

| | | | | | | | |
|-----------|--|---|----------|--------------------|--------------|---|--------|
| 1 hr. | $\frac{1}{2}$ " SHEETROCK FIRECODE "C" gypsum wallbd ceiling—1" nom wd sub & fin flr—2x10 wd joist 16" o.c.—wallbd att with 5d cem ctd nails 6" o.c.—joints fin clg wt 3 | UL Des 42-1 hr (f) | | N/A | clg matls 23 | | a-1387 |
| 1 hr. | $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd ceiling—Amer Plywood Assn 2-4-1 flr 4x10 wd joist 48" o.c.—USG met fur chan spaced 24" o.c.—wallbd att with 1" Type S screws—joints fin clg wt 3 | UL Des 28-1 hr (f) | | N/A | clg matls 36 | Only 1-hr. residential drywall system based on 48" joist spacing | a-1387 |
| 1 hr. | $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd ceiling—1" nom wd sub & fin flr—2x10 wd joist 16" o.c.—wallbd att with 6d nails 6" o.c.—joints fin clg wt 3 | UL Des 1-1 hr (f) CK-6412-7 (s) CK-6412-8 (s) | 37 38 | (INR) -19 +5 | clg matls 26 | In CK-6412-8 test, 44-oz. carpet & 40 oz. pad added atop flooring | a-1387 |
| 1 hr. est | $\frac{5}{8}$ " SHEETROCK gypsum wallbd ceiling—1 $\frac{1}{4}$ " nom wd sub & fin flr—2x10 wd joist 16" o.c.—3" THERMAFIBER ins wool blkts betw joists—wallbd att with 6d nails 6" o.c.—joints fin clg wt 3 | CK-6412-6 (s) CK-6412-5 (s) | 40 39 | (INR) -18 +7 | clg matls 35 | In CK-6412-5 test, 44-oz. carpet & 40-oz. pad added atop flooring | a-1387 |
| 45 min. | $\frac{1}{2}$ " SHEETROCK FIRECODE gypsum wallbd ceiling—1" nom wd sub & fin flr—2x10 wd joist 16" o.c.—wallbd att with 5d cem ctd nails 6" o.c.—joints fin clg wt 3 | UL Des 1-45 min (f) NBS-716 (s) | | | clg matls 23 | Basic 45-min assembly—sound attenuation test | a-1387 |

wall furring application

| | | | | | | | |
|---|---|---|---|---|-----|---|--------|
| — | Wood furring strips 16" o.c.— $\frac{1}{2}$ " Insulating SHEETROCK, PERF-A-TAPE Joint Treatment | — | — | — | 100 | Surface not isolated from structural stresses | a-1387 |
|---|---|---|---|---|-----|---|--------|

description


This basic drywall load-bearing construction is suitable wherever fire protection is desired with wood framing. SHEETROCK Gypsum Wallboard is applied direct to wood framing members—either vertically, with long edges parallel to framing, or horizontally with long edges at right angles to framing members. Horizontal application, recommended except in fire-rated partition construction or for predecorated wallboard, provides greater strength, reduces joint treatment and blocking needed, compensates for unevenness in framing alignment. Fastening of wallboard is by four alternate methods:

1. *Standard single nailing*—spacing c. to c. 6" to 7" for ceilings, 7" to 8" for walls.
2. *Double nailing*—for minimizing defects due to loosely nailed wallboard. First nails spaced 12" o.c., followed by second nails within 2" of first.
3. *Screw application*—best known insurance against fastener pops caused by loosely attached board. 1 $\frac{1}{4}$ " USG® Type W Drywall Screw is used.
4. *Adhesive nail-on*—continuous bead of SHEETROCK Brand DWA-14 or DWA-10 Adhesive applied to framing plus supplementary nailing; improves bond strength by 50% to 100%, greatly reduces face nailing needed.

This assembly is completed by finishing with the PERF-A-TAPE* or DURABOND* Joint System and decorating—both steps unne-


cessary in walls, however, when predecorated ULTRAWALL* or SHEETROCK Vinyl panels are used. SHEETROCK for this construction is available in three thicknesses and seven types. With Insulating (foil back) SHEETROCK Wallboard the system is effective as a vapor barrier, offers significant insulating value, and provides economical furring for exterior walls.

(continued on page 6)



slotted stud
partition
with wool

components




tapered edge
SHEETROCK
gypsum wallboard



beveled edge, vinyl
coated SHEETROCK
gypsum wallboard

see "gypsum wallboard and joint treatment" product
catalogs for full description on accessories & sizes



USG control
joint #093



1-1/4" USG drywall screw—type W—bugle head



1-1/4" GWB-54 annular ring nail



1-3/8" annular ring nail



1-5/8" 5d gypsum wallboard nail cement coated




1-7/8" 6d gypsum wallboard nail cement coated




1-1/8" USG matching color nail (steel)




1-3/8" USG matching color nail (brass)




divider




end cap



inside corner



outside corner



no. 100 PERF-A-BEAD* reinforcement




DUR-A-BEAD corner reinforcement




no. 200-A USG metal trim



no. 200-B USG metal trim









no. 200-C USG metal trim











PERF-A-TRIM* reinforcement



USG metal trim



details



Exterior wall assembly with foil-backed Insulating SHEETROCK Wallboard, THERMAFIBER Insulating Wool, FIRECODE* Sheathing, MAYFAIR Plastic-Surface Mineral Siding.


*Reg. U.S. Pat. Off.

details


back-blocking procedure



A. Wallboard is applied with long edges at right angles to joists. Backing blocks 8" wide, cut from scrap wallboard, are cemented and placed along full length of edge and ends of board. Floating of end joints makes it easier to form a good joint over a twisted stud or joist.



B. Immediately after all blocks are in place, the next board, which has been previously cut, is erected. Ends are loosely butted.



C. Cross section shows how floated end joint is tapered and back blocked. Brace is temporarily nailed over wood strip (top drawing) which depresses ends of boards. When strips are removed, tapered formation remains as shown in bottom drawing.



D. Side wall blocks are positioned between studs, held flush with face by wallboard strips which have been recessed against sides of studs. Blocking must be flush or slightly back of nailing face of studs.



E. After wallboard panel is nailed in place, adjacent panel is immediately butted over backing block. End joints between upper and lower courses of panels are staggered.



F. To complete back blocking of both sides of a critical wall, same procedure is followed on opposite side of wall. High ridges of cement are applied so as to be at right angles to horizontal joint formed by SHEETROCK soon to be applied.



G. Application of top sheet of wallboard follows immediately after spreading adhesive on the blocks. After 24 to 48 hours drying time, joints are treated in normal manner.



direct attachment

partitions



a

SHEETROCK* GYPSUM WALLBOARD
1-Layer & Wood Framing


1387

details

adhesive nail-on system




straight bead





zigzag bead

Full information on systems shown here is available in USG Gypsum Dry-wall Construction Handbook, WB-52

floating interior angle system



double nailing system



description (continued from page 1)

Two other proven methods upgrade job quality:

Back-Blocking Joint Reinforcement—a patented system designed to minimize an inherent joint deformation ("ridging") that may occur with adverse job and weather conditions.

Floating Interior Angle System—application of board to effectively reduce nail pops and angle cracking which may result from stresses at intersections of walls and ceilings.

function and utility

An economical, quickly completed method of constructing walls and ceilings where fire resistance requirements do not exceed one hour—also usable for open porch and carport ceilings and soffits of eaves and rakes when the construction protects the SHEETROCK Wallboard from direct contact with water (see Details and Specifications). Variations of the system meet other special requirements as outlined below.

Fire Resistance—1-hour rating for partition with $\frac{5}{8}$ " SHEETROCK FIRECODE* gypsum wallboard and for ceiling with $\frac{1}{2}$ " SHEETROCK FIRECODE "C" wallboard (see table, page 1).

Sound Isolation—Where a party wall with maximum sound loss is required, best value in its class is the staggered 2x3 stud partition (see table, page 1) with STC of 51. Erected on plates 1" apart, partition has single-layer $\frac{5}{8}$ " SHEETROCK FIRECODE facings and 2" THERMAFIBER* Insulating Wool Blankets in one side (see detail, page 3).

More economical, yet providing a 48 STC—suitable for party walls—is the patented USG Slotted Stud System conventionally framed but with $\frac{1}{8}$ " slots cut through studs lengthwise. $\frac{5}{8}$ " SHEETROCK FIRECODE face layers are backed by 3" THERMAFIBER Blankets between studs. For details, see systems folder on SHEETROCK/wood stud 2-layer construction.

Light Weight—SHEETROCK for these assemblies weighs approximately 2.6 psf in $\frac{5}{8}$ " thickness, 2.0 in $\frac{1}{2}$ ", and 1.5 in $\frac{3}{8}$ ". Conventional partition assemblies weigh 6 to 8 psf.

limitations

1. Maximum frame spacing: ceilings— $\frac{3}{8}$ " SHEETROCK, 16" o.c.; $\frac{1}{2}$ " and $\frac{5}{8}$ " SHEETROCK, 16" o.c. if applied with long edge parallel to framing or 24" o.c. if applied across the framing. Sidewalls— $\frac{3}{8}$ " SHEETROCK, 16" o.c.; $\frac{1}{2}$ " and $\frac{5}{8}$ " SHEETROCK, 24" o.c.

2. Not recommended where exposure to moisture is extreme or continuous. SHEETROCK W/R Wallboard, made water-resistant all the way through by special core and paper, is recommended as a base for wall tile in bathrooms and other high moisture areas (see USG Gypsum Wallboard Product Folder for details and specifications).

3. Where ceiling radiant heat is planned, 2-layer wallboard construction should be used (see separate USG Systems Folder).

4. Not recommended for exterior soffits and ceilings which project upwards and away from the building proper.

5. Direct attachment to wood framing with fastener penetration into wood exceeding 1" is not recommended except when required to meet fire rating.

specifications—notes to architect

1. Do not use any solvent-based adhesive for application of SHEETROCK Standard Vinyl Panel Wallboard over metal studs or treated wood framing. DWA-14 Adhesive by U.S.G. may be used for this application with SHEETROCK Custom Vinyl Panel Wallboard, and SHEETROCK VICRTEX A, B, C & T and VICRWALL Vinyl Panel Wallboard.

Because of the potential incompatibility between vinyl-surfaced wallboard and solvent-based adhesives, United States Gypsum cannot be responsible for problems arising from the use of either

its adhesives with vinyl-surfaced wallboard manufactured by others, or its vinyl-surfaced wallboard applied with adhesive manufactured by others.

2. Drywall partitions and ceilings will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements, except the floor, by control joints or other means where: (a) A partition or ceiling abuts any structural element or dissimilar wall or ceiling assembly; (b) The construction changes within the plane of the partition or ceiling.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

Expansive ceiling areas should have control joints spaced not to exceed 50' in either direction. The continuity of wallboard and supports should be broken over control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

3. Holes cut in a thin wallboard membrane such as door frames, borrowed lights, etc., cause a concentration of stresses in the wallboard. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

4. Where this partition is used as a sound barrier, the use of non-hardening caulking material to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure, is recommended. Eliminate cutting holes back to back and adjacent to each other. Door and borrowed light openings are not recommended when this partition is used as a party wall.

5. THERMAFIBER Insulation Blankets added to the stud cavity, pressed tightly in place, stapled to back of one partition face or sides of studs, will increase the sound transmission loss.

6. Where contact or furred ceilings occur under roof construction, the plenum or attic space should be vented according to recommended engineering practice.

7. For wood framing requirements, heating and ventilating recommendations, see USG Gypsum Wallboard Product Folder.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 70° F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Joint Treatment Folder for Joint Treatment Specifications.

Paint Products Folder for Paint Specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.



direct attachment

partitions

a

SHEETROCK* GYPSUM WALLBOARD
1-Layer & Wood Framing

1387

All materials herein specified shall be manufactured by the United States Gypsum Company unless otherwise indicated.

- a. Gypsum Board—48" wide—($\frac{3}{8}$ ") ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick Tapered Edge SHEETROCK (Regular) or (Insulating—foil back); ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick SHEETROCK FIRECODE; $\frac{1}{2}$ " thick SHEETROCK FIRECODE "C"; $\frac{3}{8}$ " thick ULTRAWALL panels (finish); $\frac{1}{2}$ " thick SHEETROCK Vinyl panels (finish); ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick SHEETROCK W/R Wallboard—lengths as required.
- b. Joint Treatment—PERF-A-TAPE or DURABOND Joint System.
- c. Adhesive
 - (for Back-Blocking System)—PERF-A-TAPE Joint Compound (embedding type).
 - (for Adhesive Nail-On Board Application)—SHEETROCK Brand DWA-14 or DWA-10 Adhesive.
- d. Fasteners
 - Screws— $1\frac{1}{4}$ " USG Drywall Screw Type W.
 - Nails (specify type from Pg. 2—not available from U.S.G. except for USG matching color nails).
- e. USG Metal Trim (specify type from Pg. 2).
- f. SHEETROCK Metal Moldings (for ULTRAWALL and SHEETROCK Vinyl Panels)—to match specified finishes.
- g. USG Corner Bead—DUR-A-BEAD*, PERF-A-BEAD*, ECONO Corner Reinforcement (specify type from Pg. 2).
- h. USG Control Joint No. 093.
- i. Wallboard Sealant (for SHEETROCK W/R Wallboard)—SHEETROCK Brand W/R Sealant.
- j. Caulking—Presstite 579.64 Mastic as manufactured by Presstite Division of Interchemical Corporation or equal.

wallboard erection (treated joints)

All ends and edges of all gypsum wallboard shall occur over nailing members, except when joints are at right angles to framing members as in horizontal application or when the end joints are to be backblocked.

SHEETROCK Wallboard shall be applied first to the ceiling and then to the walls. To minimize end joints, use wallboard of maximum practical lengths. Boards shall be brought into contact, but shall not be forced into place. Where ends or edges abut, they shall be neatly fitted.

End joints shall be staggered. Joints on opposite sides of a partition shall be so arranged as to occur on different studs.

Wallboard shall be attached to framing supports by: (Standard Single Nailing Method) (Adhesive—Nail-On Method) (Double Nailing Method) (Power-driven USG Drywall Screws).

Standard single nailing method—Attach wallboard with nails herein specified spaced not to exceed 7" o.c. for ceilings and 8" o.c. for walls.

Adhesive—nail-on method—Attach wallboard with SHEETROCK Brand (DWA-14) (DWA-10) Adhesive applied in a continuous $\frac{3}{8}$ " bead at the center of attachment to the face of framing members. Where two pieces of wallboard meet on a framing member, apply a serpentine bead with an 8" repeat pattern permitting adhesive contact to both panels. Do not apply adhesive to members such as bridging, diagonal bracing, etc., into which no supplemental fasteners will be driven. Immediately following contact of wallboard to adhesive, apply fasteners per manufacturer's directions.

Double nailing method—Attach wallboard with nails herein specified. Apply first nails spaced not to exceed 12" o.c. with second nails in close proximity (2").

Power-driven USG Drywall Screws—Attach wallboard with $1\frac{1}{4}$ " USG Drywall Screws Type W—spaced not to exceed 12" o.c. for walls and ceilings. For walls with studs 16" o.c., screws may be applied not to exceed 16" o.c.

Fasteners shall be spaced at least $\frac{3}{8}$ " from edges and ends of wallboard. Fasteners on all framing members shall be spaced and driven as recommended for specified fastening method. Nails shall not be staggered on adjoining edges or ends. Screws shall be staggered on adjoining edges or ends.

While the fasteners are being driven, the wallboard shall be held in firm contact with the underlying support. Attachment should proceed from central portion of the wallboard towards ends and edges. When nails are used for attaching gypsum wallboard, the nails shall be driven home with the heads slightly below the surface of the gypsum wallboard, in a dimple formed by the crowned face of the hammer striking the last blow. A nail set shall not be used, and care shall be taken to avoid breaking the paper face.

When necessary to cut ends, edges, scribe or make cutouts within the field of the wallboard, it shall be done in a workmanlike manner.

wallboard erection (predecorated ULTRAWALL or SHEETROCK Vinyl panels)

Panels shall be applied vertically to framing spaced (16") (24") o.c. Any panels used less than full width shall be positioned with the cut edge at corner.

Nail application—Color-matched nails shall be driven with plastic-headed hammer at 8" o.c. spacing into all studs. Edge nailings shall be at least $\frac{3}{8}$ " from panel edge.

Adhesive application—SHEETROCK Brand DWA-14 Adhesive shall be applied in continuous $\frac{3}{8}$ "x $\frac{3}{8}$ " bead in center of all stud faces. After partial drying of adhesive, panels shall be attached, impacted, and nailed with color-matched nails 16" o.c. along ceiling and floor edges of panels.

Panels shall be finished with SHEETROCK Aluminum Moldings matching specified finishes, according to manufacturer's directions.

wallboard erection (SHEETROCK W/R Wallboard)

(Follow specifications in USG Gypsum Wallboard Folder.)

back-blocking system

Notes to architect: Back blocking is used in single layer gypsum wallboard construction only. Maximum spacing of supports, 24" o.c.

Select Sections a, b, c or d below, depending upon job requirements. (Floating and tapering end joints requires back blocking. However, end joints may be back blocked without tapering.)

a. All ceiling end joints shall be floated, back blocked and tapered (except at perimeter of room).

b. All ceiling edge joints shall be back blocked (except at perimeter of room).

c. All side wall end joints shall be floated, back blocked and tapered.

d. All horizontal sidewall joints shall be back blocked.

e. Backing blocks shall be $\frac{3}{8}$ ", $\frac{1}{2}$ " or $\frac{5}{8}$ " SHEETROCK Gypsum Wallboard. Use $\frac{3}{8}$ " or $\frac{1}{2}$ " thick backing blocks for $\frac{1}{2}$ " wall finish; $\frac{1}{2}$ " or $\frac{5}{8}$ " thick blocks for $\frac{5}{8}$ " wall finish.

f. Adhesive shall be PERF-A-TAPE Joint Compound (embedding type).

g. All SHEETROCK Gypsum Wallboard shall be applied with the long edges at right angles to the framing. (Wood backing behind joints between framing supports is not required.) Use face side of blocks for lamination if foil back material is used.

h. When floated end joints are specified, gypsum wallboards shall be so positioned that the end joints shall occur midway between supports and per manufacturer's directions.

i. Backing blocks shall be applied where specified in strict accordance with directions of United States Gypsum Company.

floating interior angle system

a. Ceilings—SHEETROCK Wallboard for ceilings shall always be applied first. Standard framing practices for corner fastening shall be followed. Wallboard shall fit snugly at all angles.

Horizontal application—Conventional single nail or screw application shall be used where the end of the board abuts a wall intersection. Where the long edges of the board are parallel with the intersection, the first nail or screw shall be nominally 7" from the wall. Conventional nail or screw spacing shall be used in the remainder of the ceiling area.

Vertical application—Conventional single nail or screw application shall be used where the long edges of the board abut a wall intersection. Where the ends of the board are parallel to the intersection, the first nail or screw shall be nominally 7" from the wall intersection. Conventional nail or screw spacing shall be used for the balance of the ceiling area.

b. Sidewalls—All wallboard shall be applied to maintain firm contact at the ceiling line and to provide support to ceiling boards previously installed. Along the horizontal angle, the first nail or screw shall be nominally 8" from the ceiling intersection. At all vertical angles, omit only the corner fastening of the board that is first applied and overlapped in the angle. The overlapping board shall be nailed or screwed in the conventional manner. Conventional nail spacing shall be used in the remainder of the sidewall area.

c. The use of double nailing in conjunction with the floating interior angle system does not alter the nailing requirements for angles specified above. The system does not eliminate the need for conventional framing requirements and ordinary wood back-up or blocking at vertical internal angles.

wall furring application

Suitable wood furring strips shall be attached to exterior walls at 16" o.c. 1/2" Insulating SHEETROCK Wallboard shall be applied with the long dimension at right angles to furring strips and fastened with 1 1/4" USG Drywall Screws-Type W spaced 12" o.c. Joints and fastener heads shall be finished in the prescribed manner. Where there is a possibility of water penetration through the walls, an asphalt felt protection strip shall be installed between furring strips and the wall surface.

exterior ceilings and soffits

Notes to architect: In porch and carport ceilings, framing should be spaced not more than 16" o.c. for 1/2" SHEETROCK Wallboard and 24" o.c. for 5/8" SHEETROCK.

In soffits, for eave or rake projections of 26" or more, framing should be spaced not more than 16" o.c. for 1/2" SHEETROCK and 24" o.c. for 5/8" SHEETROCK. For eave or rake projections of 26" or less, framing may be spaced 24" o.c. provided both edges of the SHEETROCK Wallboard parallel to the building wall are supported by moldings or other suitable means.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: SHEETROCK (gypsum wallboard, adhesives); FIRECODE, ULTRAWALL (gypsum wallboard); USG (ceiling tile, sheathing, metal trim, drywall screws); THERMAFIBER (insulating wool); PERF-A-TAPE, DURABOND (joint treatment); DUR-A-BEAD, PERF-A-BEAD, PERF-A-TRIM, ECONO (corner reinforcement).

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

All edges and ends around perimeter of SHEETROCK exterior ceilings or soffits must be supported by moldings of sufficient size and fastened securely to prevent sagging of the wallboard. For best results, back-blocking of all joints, and floating of end joints, are recommended.

Such ceilings and soffits should be protected by (a) eave flashing strips extending inside face of exterior walls not less than 24" for pitches under 5 in 12, or 12" for pitches of 5 in 12 or over; (b) suitable metal drip edges extending not less than 3" under roof shingles; (c) fascia boards of sufficient width to provide minimum 1/4" drip below adjacent trim on underside of eave, rake or ceiling.

Attic spaces above open porches and carport ceilings should be provided with ventilation in compliance with FHA requirements for attic spaces over living quarters. When SHEETROCK is applied direct to rafters, vents should be provided at each end of each span.

Rafters or joist spaces should have minimum of 2" X full width provided with rafters or joists, screened vent at each end of each space.

Vent openings should be framed with wood and located within 6" of outer edge of eave.

Wood facings should be provided between SHEETROCK Wallboard ceilings or soffits of eaves and rakes, and brick or masonry work of any kind.

SHEETROCK Wallboard shall be applied with the long edges at right angles to framing members. Wallboard application and joint treatment shall be accomplished in the same manner prescribed for interior finishing of SHEETROCK. All exposed surfaces shall be painted with a minimum of two coats of USG exterior paint (specify from USG Paint Products Folder).

wallboard accessories

a. (PERF-A-TAPE) (DURABOND) Joint System shall be used on all face board joints and internal angles formed by the intersections of walls and ceilings (specify from USG Joint Treatment Folder).

b. Metal Corner Bead No. () shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.

c. Metal Trim No. () shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.

d. Fasteners shall be as shown on drawings or as herein specified. Fasteners shall be driven at least 3/8" from ends or edges of wallboard to provide uniform dimple not over 1/32" deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

e. Control Joints shall be provided as indicated and where detailed. Staple in place.

a-1387



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
 UEG
 Construction
 Section
 for
 Sales
 Office

partitions

a

1397

direct attachment

SHEETROCK* GYPSUM WALLBOARD
2-Layer & Wood Framing

A.I.A. File No. 20-B-21/23-L

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|---|------------|----------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 2 hrs. | Wd Stud—2 layers $\frac{5}{8}$ " SHEETROCK FIRECODE or W/R FIRECODE "C" gypsum wallbd—2x4 16" o.c.—base layer 6d nails 6" o.c.—face layer lamin to base—joints fin wt 12 width 6 $\frac{1}{8}$ " | UL Des 4-2 hr (f) TL-57-14 (s) | | 38 | 161 | Basic 2-hour partition constr. | a-1397 |
| 1 hr. | Stag Wd Stud— $\frac{5}{8}$ " SHEETROCK FIRECODE or W/R FIRECODE "C" gypsum wallbd—2 rows 2x3 stag & sep plates 1" apart—base layer of $\frac{1}{2}$ " USG wd fiber sound dead bd att with 6d ctd nails—face layer 7d ctd nails 7" o.c.—joints fin wt 9 width 8 $\frac{1}{2}$ " | UL Des 17-1 hr (f) USG-46-FT-G&H (s) | | 53 | 175 | Good sound isolation—party wall use | a-1397 |
| 1 hr. est | Slot Wd Stud— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd—2x4 slotted studs 16" o.c.—base layer of $\frac{1}{2}$ " USG wd fiber sound dead bd 2 sides att with 5d ctd nails 12" o.c.—face layer 6d ctd nails 8" o.c.—joints fin wt 8 width 5 $\frac{7}{8}$ " | USG-44-FT-G&H (s) | | 49 | 155 | Party wall use—good value | a-1397 |
| 1 hr. est | Slot Wd Stud— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd—2x4 slotted studs 16" o.c.—single layer screw appl one side—2 layers opp side base layer screw appl & face layer lamin—joints fin—perimeter caulked wt 8.8 width 5 $\frac{1}{2}$ " | USG 28-FT-G&H (s) | | 48 | 143 | Party wall use—good sound performance | a-1397 |
| 1 hr. est | Wd Stud— $\frac{5}{8}$ " SHEETROCK FIRECODE gypsum wallbd—2x4 16" o.c.—base layer of $\frac{1}{2}$ " USG wd fiber sound dead bd 2 sides att with ctd nails—face layer wallbd 6d ctd nails 8" o.c.—joints fin wt 8 width 5 $\frac{7}{8}$ " | IBI-20-FT-G&H (s) USG-43-FT-G&H (s) | | 50 36 | 151 | Party wall use—IBI-20-FT based on face layer wallbd strip lamin—perimeter caulked | a-1397 |
| 1 hr. | Wd Stud—2 layers $\frac{3}{8}$ " SHEETROCK gypsum wallbd lamin & nailed—2x4 16" o.c.—joints fin wt 7 width 5 $\frac{7}{8}$ " | T-118-48-48A-OSU (f) | N/A | | 133 | | a-1397 |
| 45 min. est | Wd Stud— $\frac{1}{2}$ " SHEETROCK gypsum wallbd—2x4 16" o.c.—base layer $\frac{1}{2}$ " USG sound dead bd att with 1 $\frac{5}{8}$ " ctd nails 12" o.c.—wallbd face layer strip lamin & 2 $\frac{3}{4}$ " ctd nails 24" o.c. into studs wt 7 width 5 $\frac{7}{8}$ " | IBI-5-FT-G&H (s) | | 42 | 162 | Good where sound resistance more important than fire rating | a-1397 |

For ceiling applications, see pages 4 to 7.

description

These "Double Wall" systems consist of a face layer of SHEETROCK Gypsum Wallboard job-laminated and/or nailed to a base layer of gypsum or wood fiber board and directly attached to wood framing in walls and ceilings. Because the systems minimize the use of mechanical fasteners in the face layer, finer appearance is the result—together with greater strength and higher fire and sound resistance.


A base layer of SHEETROCK Wallboard, BAXBORD* Gypsum Backing Board or USG® Wood Fiber Sound Deadening Board is nailed or screwed to the framing. The SHEETROCK face layer is applied to the base layer, then treated with the PERF-A-TAPE* Joint System, and decorated—the latter two steps unnecessary when predecorated ULTRAWALL* or SHEETROCK Vinyl panels are used as face layer.

Three alternate framing methods with wood studs spaced 16" o.c. provide load bearing support in constructions developed to meet fire resistance and sound control requirements in partitions:



1. Conventional 2x4 stud construction, two layers $\frac{5}{8}$ " SHEETROCK FIRECODE* Gypsum Wallboard, or FIRECODE or regular SHEETROCK over base layer of USG Wood Fiber Sound Deadening Board. These offer higher sound and/or fire ratings than did the original double wall assembly employing two layers of $\frac{3}{8}$ " SHEETROCK.
2. The patented USG Slotted Stud System, conventionally framed but with $\frac{1}{8}$ " slots cut through studs lengthwise. $\frac{5}{8}$ " SHEETROCK FIRECODE is applied as face layer over sound deadening board, or as double and single layers on opposite sides of the studs.
3. Double row of 2x3 staggered studs set on separate plates 1" apart, with face layer of $\frac{5}{8}$ " SHEETROCK FIRECODE nailed to base layer of sound deadening board. This provides optimum in sound isolation, STC of 53, where one-hour fire resistance (load bearing) is required.

SHEETROCK for these assemblies is available in three thicknesses and six types (see Specifications). Adhesive lamination of face layer to base layer, when both are gypsum wallboard, is by either of two methods: (a) *strip lamination*—USG Laminating Adhesive applied in vertical strips 24" o.c. and supplementary 1 $\frac{1}{2}$ " USG Drywall Screws Type G, or (b) *sheet lamination*—USG Laminating Adhesive or PERF-A-TAPE Joint Compound (embedding type) applied over the entire wallboard surface with supplementary Type G screws or temporary supports until adhesive dries. When base layer is wood fiber sound deadening board, face layer of gypsum wallboard is attached by strip lamination with either permanent face nailing or supplementary temporary nailing or support until adhesive dries.

(continued on page 5)



components



see "gypsum wallboard and joint treatment" product catalogs for full description on accessories & sizes



1-1/4" USG drywall screw—type W—bugle head




1 1/2" USG drywall screw—type G—bugle head



1-1/4" GWB-54 annular ring nail



2-1/2" 7d gypsum wallboard nail cement coated



1-7/8" 6d gypsum wallboard nail cement coated




1-5/8" 5d gypsum wallboard nail cement coated




1-7/8" USG matching color nail (steel)


SHEETROCK moldings




divider




end cap




inside corner




outside corner



no. 100 PERF-A-BEAD* reinforcement




DUR-A-BEAD corner reinforcement




no. 200-A USG metal trim



no. 200-B USG metal trim










no. 200-C USG metal trim




PERF-A-TRIM* reinforcement




USG metal trim





details



sheet lamination





strip lamination





details

double layer ceiling construction




typical layout electrical radiant heated ceiling

miscellaneous details




metal corner reinforcement

SHEETROCK W/R wallboard—installation details for tub and shower areas



tub

NOTE:
5/8" SHEETROCK W/R FIRECODE "C" gypsum wallboard base layer required for 1-hour fire rating



shower receptor



direct attachment

partitions

a

SHEETROCK® GYPSUM WALLBOARD
2-Layer & Wood Framing

1397

description (continued from page 1)

In order to further reduce the possibility of nail pops and angle cracking, the *floating interior angle* method of board application is recommended for the base layer in double-layer wall construction (see details and specifications in USG Folder on SHEETROCK/Wood Framing 1-layer systems). In addition, nailing of the two wallboard layers to form "floating" inside and outside corners is recommended (see Details, page 4).

function and utility

Sound Isolation—Excellent choices available for party wall use and other critical sound requirements—STC as high as 53 (see table, page 1). A non-hardening, non-skinning caulking compound was used to obtain the sound ratings shown.

Fire Resistance—2-hour rating with double layer of 5/8" SHEETROCK FIRECODE, one hour with four other recommended assemblies (see table, page 1). If a partition requires one-hour rating and sound is not a major consideration, 5/8" FIRECODE single-layer wood frame construction should be considered.

Economy—Wherever sound isolation is important, SHEETROCK systems using slotted wood studs (table page 1) and the RC-1 resilient channel (USG Systems Folder—SHEETROCK & RC-1/Wood Framing) deliver "more db for the dollar."

Low Maintenance—SHEETROCK double wall systems offer easy decoration, reduce possibility of nail "pops" and discoloration over nail heads.

Radiant Heated Ceilings—Double-layer gypsum wallboard also has been used extensively in electric cable radiant heated ceilings. Regular SHEETROCK is the base layer, heating cables are embedded in a filler, and face layer SHEETROCK is attached directly to the adhesive filler. See Details and Specifications for particulars.

limitations

1. Maximum frame spacing: 16" o.c. if 1-hour fire rating is required, also for ceilings with 3/8" base layer; 24" for ceilings with 1/2" base layer applied with long dimension applied across framing, also for all double-layer sidewalls if fire rating of one hour or more is not required.
2. Wall assemblies incorporating wood fiber sound deadening board are limited to interior partitions only.
3. Not recommended where exposure to moisture is extreme or continuous. Specially formulated SHEETROCK W/R Wallboard is recommended as a base for wall tile in bathrooms and other high moisture areas (see USG Gypsum Wallboard Product Folder for details and specifications).
4. In radiant heated ceilings where SHEETROCK wallboard is used, maximum surface temperature of the SHEETROCK must not exceed 115°F. Heating coils must not come into direct contact with SHEETROCK surfaces.
5. Direct attachment to wood framing with fastener penetration into wood exceeding 1" is not recommended except where required to meet fire rating.
6. Wood fiber sound deadening board is not recommended as a base layer for 2-layer flat or sloping ceilings with adhesive application of the face layer or as a base layer for radiant heated ceilings or SHEETROCK vinyl wallboard.

sound transmission loss

| test no. | method | decibel frequency in cps | | | | | | | | | | | STC |
|---------------|--------|--------------------------|-----|-----|-----|-----|-----|------|------|------|------|------|-----|
| | | 125 | 175 | 250 | 350 | 500 | 700 | 1000 | 1400 | 2000 | 2800 | 4000 | |
| USG-46-FT-G&H | Lab | 32 | 41 | 41 | 47 | 53 | 57 | 57 | 56 | 57 | 59 | 59 | 53 |
| USG-44-FT-G&H | Lab | 30 | 33 | 39 | 43 | 45 | 52 | 54 | 55 | 54 | 56 | 56 | 49 |
| USG-43-FT-G&H | Lab | 23 | 20 | 35 | 30 | 35 | 41 | 42 | 51 | 47 | 51 | 52 | 36 |
| IBI-5-FT-G&H | Lab | 19 | 28 | 34 | 38 | 43 | 50 | 52 | 54 | 55 | 56 | 54 | 42 |
| USG-28-FT-G&H | Lab | 29 | 34 | 39 | 43 | 44 | 50 | 51 | 51 | 46 | 49 | 53 | 48 |
| IBI-20-FT-G&H | Lab | 27 | 34 | 41 | 44 | 46 | 52 | 55 | 54 | 56 | 55 | 56 | 50 |

specifications

notes to architect

1. Drywall partitions and ceilings will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements, except the floor, by control joints or other means where:

- a. A partition or ceiling abuts any structural element or dissimilar wall or ceiling assembly.
- b. The construction changes within the plane of the partition or ceiling.

In long partition runs, control joints should be provided at no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

Expansive ceiling areas should have control joints spaced not to exceed 50' in either direction. The continuity of wallboard and supports should be broken over control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

2. Holes cut in a thin wallboard membrane such as door frames, borrowed lights, etc., cause a concentration of stresses in the wallboard. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.
3. Ceramic Tile—SHEETROCK® W/R Gypsum Wallboard is recommended as a base for the adhesive application of ceramic, metal and plastic tile (see USG Gypsum Wallboard Product Folder).
4. Where these partitions are used as a sound barrier, the use of non-hardening caulking material to seal all cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure, is recommended. Eliminate cutting holes back to back and adjacent to each other. Door and borrowed light openings are not recommended when this partition is used as a party wall.
5. Where contact or furred ceilings occur under roof construction, the plenum or attic space should be vented according to recommended engineering practice.

6. For wood framing requirements, heating and ventilating recommendations, see USG Gypsum Wallboard Product Folder.

7. The 1 1/2" USG Drywall Screw Type G is not recommended for fastening two-ply 3/8" SHEETROCK or BAXBORD® double wall. In this assembly scaffold nails driven through gypsum blocks at third points vertically, or temporary shoring should be used. The Type G Screw is not recommended for attaching gypsum face layers to wood fiber sound deadening board.

The most expedient way to obtain information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 70°F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Joint Treatment Folder for Joint Treatment Specifications.

Paint Products Folder for Paint Specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. Faceboards—48" wide—($\frac{3}{8}$ ") ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick Tapered Edge SHEETROCK; ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick SHEETROCK FIRECODE*; $\frac{3}{8}$ " thick ULTRAWALL* panels (finish); $\frac{1}{2}$ " thick SHEETROCK Vinyl panels (finish)—lengths as required.
- b. Backing Board—48" wide—($\frac{3}{8}$ ") ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick (Tapered Edge) (Insulating) SHEETROCK; ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick SHEETROCK FIRECODE; ($\frac{3}{8}$ ") ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick BAXBORD* Gypsum Backing Board; ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick BAXBORD FIRECODE, $\frac{1}{2}$ " thick USG Wood Fiber Sound Deadening Board—lengths as required.
- c. 48" wide, ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") thick SHEETROCK W/R Gypsum Wallboard—as required (for bathrooms, other high moisture areas).
- d. Joint Treatment—PERF-A-TAPE or DURABOND Joint System.
- e. Laminating Adhesive—USG Laminating Adhesive or PERF-A-TAPE Joint Compound (embedding type).
- f. Fasteners
 - Screws—1 $\frac{1}{4}$ " USG Drywall Screw—Type W.
 - Nails (specify type from Pg. 2—not available from U.S.G. except USG matching color nails).
 - Staples—16 ga. flat galvanized wire, $\frac{1}{2}$ " wide, (1") (1 $\frac{1}{8}$ ") (1 $\frac{1}{4}$ ") long with divergent points (not available from U.S.G.).
- g. USG Metal Trim (specify type from Pg. 2).
- h. SHEETROCK Metal Moldings (for ULTRAWALL and SHEETROCK Vinyl Panels)—to match specified finishes as required.
- i. USG Corner Bead—DUR-A-BEAD*, PERF-A-BEAD*, ECONO Corner Reinforcement (specify type from Pg. 2).
- j. THERMAFIBER* Insulating Wool Blankets (thickness).
- k. Wallboard Sealant (for SHEETROCK W/R Wallboard)—SHEETROCK Brand W/R Sealant.
- l. Caulking—Presstite 579.64 Mastic as manufactured by Presstite Division of Interchemical Corporation or equal.

base layer erection (gypsum wallboard)

Ceilings—Base layer gypsum wallboard shall be applied with long edges perpendicular to framing members. End joints may occur on or between framing members, and shall be positioned to offset face layer joints by at least 10".

Walls—Base layer gypsum wallboard shall be applied with long edges parallel to and centered on framing members. Wallboard shall be attached to framing supports by: (screw) (nail) (staple) attachment, as follows:

Screw attachment—The base layer shall be screw-applied to framing members with power-driven USG 1 $\frac{1}{4}$ " drywall screws—Type W spaced not to exceed 12" o.c. for walls and ceilings. For walls with studs 16" o.c., screws may be applied not to exceed 16" o.c.

Nail attachment—The base layer shall be nailed to framing members with the recommended nails for the wallboard thickness and type used, spaced 7" on ceilings and 8" on walls (spaced 12" if double nailing used). The nailheads shall be driven flush with surface of board.

Staple attachment—The base layer shall be attached to framing members with power-driven staples of type above specified, spaced 7" on ceilings and 8" on walls.

Screws shall be staggered on adjoining edges or ends. Nails shall not be staggered on adjoining edges or ends. While the fasteners are being driven, the wallboard shall be held in firm contact with the underlying support. Attachment should proceed from the central portion of the wallboard toward ends and edges.

base layer erection (wood fiber sound deadening board)

The base layer of wood fiber sound deadening board shall be applied (vertically) (horizontally) with joints staggered on opposite sides of the partition. Board shall be fastened to wood studs on each side of the partition with (5d) (6d) cement coated gypsum wallboard nails spaced 12" o.c.

face layer erection (treated joints)

Gypsum wallboard of maximum practical lengths shall be used in order to minimize end joints. Boards shall be loosely butted and neatly fitted at joints. All joints in face layer shall fall at least 10" from parallel joints in base layer.

When necessary to cut ends, edges, scribe or make cutouts within the field of the wallboard, it shall be done in a workmanlike manner.

After face layer panels have been cut to size, adhesive shall be mixed, applied and boards laminated in place according to the manufacturer's directions and in the following manner:

Sheet lamination—PERF-A-TAPE Joint Compound (embedding type) or USG Laminating Adhesive shall be mixed according to manufacturer's directions and applied to the entire back surface of face boards and to the extreme edges of the board. Adhesive shall be applied in beads approximately $\frac{3}{8}$ " wide at the base and $\frac{1}{2}$ " high and spaced 4 $\frac{1}{2}$ " o.c. Face boards shall then be laminated to base layer boards using moderate pressure and (temporary nailing) (temporary supports) (USG Drywall Screws) as follows:

1. **Temporary nailing** with nails that have at least $\frac{3}{4}$ " penetration into the framing shall be used to provide support for the face layer every 16" to 24" and insure adequate bond. When proper bond is developed between the two layers, nails shall be removed and nail holes properly dimpled before applying joint treatment.

2. **Temporary supports** consisting of bracing or shoring shall be used to provide support for the face layer every 16" to 24" and insure adequate bond. When proper bond is developed supports shall be removed.

3. **USG Drywall Screws** shall be used to permanently attach face boards to base layer boards. 1 $\frac{1}{2}$ " USG Drywall Screws Type G shall be placed along the vertical edges spaced 36" o.c. maximum, within 2' of joint and 12" of both ends. Screws in the field of the board at the centerline of the panel shall occur 18" o.c. maximum and within 24" of both ends.

Strip lamination—USG Laminating Adhesive or PERF-A-TAPE Joint Compound (embedding type) shall be mixed according to manufacturer's directions and applied to base layer boards in strips, 2" o.c. running continuously from floor to ceiling. Each adhesive strip shall consist of four beads $\frac{1}{2}$ " high and $\frac{3}{8}$ " wide at the base and spaced 1 $\frac{1}{2}$ " to 2' o.c.



direct attachment

partitions

a

SHEETROCK* GYPSUM WALLBOARD
2-Layer & Wood Framing

1397

Face layer boards shall then be laminated to base layer boards using moderate pressure and 1½" USG Drywall Screws Type G placed to penetrate the adhesive strips. Screws along vertical edges shall occur 36" o.c. maximum, within 2" of joint and 12" of both ends. Screws in the field of the board at the centerline of the panel shall occur 48" o.c. maximum and within 24" of both ends.

face layer erection over wood fiber sound deadening board with nails

(Specify first two paragraphs from Face Layer Erection—Treated Joints section, above.)

After face layer panels have been cut to size, the ⅝" SHEETROCK FIRECODE face panels shall be applied (horizontally) (vertically). Face layer shall be fastened with (6d) (7d) cement coated nails spaced (7") (8") o.c. and staggered from nails in wood fiber deadening board.

face layer erection over wood fiber sound deadening board with strip lamination

(Specify first two paragraphs from Face Layer Erection—Treated Joints section, above.)

After face layer panels have been cut to size, they shall be applied vertically using the PERF-A-TAPE Joint Compound (embedding type) strip lamination system. Joint compound shall be mixed according to manufacturer's directions and applied to base layer (not allowed to set for more than 15 min.) or back surface of face layer in strips, 2' o.c. running continuously from floor to ceiling. Each adhesive strip shall consist of four beads ⅝" high and ½" wide at the base and spaced 1½" to 2" o.c. Face layer boards shall then be laminated to base layer boards using moderate pressure and temporary nailing or supports until adhesive is dry.

face layer erection (predecorated ULTRAWALL or SHEETROCK Vinyl panels)

Panels shall be applied vertically according to manufacturer's directions. Any less than full width panels used shall be positioned with cut edge at corner. Boards shall be loosely butted and neatly fitted at joints. All joints in face layer shall fall at least 10" from parallel joints in base layer.

(Specify laminating procedure from Face Layer Erection—Treated Joints section, above.)

When nail application is used for ULTRAWALL panels, 1⅞" USG color-matched steel nails shall be driven with plastic-headed hammer at 8" o.c. spacing through base layer into all studs.

(Optional) Panels shall be finished with SHEETROCK Aluminum Moldings matching specified finishes of ULTRAWALL or SHEETROCK Vinyl panels, according to manufacturer's directions.

SHEETROCK W/R wallboard erection

(Follow specifications in USG Gypsum Wallboard Product Folder.)

fastening for "floating corner" construction

At inside corners, only the overlapping panel of the base layer board shall be nailed to the corner framing, thus securing both boards into the corner without nailing of the face layer.

At outside corners, only the face layer board, not the base layer, shall be nailed to the corner framing. When nail-on corner reinforcement is to be applied, either temporary nailing of the face layer shall be used or the permanent nails shall be driven to penetrate the framing approximately ¾" and shall be countersunk or concealed by the corner reinforcement.

fastening for "floating interior angle" construction

(Follow specifications in USG Systems Folder—SHEETROCK/1-layer & Wood Framing for base layer.)

board erection for radiant heated ceilings

Notes to architect

In radiant heated ceiling in which the heating elements are located between two layers of SHEETROCK gypsum wallboard, certain precautions are necessary in order to minimize the possibility of defects developing after installation. Among these are cracking due to thermal shock, shadowing due to unequal initial drying rates, and calcination of gypsum wallboard due to overheating (see Limitations, Page 5). The following partial specifications must be supplemented and adapted to conform to the heating engineer's design.

Fasteners—The base layer of gypsum board shall be applied horizontally direct to framing members. **Screws**: shall be spaced 24" o.c. for base layer. **Nails**: shall be spaced 7" for base layer and 16" o.c. for face layer. Alternate: Where filler is not used as an adhesive, space base layer nails 14" o.c.; face layer nails 7" o.c. Nails to be used shall be (base layer) 1¼" GWB-54 for ⅝" and ½" thick board, 1⅜" GWB-54 for ⅝" thick board; (face layer) GWB-54 or coated nails providing ¾" and 1" penetration, respectively. Nails shall be driven flush with surface in base layer; heads shall be slightly recessed and dimpled in face layer and shall remain in place for conventional finishing with joint treatment. **Staples**: may be used in the base layer only and shall be spaced 7" and be driven at no less than ⅜" from ends and edges of gypsum wallboard. Staples to be used shall be 16 ga. flat galvanized wire, ⅞" wide crown, 1" long legs for ⅝" thick board, 1⅞" legs for ½" board, 1¼" legs for ⅝" thick board, all with divergent points. Staples shall be driven with crown at right angles to long dimension of framing member, except where paper bound edges fall on framing members; then staples shall be driven parallel to edges. Staples shall be driven in such a manner that crown bears tightly against wallboard, but does not cut into face paper.

Radiant electric cable systems—Base layer of SHEETROCK wallboard shall be horizontally applied to joists, and electric heating cables shall be securely attached to wallboard and spaced in accordance with cable manufacturer's recommendations. Cables shall be positioned parallel to and between nailing members, so that at least a 2½" unobstructed channel is provided under each nailing member. Cables shall cross nailing members only near edges of ceiling, within a 4" to 6" area from wall. A space of at least 4" shall be left around perimeter of each ceiling, and of at least 8" around all openings, which is completely clear of cable.

All inspections and testing of the electrical heating system shall be completed before application of face layer of gypsum wallboard. Filler shall be DURABOND Joint Compound and ASTM C-35 sand mixed in the proportion of 1:1 by weight. Heating elements shall be completely embedded in a filler leveled to provide complete contact between face layer and base layer of wallboard. (Where filler serves as adhesive to hold face layer, nail spacing may be 7" o.c. for base layer and 16" o.c. for face layer.) (If necessary, furring strips of same thickness as layer of filler may be attached over base layer parallel to joists.) Face layer shall be erected immediately after filler has been spread. Where base layer is supported by furring strips attached to wood beams, trusses or joists spaced over 24" o.c. the DURABOND filler or fill coat shall be applied and allowed to dry completely. A thin adhesive coat of DURABOND Joint Compound shall be applied and the face layer erected and fastened with nails 7" o.c. Face layer nails shall be spaced 8" to 10" away from walls at all ceiling perimeters. Minimum of one week with good drying conditions, and two weeks in cold season, shall be allowed after completion before system is operated.

wallboard accessories

a. (PERF-A-TAPE) (DURABOND) Joint System shall be used on all face board joints and internal angles formed by the

intersections of walls and ceilings (specify from USG Joint Treatment Product Folder).

b. **Metal Corner Bead No.** () shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.

c. **Metal Trim No.** () shall be securely installed where

indicated. Finish with PERF-A-TAPE Joint Compound, as required.


d. **Fasteners** shall be as shown on drawings or as herein specified. Fasteners shall be driven at least $\frac{3}{8}$ " from ends or edges of wallboard to provide uniform dimple not over $\frac{1}{32}$ " deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

e. **Control Joints** shall be provided in the face layer as indicated and where detailed. Staple in place.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: SHEETROCK (gypsum wallboard, mouldings, adhesives); FIRECODE, ULTRAWALL, BAXBORD (gypsum board); USG (wood fiber board, metal products, adhesives); PERF-A-TAPE, DURABOND (joint treatment); THERMAFIBER (insulating wool); DUR-A-BEAD, PERF-A-BEAD, PERF-A-TRIM (corner reinforcement).

a-1397

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



resilient attachment

partitions

a

SHEETROCK* & RC-1/Wood Framing
 GYPSUM WALLBOARD

1407

A.I.A. File No. 20-B-21/23-L

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|---|------------|------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. est | Wd Stud—Resil SHEETROCK gypsum wallbd 2 layers one side & 1 layer opp side—2x4 16" o.c.—RC-1 chan both sides spaced horiz 24" o.c.—1 layer 5/8" wallbd screw att one side—opp side base layer of 5/8" wallbd screw att & face layer of 1/2" wallbd lamin—joints fin—perimeter caulked wt 8.7 width 6 1/2" | TL-61-10 (s) | 48 | | 146 | | a-1407 |
| 1 hr. | Wd Stud—Resil 5/8" SHEETROCK FIRECODE "C" gypsum wallbd—2x4 16" o.c.—3" THERMAFIBER ins wool blkts—RC-1 chan one side spaced 24" o.c.—wallbd att with 1" Type S screws—opp side direct att with 1 1/4" Type W screws—joints fin—perimeter caulked wt 7 width 5 3/8" | UL Des 27-1 hr (f) USG-33-FT-G&H (s) | 52 | | 134 | Best value of wood stud drywall party walls | a-1407 |
| 1 hr. | Wd Stud—Resil 5/8" SHEETROCK FIRECODE gypsum wallbd—2x4 16" o.c.—RC-1 chan both sides spaced horiz 24" o.c. att with 6d nails—wallbd att with 1" Type S screws—joints fin—perimeter caulked wt 7 width 5 3/8" | T-1396-OSU (f) TL-60-52 (s) | 45 | | 127 | Fully resilient 1-hr. fire rated party wall | a-1407 |

wall furring application

| | | | | | | | |
|---|---|---|---|---|-----|--|--------|
| — | RC-1 Furring Channels 24" o.c., 1/2" Insulating SHEETROCK screw attached, PERF-A-TAPE Joint Treatment | — | — | — | 101 | RC-1 channel reduces transfer of structural stresses to surface membrane | a-1407 |
|---|---|---|---|---|-----|--|--------|

description

Superior sound transmission loss and 1-hour fire-resistance are provided by these lightweight drywall assemblies. SHEETROCK Gypsum Wallboard face layers are attached with RC-1 SHEETROCK Resilient Channels to wood studs placed 16" o.c. These channels, roll formed from 25 ga. electro-galvanized steel, are designed to improve sound control at an economical cost. They are attached 24" o.c. at right angles to the partition framing with screws or nails.

SHEETROCK wallboard is fastened to the resilient channels with power-driven USG® Drywall Screws Type S spaced 16" o.c. These specially designed self-tapping steel screws with a rust-inhibitive coating provide superior holding power and optimum surface depression, thereby reducing fastener failure. Work is completed with the PERF-A-TAPE* or DURABOND* Joint System and DUR-A-BEAD* Corner Reinforcement.

SHEETROCK for these assemblies is available in 1/2" or 5/8" thickness and in five types. SHEETROCK FIRECODE* wallboards generally obtain higher fire resistance ratings than regular SHEETROCK. With Insulating (foil back) SHEETROCK wallboard, the system is effective as a vapor barrier, offers significant insulating value and provides economical, crack-resistant furring for exterior walls.

One of the best values in wood stud party walls consists of single-layer 5/8" SHEETROCK FIRECODE Gypsum Wallboard, resiliently attached to one side of wood studs and directly attached to the other side, plus 3" THERMAFIBER* Insulating Wool Blankets pressed tightly into the stud cavity. This lightweight partition has been widely used for its high sound value, STC 52, at costs which are little more than conventional partition systems. It also offers 1-hour rated fire resistance; has been repeatedly chosen for use between units in garden apartments and other multi-family buildings.

For greater strength and fire resistance, double-layer wallboard construction for partitions may be used with or without RC-1 channels (see table, above, and separate USG Systems

Folder on SHEETROCK/Wood Framing 2-layer construction. For ceiling application, see separate USG Systems Folder).

function and utility

Fire Resistance—The 1-hour fire-resistance ratings offered by these assemblies meet the fire resistance requirements established by ASTM E-119.


Sound Control—The resilient application of SHEETROCK wallboard with the RC-1 Resilient Channel offers a significant improvement in sound transmission loss over the direct application of wallboard.

Versatility—These assemblies are suitable for use in remodeling or in all types of new construction using wood framing.

Economy—Only three basic components are required: the resilient channel, drywall screws, and gypsum wallboard. They erect quickly to provide economical construction.

limitations

- 1" USG Drywall Screws Type S must be used for attachment of single layer wallboard to RC-1 Resilient Channels.
- Not recommended for use where normally exposed to excessive moisture or continued wetting.




resilient channel
one side with wool

resilient channel
both sides

sound transmission loss

| test no. | method | decibel frequency in cps | | | | | | | | | | | | STC |
|---------------|--------|--------------------------|------|------|------|-----|-----|------|------|------|------|------|----|-----|
| | | 125 | 175 | 250 | 350 | 500 | 700 | 1000 | 1400 | 2000 | 2800 | 4000 | | |
| USG-33-FT-G&H | Lab | 32 | 36 | 42 | 46 | 52 | 54 | 58 | 55 | 53 | 53 | 54 | 52 | |
| TL-60-52 | Lab | 29.5 | 32.5 | 39.5 | 43.5 | 46 | 48 | 50 | 51 | 49 | 44 | 49 | 45 | |

components



see "gypsum wallboard and joint treatment" product catalogs for full description on accessories & sizes















1-1/4" USG drywall screw—type W—bugle head



1" USG drywall screw—type S—bugle head




1-5/8" USG drywall screw—type S—bugle head





details/partitions

ceiling attachment

scale: 3" = 1'-0"



floor attachment



specifications

notes to architect

1. Drywall partitions will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements except the floor, by control joints or other means where (a) A partition abuts any structural element or dissimilar wall or ceiling assembly; (b) The construction changes within the plane of the partition.

In long partition runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling are recommended as control joints. For doors less than ceiling height, control joints extending from both corners of the frame to the ceiling may be used.

2. Holes cut in a thin wallboard membrane such as door frames, borrowed lights, etc., cause a concentration of stresses in the wallboard. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

3. Ceramic Tile—SHEETROCK W/R Gypsum Wallboard is recommended as a base for the adhesive application of ceramic, metal and plastic tile (see USG Gypsum Wallboard Product Folder).

4. Where this partition is used as a sound barrier, the use of non-hardening caulking material to seal cut-outs, such as at electrical fixtures and to seal all intersections with the adjoining structure, is recommended. Eliminate cutting holes back to back

and adjacent to each other. Door and borrowed light openings are not recommended when this partition is used as a party wall.

5. THERMAFIBER Insulation Blankets added to the stud cavity, pressed tightly in place, stapled to the back of one partition face, will increase the sound transmission loss of the construction.

6. For wood framing requirements, heating and ventilating recommendations, see USG Gypsum Wallboard Product Folder.

7. With fire rated construction, all vertical butt joints should be back blocked. Back blocking end joints is recommended to minimize joint ridging or deformation at the panel joints that may occur in gypsum board construction under adverse job or weather conditions. Where back blocking is used, float the end joints between studs and back block between resilient channels with RC-1 channels or minimum 8" wide strip of 3/8" gypsum board the full length of the joint adhesively applied over abutting ends. See separate USG system folder on SHEETROCK 1-layer & Wood Framing for details.

8. Fixture Attachment—Lightweight fixtures and trim should be installed using plastic plugs or other expandable anchors for screw attachment. Medium and heavy weight fixtures are not recommended on resilient surfaces but if required they should be supported from the primary framing.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 70° F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Gypsum Wallboard Folder for information on Wallboard System Components.

Joint Treatment Folder for Joint Treatment Specifications.

Paints Product Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. Gypsum Board—48" wide—(1/2") (5/8") thick Tapered Edge SHEETROCK (Regular) or (Insulating—foil back); (1/2") (5/8") thick SHEETROCK FIRECODE; 1/2" thick FIRECODE "C"; (1/2") (5/8") thick SHEETROCK W/R Wallboard—lengths as required.
- b. Joint Treatment—PERF-A-TAPE or DURABOND Joint System.
- c. Adhesive—(for Back-Blocking System)—PERF-A-TAPE Joint Compound (embedding type).
- d. Fasteners—Screws (specify from Pg. 2).
- e. USG Metal Trim (specify type from Pg. 2).
- f. Resilient Channels—RC-1 SHEETROCK Resilient Channel.
- g. USG Corner Bead—DUR-A-BEAD, PERF-A-BEAD,* ECONO* Corner Reinforcement (specify type from Pg. 2).
- h. Control Joints—USG Control Joint No. 093.

resilient channel erection

RC-1 SHEETROCK Resilient Channels shall be positioned at right angles to the wood framing, spaced 24" o.c. and attached to the supports with 1 1/4" USG Drywall Screws Type W driven through the punch holes provided in the attachment flange. On walls, resilient channels shall be positioned with the wallboard attachment flange up and shall be located at the floor, 24" up from the floor line, a maximum of 6" down from the ceiling line, and extended into all corners and connected to the corner framing. Channels shall not be cantilevered more than 6". When required, the resilient channel shall be spliced directly over the support by nesting the channel and attaching both flanges to the support.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: SHEETROCK (gypsum wallboard, metal channel); FIRECODE (gypsum wallboard); USG (metal products); THERMAFIBER (insulating wool); PERF-A-TAPE, DURABOND (joint treatment); DUR-A-BEAD, PERF-A-BEAD, PERF-A-TRIM, ECONO (corner reinforcement).

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

panel erection

Gypsum board of maximum practical length shall be applied with the long dimension parallel to the resilient channel and fastened with 1" USG Drywall Screws Type S spaced 12" o.c. along the channels. The horizontal abutting edges shall be centered over the screw flange of the channel.

For two-layer application of gypsum board, base layer shall be attached to the resilient channels with 1" USG Drywall Screws Type S spaced 16" o.c. Face layer shall be erected with the long dimension at right angles to the long edges of the base layer and fastened with 1 3/8" USG Drywall Screws Type S spaced 16" o.c.

wall furring application

RC-1 SHEETROCK Resilient Channels shall be positioned horizontally and attached with 2" cut nails in mortar joints of brick, clay tile or concrete block or in the field of lightweight aggregate block; 3/8" concrete stub nails or power-driven fasteners in monolithic concrete. Fasteners shall be spaced 24" o.c. Position channels within 4" of floor and ceiling line and not more than 24" o.c.

1/2" Insulating SHEETROCK Wallboard of maximum practical length shall be applied with the long dimension parallel to the resilient channels with 1" USG Drywall Screws Type S spaced 12" o.c. The horizontal abutting edges shall be centered over the screw flange of the channel. Where there is a possibility of water penetration through the walls, an asphalt felt protection strip shall be installed between the resilient channels and the wall.

wallboard accessories

a. (PERF-A-TAPE) (DURABOND) Joint System shall be used on all face board joints and internal angles formed by the intersections of walls and ceilings (specify from USG Joint Treatment Product Folder).

b. Metal Corner Bead No. () shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.

c. Metal Trim No. () shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.

d. Fasteners shall be as shown on drawings or as herein specified. Fasteners shall be driven at least 3/8" from ends or edges of wallboard to provide uniform dimple not over 1/32" deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

e. Control Joints shall be provided in the face layer as indicated and where detailed. Staple in place.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
 USG
 Construction
 Selection
 for
 Sales
 Offices

STRUCTICORE* & Wood Framing

PRE-ASSEMBLED GYPSUM PANELS

1417

AIA File No. 20-B-21



description

The STRUCTICORE Panel Partition System is a low-cost and structurally sturdy assembly for divider walls in residential construction. Newly developed by U.S.G. research, it clearly has proven in extensive field use to be a revolutionary improvement in the panelization of components. The system is exclusive with United States Gypsum.

Suited for use with wood truss or wood joist roof construction, this thin, lightweight non-load bearing partition is quickly erected without conventional wood stud framing. It is erected after subfloors, load bearing walls, plumbing and other conventionally framed partitions are installed—but before the wallboard is applied to ceilings and exterior walls.

STRUCTICORE Panels are 2½" thick, 4' wide and consist of two ⅜" thick (nom.) tapered edge gypsum wallboard face panels with integrally formed interior gypsum ribs spaced 6½" o.c. The panels, routed at the bottom, are erected vertically over a 2x2 wood floor runner. At the ceiling 2x2 wood blocks spaced 24" o.c. are inserted in the panel cavity and nailed to the overhead framing. This cavity also provides ready access for electrical installation or space for blocking to support cabinets and other fixtures. Vertical panel joints and intersections are reinforced with 2x2 wood splines and concealed with USG® Ready-Mixed Joint Compound—All Purpose and PERF-A-TAPE® Reinforcing.

function and utility

Simplified Erection—Factory-fabricated panels are delivered to the job ready for installation. Erection is fast, requiring simple tools, established techniques and few components.

High Strength—Beam-shaped internal ribs add rigidity to STRUCTICORE panels. This structurally sturdy lightweight construction meets FHA load and impact requirements for non-load bearing partitions.

Lightweight—Finished partition weighs only 4 psf.

Fire Resistant—Incombustible STRUCTICORE Gypsum Panels provide fire protection for wood runners and splines.

Easily Decorated—Construction eliminates fasteners and end joints in field of panels. No nails to spot or "pop." The strong, highly calendered face paper on STRUCTICORE Panels is ideal for any type of decoration with paint, texture or wallpaper.

Economical—The low material cost, fast erection, light weight and space-saving features of STRUCTICORE Panels combine to make this system one of the most economical residential partition constructions.

limitations

1. A non-load bearing partition.
2. Limiting height is 12'.
3. Partition should not be used where exposed to abnormal moisture or excessively high humidity.

specifications

notes to architect

1. **Wood Framing Requirements**—Wood framing should meet the minimum requirements of FHA and local building codes.
2. **Door Frames**—Wood door frames or three-piece knock down steel door frames installed according to manufacturer's directions are recommended for use with STRUCTICORE partitions. One-piece frames should not be used.

3. Electrical Fixtures—The depth of electrical boxes should not exceed 2". Boxes should be gangable, with ears, and should be attached to panel faces with sheet metal drywall box supports or integral clamps on receptacle boxes.

4. Fixture Attachment—Lightweight fixtures and trim should be installed using plastic plugs or other expandable anchors for screw attachment. Medium and heavyweight fixtures should be supported from wood blocking inserted in the panel cavity.

5. Heating and Air Conditioning—Distribution may best be accomplished with perimeter floor or ceiling diffusers or with ducts extending through the STRUCTICORE Panels from a plenum above a dropped ceiling in a hall area. Return may be with centrally located ceiling or base board grilles.

6. Plumbing—The STRUCTICORE Partition System is not recommended as a plumbing wall; however, a single pipe such as a gas pipe can be accommodated by placing a panel joint at the pipe location.


The most expedient way to obtain additional information or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 70° F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.




The installation and application of all materials shall be in
(continued on page 3)





details

scale: 3" = 1'-0"




ceiling attachments



floor attachment & bases





doors



details/specifications

intersecting walls



specifications (continued from page 1)

accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Gypsum Wallboard Folder for information on Wallboard System Components.

Joint Treatment Folder for Joint Treatment Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

a. Gypsum Panels—2 1/2" thick STRUCTICORE Partition Panels—48" wide x 8' long.

b. Joint Treatment—USG Ready-Mixed Joint Compound—All Purpose and PERF-A-TAPE Reinforcing.

c. DUR-A-BEAD® Corner Bead—No. (101) (102) (103).

d. Wood—[2x2 (1 5/8"x1 3/4"—ripped 2x4's)] [2x3 (1 5/8"x2 5/8")] wood stock of suitable grade, straight, true and free of knots (obtain locally.)

e. Screws—1 1/4" USG Brand Screw—Type W—Bugle Head.

f. Nails—(obtain locally).

—(16d) (12d) (10d) (8d) Common Nails.

—4d Cement Coated Cooler Nails.

partition erection

Partition erection shall begin at exterior and framed walls and run to door openings and partition terminals. At conventionally framed walls floor-to-ceiling height 2x2 wood starter strips shall be placed prior to floor runner attachment. Starter strips at perimeter walls shall be nailed to top and bottom plates with 12d nails and to flat 2x4 backing extending between plates with 12d nails 24" o.c.

(2x2) (2x3) floor runners shall be securely attached to the floor 24" o.c., maximum, with the following fasteners: **1. For wood floor**—Use 10d common nail for 2x2 runner; 16d common nail for 2x3 runner. **2. For concrete floor**—Use 2 1/2" long case hardened concrete nail for 2x2 runner; 3 1/2" long nail for 2x3 runner.

Runners shall be cut at the rough door opening dimension. At partition terminals, runners shall be cut 3/8" short of

finished terminal dimension. At corners and partition intersections, intersecting runners shall be spaced about $\frac{3}{4}$ " from previously installed runner.

2x4 ceiling ladder blocking shall be installed between supports and flush with bottom of framing over all door jambs, partition terminals, panel intersections and over all splines in partitions running parallel to overhead framing.

STRUCTICORE Panels shall be erected vertically with the routed end over floor runner and positioned within $\frac{1}{2}$ " of the ceiling framing. Panels shall be supported at both vertical edges by 2x2 wood splines, starter strips, corner inserts or jamb strips inserted in the panel recess. Panels shall overlap runners and all 2x2 wood components at least $\frac{3}{4}$ " to provide for proper attachment. Panels shall be attached to all vertical 2x2 wood components with $1\frac{1}{4}$ " USG Brand Screws—Type W spaced 16" o.c.; to all runners with $1\frac{1}{4}$ " screws spaced 12" o.c. 4d cement coated cooler nails spaced 12" o.c. at vertical panel joints and 8" o.c. at floor intersection may be used in place of screws. If panels are fastened by nailing, all 2x2 wood components shall be toenailed to runners with one 10d nail.

At all panel joints, the 2x2 wood spline shall be full length, extending from top of the floor runner to bottom of ceiling framing. Where partitions are parallel to framing, the splines shall be pinned at the top with a 12d nail driven through the ladder blocking into the spline. Where partitions run perpendicular to framing, a 2x2x12" long wood block shall be inserted in the panel cavity at each panel-framing intersection and fastened to the framing only with one 12d nail. Panel shall not be face-nailed to the block.

Corner intersections shall have a full length 2x2 corner insert placed vertically in one panel cavity; one face of abutting panel shall be cut back $2\frac{1}{2}$ "; and both panels shall be fastened to vertical corner insert.

At partition intersections, 2x2x12" wood backing shall be inserted into the cavity flush with the top of the continuous partition. A full length 2x2 wood starter strip to receive the abutting partition shall be toenailed to the floor runner with a 10d nail, and secured at the top to the wood backing with a 16d nail. Where a door opening occurs within 24" of intersection, 2x2 wood backing shall be full length and starter strip shall be secured, the full length with 16d nails spaced 24" o.c. Where the abutting partition terminates at a continuous partition, as in closet dividers, pre-insert and fasten a full length jamb strip to panel. Intersection shall be secured within 2" of top of panel with a 16d nail driven through opposite panel face and backing into jamb strip.

Partition terminals shall have full height 2x2 wood jamb strips inserted in the partition cavity, toenailed to floor runner with a 10d nail and secured to overhead blocking with a 12d nail. Exposed edge of STRUCTICORE Panel shall be faced with $\frac{3}{8}$ " SHEETROCK Gypsum Wallboard attached to jamb strip with $1\frac{1}{4}$ " Type W screws spaced 16" o.c.

***TRADEMARKS:** The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: STRUCTICORE (gypsum panels), SHEETROCK (gypsum wallboard, adhesive, sealant); USG (compound, screws); PERF-A-TAPE (joint reinforcement); DUR-A-BEAD (corner reinforcement).

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

Suitable fastener anchorage shall be provided as required for the attachment of shelves and cabinets. All exterior corners, interior angles and faceboard joints shall be reinforced and treated with joint compound applied according to manufacturer's directions. Work done by this contractor shall be coordinated properly with that done by other trades.

door frames

Door frames shall be rough framed with 2x2 wood components. A 2x2 wood header block of appropriate length for attachment of header panel shall be pre-attached to each jamb strip with two 12d nails. Full height vertical jamb strips shall be securely attached to overhead blocking with one 12d nail and to floor runner with one 10d nail. When panels are screw-applied, toenails to floor runner may be omitted.

Header panels shall be cut from a section of STRUCTICORE Panel so that ribs may be positioned horizontally. The ribs at each vertical edge shall be routed to a $2\frac{1}{2}$ " depth, minimum. Header panel shall be slid over header blocks and fastened each side to header blocks. A 2x2 wood lintel block inserted in header panel recess shall be toenailed to jamb and header blocks with two 8d nails each side of frame.

Header panel shall be attached to header and lintel blocks with $1\frac{1}{4}$ " Type W screws spaced 12" o.c. or 4d cement coated cooler nails 8" o.c.

Where rough jambs are located in panel field, an additional full height 2x2 wood backer shall be inserted in the panel cavities and the jamb strip secured to this backing with 16d nails spaced 24" o.c.

bath and shower areas

Panels abutting bathtubs or enclosing shower stalls shall have full height 2x2 wood backing inserted in panel cavity and spaced 24" o.c. Shower pans or tubs must have an upstanding lip or flange a minimum of 1" higher than the water dam or threshold of the container.

SHEETROCK W/R Wallboard shall be applied to the STRUCTICORE Panels as a base for ceramic, metal, or plastic tile on all areas where tile is to be used as a finished surface.

Wallboard shall be applied horizontally with the factory (paper bound) edge abutting the top edge of a temporary wood strip, which shall allow a minimum $\frac{1}{4}$ " space between the lip of the tub or subpan and the gypsum wallboard. SHEETROCK Brand DWA-14 Adhesive shall be applied to the STRUCTICORE Panels in $\frac{1}{4}$ " vertical beads 6" o.c. Wallboard shall be held in place with $1\frac{1}{4}$ " Type W screws driven into panel splines and intermediate backing 12" o.c. or nails driven 8" o.c. All cut edges, utility holes and joints, including those at all angle intersections, and all fastener heads shall be treated with SHEETROCK Brand W/R Sealant. In areas to be tiled, no joints or angles shall be taped with conventional joint systems. Nonsetting caulking compound shall be applied between wall surfacing material and tub rim or shower flange.

a-1417



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Source
for
Sales
Offices



floor—ceilings

b

Resilient Drywall/Wood Framing

1457

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|--|------------|-----------|---------------------|----------------------------------|------------------|
| | | | 11-f | 16-f | | | |
| 1½ hrs. | Resil 2 layers ½" SHEETROCK FIRECODE "C" gypsum wallbd ceiling—1" nom wd sub & fin flr—2x10 wd joist 16" o.c.—RC-1 chan spaced 24" o.c. screw att over base layer wallbd—face layer screw att to chan 12" o.c.—joints fin clg wt 5 | UL Des 22-1½ hr (f) | 49 est | | clg matls 46 | | b-1457 |
| 1 hr. | Resil ¾" SHEETROCK FIRECODE gypsum wallbd ceiling—1" nom sub & fin flr—2x10 wd joist 16" o.c.—RC-1 chan spaced 24" o.c.—wallbd att with 1" & 1½" Type S screws—joints fin clg wt 3 | UL Des 25-1 hr (f) NBS-717 (s) | 45 | | clg matls 36 | Sound test based on 2x8 16" o.c. | b-1457 |
| 1 hr. | Resil ½" SHEETROCK FIRECODE "C" gypsum wallbd ceiling—1¼" nom wd sub & fin flr—2x10 wd joist 16" o.c.—RC-1 chan spaced 24" o.c.—wallbd att with 1" Type S screws—joints fin clg wt 3 | UL Des 41-1 hr (f) | N/A | | clg matls 33 | | b-1457 |
| 1 hr. est | Resil SHEETROCK gypsum wallbd ceiling—1¼" nom wd sub & fin flr—2x10 wd joist 16" o.c.—RC-1 chan screw att to joist—wallbd att with 1" Type S screws—joints fin clg wt 3 | CK-6512-6 (s) (½" FIRECODE "C") CK-6412-10 (s) (¾" reg SHEETROCK) | 47 | (INR) -12 | clg matls 33 | | b-1457 |
| 1 hr. est | Resil SHEETROCK gypsum wallbd ceiling—1¼" nom wd sub & fin flr—44-oz carpet & 40-oz pad atop flr—2x10 wd joist 16" o.c.—RC-1 chan screw att to joists—wallbd att with 1" Type S screws—joints fin clg wt 3 | CK-6512-7 (s) (½" FIRECODE "C") CK-6412-9 (s) (¾" reg SHEETROCK) | 46 | (INR) +16 | clg matls 33 | | b-1457 |
| 1 hr. est | Resil SHEETROCK gypsum wallbd ceiling—1¼" nom wd sub & fin flr—2x10 wd joist 16" o.c.—3" THERMAFIBER ins wool blkts betw joists—RC-1 chan screw att to joists—wallbd att with 1" Type S screws—joints fin clg wt 3 | CK-6512-9 (s) (½" FIRECODE "C") CK-6412-3 (s) (¾" reg SHEETROCK) | 50 | (INR) -5 | clg matls 45 | | b-1457 |
| 1 hr. est | Resil SHEETROCK gypsum wallbd ceiling—1¼" nom wd sub & fin flr—44-oz carpet & 40-oz pad atop flr—2x10 wd joist 16" o.c.—3" THERMAFIBER ins wool blkts betw joists—RC-1 chan screw att to joists—wallbd att with 1" Type S screws—joints fin clg wt 3 | CK-6512-8 (s) (½" FIRECODE "C") CK-6412-4 (s) (¾" reg SHEETROCK) | 50 | (INR) +20 | clg matls 45 | | b-1457 |
| 1 hr. est | USG Sound Code flr/clg assembly—Resil ½" SHEETROCK gypsum wallbd screw att to RC-1 chan spaced 24" o.c.—joints fin—2x10 wd joist 16" o.c.—3" THERMAFIBER ins wool blkts betw joists—1 layer ea of ½" plywd—½" USG wd fiber sound dead bd—½" FIRECODE gypsum sheathg—¾" A.C. plywd—resil flr tile clg wt 5 | CK-6512-22 (s) | 51 | (INR) +2 | clg matls 45 | | b-1457 |

For directly attached drywall ceilings, see pertinent Partition System Folders or Construction Selector.

description

In these assemblies SHEETROCK® Gypsum Wallboard face layers are attached to either wood ceiling joists or wood trussed rafters using the RC-1 SHEETROCK Resilient Channel screw attached 24" o.c. to the framing. These channels, roll formed from 25 ga. electro-galvanized steel, are ingeniously designed to improve sound control at an economical cost. Specially designed power-driven, self-tapping USG® Drywall Screws Type S are used to attach the gypsum board to the channels. The constructions are completed with the PERF-A-TAPE® or DURABOND® joint system.

SHEETROCK for these assemblies is available in ½" and ¾" thickness and in five types. SHEETROCK FIRECODE® wallboards generally obtain higher fire-resistance ratings than regular SHEETROCK. Insulating (foil back) SHEETROCK Wallboard may be used as an effective vapor barrier, with significant insulating value.

Floor and ceiling constructions using 2x10 wood joists spaced up to 16" o.c. and resiliently attached wallboard provide excellent fire and sound resistance (see table above) and make these assemblies particularly suited for motels and multi-story apartment units.

With a double layer assembly of ½" SHEETROCK FIRECODE "C" Wallboard separated by RC-1 Resilient Channels, a 1½-hour fire-resistance rating is provided. With a single layer of either ½" SHEETROCK FIRECODE "C" or ¾" SHEETROCK FIRECODE panels, a 1-hour rating has been obtained. Along with RC-1 channels, the addition of 3" THERMAFIBER® Insulating Wool Blankets stapled between the joists greatly improves

sound attenuation values. With 44 oz. carpet and 40 oz. pad added atop the floor, impact noise resistance (INR) is appreciably improved. The new USG Sound Code Floor/Ceiling System provides impact noise resistance suitable for kitchen and bath areas where carpets are not generally used.


function and utility

Fire Resistance—Up to 1½-hour fire rating available.


Sound Control—Up to 51 STC and +20 INR available.

Versatility—Suitable for remodeling or all types of new wood frame construction.

(continued on page 3)





resilient channel with wool






sound code floor system

components

scale: 3" = 1'-0"



RC-1
SHEETROCK
resilient
channel



1 1/4" USG drywall screw—
type W—bugle head



1" USG drywall screw—
type S—bugle head

see "gypsum wallboard and joint treatment" product
catalogs for full description on accessories & sizes




1 1/8" USG drywall screw—type S—bugle head




1 1/8" 6d gypsum wallboard nail cement coated

resilient ceiling & floor assemblies




typical ceiling application



test CK-6512-7

test CK-6512-6—same but without carpet & pad




test CK-6512-8


test CK-6512-9—same but without carpet & pad

details

sound code floor system (Details from DW-34)



ceiling cross section


vertical section
thru partition

function and utility (continued from page 1)


Economy—Utilizes low-cost materials. A minimum number of components and simplified installation result in fast erection.

limitations


1. 1" USG Drywall Screws Type S must be used for attachment of single layer wallboard to RC-1 Resilient Channels.
2. RC-1 Resilient Channels must be attached to the bottom face of wood floor joists only with 1 1/4" USG Drywall Screws Type W. Nails must not be used.
3. Resilient ceilings should not be installed beneath highly flexible floor joists. Install only to framing meeting "Wood Framing Requirements" shown in USG Gypsum Wallboard Product Folder.
4. Wood Fiber Sound Deadening Board is not recommended for use in bathrooms.

specifications—notes to architect

1. Drywall ceilings will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements by control joints or other means where: (a) a ceiling abuts any structural element or dissimilar wall or ceiling assembly, (b) the construction changes within the plane of the ceiling.



Note: door jamb shall extend to 1/2" plywood sub-floor for nailing trim on carpet side of room

vertical section—transition from carpet
& pad area to sound code floor system

vertical section
thru door opening

Expansive ceiling areas should have control joints spaced not to exceed 50' in either direction. The continuity of wallboard and supports should be broken over control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

2. Holes cut in gypsum board ceilings such as vents, grilles, access panels, light troffers, etc., cause a concentration of stresses in the gypsum board. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy and design, a control joint is not otherwise specified.

3. Where drywall ceilings occur under roof construction, the plenum should be vented according to recommended engineering practice.

4. To retain maximum sound isolation, the integrity of the ceiling should not be voided by openings such as vents, light troffers, etc., so as to create sound leaks. The use of caulking to seal all cutouts and intersections with the adjoining structure is recommended. THERMAFIBER Insulation Blankets stapled between joists will increase the sound transmission loss of the construction.

5. Ridging or deformation at the panel joints may occur in gypsum board construction under adverse job or weather con-



ditions. Back blocking end joints will minimize joint ridging and is recommended. Where back blocking is used, float the end joints between resilient channels and back block with an 8" wide strip of gypsum board the full length of the joint adhesively applied over abutting ends, or screw-attach each floated end to a 5' length of resilient channel.

6. For wood framing requirements, heating and ventilating recommendations, see USG Gypsum Wallboard Product Folder.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 70° F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period. All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Gypsum Wallboard Folder for information on Wallboard System Components.

Joint Treatment Folder for Joint Treatment Specifications.

Paints Product Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. Gypsum Board—48" wide—(1/2") (3/8") thick Tapered Edge SHEETROCK (Regular) or (Insulating—foil back); (1/2") (3/8") thick SHEETROCK FIRECODE; (1/2") (3/8") thick FIRECODE "C"—lengths as required.
- b. FIRECODE Gypsum Sheathing, 1/2" thick, 24" wide, "V" T & G edge, 8' long or 48" wide, square edge, (8') (9') long.
- c. USG Wood Fiber Sound Deadening Board, 1/2" thick, 48" wide—lengths as required.
- d. Plywood—1/2" x 48" x 96" (for sub-floor), 3/8" x 48" x 8' Grade AC (for finish floor), obtain locally.
- e. Joint Treatment—PERF-A-TAPE or DURABOND Joint System.
- f. Adhesive—(for Back-Blocking System)—PERF-A-TAPE Joint Compound (embedding type); (for Sound Code Floor System)—3-M Mastic EC-511.
- g. Fasteners—Screws (specify from pg. 2).
- h. USG Trim (specify type from pg. 2).
- i. Resilient Channels—RC-1 SHEETROCK Resilient Channel.
- j. USG Control Joint No. 093.
- k. THERMAFIBER Insulating Wool Blankets (thickness).

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: SHEETROCK (gypsum wallboard, metal channel); FIRECODE (gypsum wallboard, sheathing); USG (metal products, wood fiber board); THERMAFIBER (insulating wool); PERF-A-TAPE, DURABOND (joint treatment).

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

resilient channel erection

RC-1 SHEETROCK Resilient Channels shall be positioned at right angles to the wood framing, spaced 24" o.c. and attached to the supports with USG Drywall Screws (1 1/4" Type W) (1 7/8" Type S) driven through the punch holes provided in the attachment flange. Channels shall not be cantilevered more than 6". When required, the resilient channel shall be spliced directly over the support by nesting the channel and attaching both flanges to the support.

panel erection

a. **base layer**—SHEETROCK FIRECODE "C" Wallboard shall be applied with the long edge across the joists, with end joints staggered, and fastened with 6d cement coated nails. Nails shall be spaced 1", 6", and 21" from each edge in field of board with additional nails 15" from edge at end joints.

b. **face layer**—SHEETROCK Wallboard of maximum practical length shall be applied with long dimension at right angles to resilient channel and fastened with 1" USG Drywall Screws Type S spaced 12" o.c. in field of board and along abutting ends. End joints shall be staggered and neatly and accurately fitted. End joints shall occur over resilient channel web surface or occur midway between channels with joint floated and back blocked. Gypsum board shall be properly supported around all cutouts and openings.

sound code floor erection

1/2" plywood sub-floor shall be nailed in place over joists using 8d cement coated nails. After sub-floor is installed, 1/2" wood fiber sound deadening board perimeter relief strip shall be tack-nailed to all bottom plates. Over the sub-floor, full sheets of 1/2" sound deadening board shall be laid dry with joints offset from sub-floor joints. In bathrooms FIRECODE Gypsum Sheathing shall be substituted for sound deadening board. Next a layer of FIRECODE Sheathing shall be laid dry with joints offset at least 10" from those in preceding layer. Top layer of 3/8" A.C. plywood shall be applied to sheathing layer using 3-M Adhesive EC-511 spread over sheathing surface with a large-tooth notched trowel. All joints shall be matched, tightly fitted and offset from sheathing joints.

wallboard accessories

a. **PERF-A-TAPE or DURABOND Joint System** shall be used on all gypsum board joints and internal angles formed by the intersections of walls and ceilings.

b. **Metal Trim No. ()** shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.

c. **Fasteners** shall be as shown on drawings or as herein specified. Fasteners shall be driven not less than 3/8" from ends or edges of gypsum board to provide uniform dimple not over 1/32" deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

d. **Control Joints** shall be provided in the face layer as indicated and where detailed. Staple in place.

b-1457



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

• See
USG
Construction
Selector
for
Sales
Offices



BRACE-TITE® Lathing System

ceilings

b

ROCKLATH® Plaster Base & Plaster

1466

A.I.A. File No. 20-B-2

| fire rating | description | test no. | sound rating | | relative cost index | comments | folder reference |
|-------------|---|------------------|--------------|-----------|---------------------|--|------------------|
| | | | stc | 9-f avg | | | |
| 4 hrs. | ROCKLATH PI Base & Plaster— $\frac{3}{4}$ " cr chan 12" o.c. & BRACE-TITE Clips— $\frac{3}{8}$ " perf gypsum lath—1" 100:2-100:3 gypsum perlite plaster—1" 20-ga hex mesh—2" conc on riblath over bar joist clg wt 7 | GA-NBS-311 (f) | N/A | | clg matls 120 | | b-1466 |
| 3 hrs. | ROCKLATH PI Base & Plaster— $\frac{3}{4}$ " cr chan 12" o.c. & BRACE-TITE Clips— $\frac{3}{8}$ " perf gypsum lath—14-ga diag wire reinf— $\frac{3}{16}$ " 100:2 $\frac{1}{2}$ gypsum perlite plaster—2 $\frac{1}{2}$ " conc over cellular stl flr clg wt 5 | GA-NBS-337 (f) | N/A | | clg matls 115 | Good crack resistance with an opportunity to reinforce plaster at re-entry angle | b-1466 |
| 2 hrs. | ROCKLATH PI Base & Plaster— $\frac{3}{4}$ " cr chan 12" o.c. & BRACE-TITE Clips— $\frac{3}{8}$ " perf gypsum lath—14-ga diag wire reinf— $\frac{3}{16}$ " 100:2-100:3 gypsum sand plaster—2" conc over bar joist clg wt 7 | GA-NBS-345 (f) | N/A | | clg matls 106 | Good crack resistance with an opportunity to reinforce plaster at re-entry angle | b-1466 |
| 1 hr. | ROCKLATH PI Base & Plaster— $\frac{3}{4}$ " cr chan 16" o.c.— $\frac{3}{8}$ " perf gypsum lath— $\frac{3}{8}$ " STRUCTO-LITE plaster—2 $\frac{1}{2}$ " conc on riblath over bar joist clg wt 5 | NBS 261 (f) | | 45 db est | clg matls 104 | Attenuation test—good crack resistance, can reinforce plaster at re-entry angle | b-1466 |
| N/A | ROCKLATH PI Base & Plaster— $\frac{3}{4}$ " cr chan & BRACE-TITE Clips— $\frac{3}{8}$ " gypsum lath— $\frac{1}{2}$ " 100:2-100:2 $\frac{1}{2}$ gypsum sand plaster clg wt 6 | USG-6-FT-G&H (s) | | 47 db | clg matls 103 | Attenuation test—suspension & ceiling membrane only | b-1466 |

description

This ceiling assembly consists of ROCKLATH Plaster Base attached to conventional furred or suspended ceiling grillage with the BRACE-TITE Lathing System. In this system special wire clips are attached to the $\frac{3}{4}$ " furring channel and provide sag-resistant, spring-tension support across the full lath width.

ROCKLATH, a gypsum core faced on both sides with special paper, forms a rigid base for the economical application of gypsum plasters. For this assembly, ROCKLATH is $\frac{3}{8}$ " thick and depending upon ceiling design requirements is available in three types: Plain, for most ceiling installations; Insulating (foil back), where insulation and vapor barrier are required; Perforated, where fire ratings are needed. In Perforated ROCKLATH, $\frac{3}{4}$ " round holes are punched through the lath 4" o.c. in each direction, providing a mechanical key in addition to the natural plaster bond. Fire resistance ratings up to 4 hours can be obtained using this system (see table above).

function and utility

BRACE-TITE ceilings serve to conceal and protect structural and mechanical elements with a lightweight fireproof membrane of gypsum lath and plaster that is easily decorated and maintained. In addition the BRACE-TITE Lathing System for attaching ROCKLATH offers:

Crack Resistance—The BRACE-TITE clips while supporting the plaster base firmly against the channels, isolate the plaster membrane from minor movements of the grillage.

Fire Resistance—Incombustible components make possible established fire-resistance ratings of 1 to 4 hours.

Insulation and Vapor Barrier—Insulating (foil back) ROCKLATH provides an effective vapor barrier and increases the overall "U" factor of the roof-ceiling assembly.

Economy—With ROCKLATH Plaster Base the scratch coat of plaster and labor of application may be saved. The established fire resistance ratings can reduce annual insurance premiums.

limitations

1. A non-load bearing ceiling construction.
2. BRACE-TITE Field Clips are designed for use with standard $\frac{3}{4}$ " cold rolled channels having $\frac{1}{2}$ " legs (minimum).

3. The three-coat plastering method is required over Perforated ROCKLATH, and recommended over Plain and Insulating ROCKLATH when drying conditions are unfavorable.




4. In ceiling constructions certain precautions concerning construction, isolation and ventilation are necessary for good performance (see Specifications, page 3).

5. Maximum support spacing 16" o.c.




A.I.A. File No. 20-B-2

components | details




BRIDJOINT* B-1
field clip

see "plaster bases" product catalog for
full description on accessories & sizes




details


scale: 3" = 1'-0"




control joint parallel to 3/4" channels




control joint perpendicular to 3/4" channels



perimeter isolation



isolation from walls or columns



vertical section at light troffer

specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.
2. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and moisture content. It is recommended that lath and plaster surfaces be isolated from all structural elements by control joints or other means where:
 - a. a ceiling abuts any structural element, dissimilar wall or partition assembly, or other vertical penetration.
 - b. the ceiling construction changes within the plane of the ceiling.

Main runners and cross furring members should not be let into masonry walls or partitions, and clearance of at least 1" must be provided at each end of the channels.

Expansive ceiling areas should have control joints spaced not to exceed 60' in either direction and the area within separated

sections should not exceed 2,400 sq. ft. The continuity of grillage, lath and plaster should be broken over control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

3. Holes cut in a thin lath and plaster membrane such as vents, grilles, access panels, light troffers, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy and design, a control joint is not otherwise specified.

4. The spacing of hanger wires and channels are maximum and should not be exceeded. The grillage is designed to support the dead load of lath and plaster and is not designed to support concentrated loads of mechanical equipment or workmen, particularly after the plaster has been applied. Independently supported catwalks and equipment platforms should be provided.

5. Where a plaster surface is flush with metal, metal access panels, light troffers, etc., the plaster should be grooved between the two materials.



6. Where furred or suspended ceilings occur under roof construction, the plenum should be vented according to recommended engineering practice.

7. To retain maximum sound isolation, the integrity of the ceiling should not be voided by openings such as vents, light troffers, etc., so as to create sound leaks. Use sand aggregate only, do not use lightweight aggregates.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architect Service Department, 101 S. Wacker Dr., Chicago, Ill. 60606.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. ROCKLATH Plaster Base $\frac{3}{8}$ " (Plain) (Perforated) (Insulating) 16" x 48".
- b. BRACE-TITE Field Clip BT-1.
- c. BRACE-TITE Starter Clip BT-1.
- d. BRIDJOINT® B-1 Field Clip.
- e. USG® Selv-edge Cornerite (2" x 2") (3" x 3").
- f. USG Self-Furring Junior Diamond Mesh Metal Lath.
- g. USG Casing Bead (specify type from page 2).
- h. USG Control Joint.
- i. USG Cold Rolled Channels $\frac{3}{4}$ ", $1\frac{1}{4}$ " 2".
- j. 9 Gauge Hanger Wire.
- k. 16 Gauge Tie Wire.
- l. 14 Gauge Reinforcing Wire.
- m. 20 Gauge Galvanized 1" Hexagonal Wire Mesh (not available from U.S.G.).

grillage erection

9 gauge hangers shall be spaced not over 4'-0" in the direction of the $1\frac{1}{2}$ " main runner channels and not over 3'-0" in the direction at right angles to the main runners, and within 6" of the ends of main runner runs and of boundary walls, girders or similar interruptions of ceiling continuity. (For alternate hangers, main runner channels and cross furring channels see table in USG Plaster Bases Product Folder.)

Main runners shall be placed not over 3'-0" o.c., properly positioned, leveled, and hangers shall be saddle tied along runner.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ROCKLATH (plaster base); BRACE-TITE (lathing system); BRIDJOINT (clips); TRUSSTEEL (metal studs).

NOTE: Since methods and conditions of application and use are beyond our control, the United States Gypsum Company will not be responsible for failure of its products when not used according to our directions and specifications.

Main runners shall not be let into nor come in contact with abutting masonry walls. Runner channels shall be located within 6" of the walls to support the ends of the $\frac{3}{4}$ " cross furring channels.

Cross furring channels shall be spaced (12") (16") o.c. and securely saddle tied with two strands of 16-gauge tie wire to main runners and shall not be let into or come in contact with abutting masonry walls.

plaster base attachment

ROCKLATH Plaster Base shall be applied with the long dimension at right angles to the $\frac{3}{4}$ " channels and secured to the channels with BRACE-TITE Field Clips. ROCKLATH end joints shall fall between channels and be secured with B-1 Field Clips on each side. Set grounds to ($\frac{1}{2}$ ") ($\frac{5}{8}$ ") (1") minimum thickness over ROCKLATH, including $\frac{1}{16}$ " finish.

related inclusions

One-Hour Rating—Perforated ROCKLATH, $\frac{5}{8}$ " gypsum perlite plaster.

Two-Hour Rating—Lengths of 14-gauge wires shall be run diagonally across ceiling through each BRACE-TITE clip loop — $\frac{5}{8}$ " gypsum sanded plaster.

Three-Hour Rating—Same as two-hour rating except change furring channel spacing from 16" o.c. to 12" o.c. and use $\frac{1}{2}$ " gypsum perlite plaster.

Four-Hour Rating—Same as three-hour rating except add the following: "Staple 20-gauge hexagonal mesh to lath and wire tie mesh to furring channels at long edge of the lath, and use 1" gypsum perlite plaster."

lathing accessories


a. **Cornerite** (2" x 2") (3" x 3") shall be installed in all interior plaster angles. Staple at the edges.

b. **Casing Bead No. (0000)** shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed.

c. **Reinforcing**—Install a strip of self-furring diamond mesh lath over joints between dissimilar plaster bases. At all openings, reinforce the corners attaching a 12" x 24" piece of self-furring diamond mesh lath diagonally across the corners.

d. **Control Joint** shall be provided as detailed and where indicated. Staple in place.

b-1466



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



UNITED
STATES
GYPSUM

furred or suspended

ceilings

b

USG® Metal Lath and Plaster

1487

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|----------------------|--|--|------------|------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 4 hrs. (beam 4 hrs.) | Metal Lath & Plaster— $\frac{3}{4}$ " cr chan susp $7\frac{1}{2}$ " below deck 2" below beam—3.4# dm met lath & $\frac{5}{8}$ " 100:3 gypsum perlite plaster basecoat— $\frac{1}{2}$ " USG acoust plaster—conc over cellular stl flr | GA-NBS-338 (f) | N/A | | clg matls 140 | | b-1487 |
| 4 hrs. (beam 4 hrs.) | Metal Lath & Plaster— $\frac{3}{4}$ " chan 13" o.c. $3\frac{1}{2}$ " below beam —3.4# dm met lath & $\frac{5}{8}$ " STRUCTO-LITE (Type S) plaster—2" conc over fluted stl flr | UL Des 12-4 hr (f) | N/A | | clg matls 129 | | b-1487 |
| 3 hrs. (beam 4 hrs.) | Metal Lath & Plaster— $\frac{3}{4}$ " cr chan susp $15\frac{1}{2}$ " below deck & $3\frac{1}{2}$ " below beam—3.4# dm mesh metal lath— $\frac{5}{8}$ " STRUCTO-LITE (Type R) plaster—2" conc over cellular stl flr | UL Des 11-3 hr (f) | N/A | | clg matls 127 | | b-1487 |
| 3 hrs. | Metal Lath & Plaster— $\frac{3}{4}$ " cr chan furred or susp—3.4# dm met lath & $\frac{5}{8}$ " neat wood fiber gypsum plaster—2 $\frac{1}{2}$ " conc on riblath over bar joist | BMS-92 table 43 (f) | N/A | | clg matls 130 | Cost index based on furred construction | b-1487 |
| 2 hrs. | Metal Lath & Plaster—3.4# dm met lath & $\frac{5}{8}$ " 100:2-100:3 gypsum sand plaster—susp 3" min clearance below flr plates—2" conc deck on stl plate flr | BSM-92 table 44 (f) USG-10-FT-G&H (s) | 45 | | clg matls 126 | | b-1487 |
| 1½ hrs. | Metal Lath & Plaster— $\frac{3}{4}$ " cr chan furred or susp—3.4# dm met lath & $\frac{5}{8}$ " 100:2-100:3 gypsum sand plaster—2" conc on riblath over bar joist | BMS-92-table 43 (f) | N/A | | clg matls 119 | Cost index based on furred construction | b-1487 |
| 1½ hrs. | Metal Lath & Plaster—susp 3.4# dm met lath & 1" 100:2 gypsum sand plaster—rib type stl rf deck with 1½" wd fiber insul | NBS-58 (f) | N/A | | clg matls 129 | | b-1487 |
| 1½ hrs. | Metal Lath & Plaster—susp 3.4# dm met lath & $\frac{5}{8}$ " 100:2-100:3 gypsum sand plaster—rib type stl rf deck with 1" wd fiber insul | NBS-57 (f) | N/A | | clg matls 127 | | b-1487 |

beam applications

| | | | | | | | |
|--------|---|---------------------------------|--|--|----|--|--------|
| 4 hrs. | Metal Lath & Plaster Caged Beam Fireprfg—3.4# sf dm met lath enclosing beam—1½" 100:2 gypsum perlite plaster UL 40 U18.16 | UL Des 8-4 hr (Beam 4 hrs) (f) | | | 99 | | b-1487 |
| 3 hrs. | Metal Lath & Plaster Caged Beam Fireprfg—9 ga galv wire wrapped around beam 18" o.c. bent over bottom flange—3.4# sf dm met lath—1" mill formulated gypsum plaster UL 40 U18.3 (Type S) | UL Des 10-2 hr (Beam 3 hrs) (f) | | | 84 | | b-1487 |

description

These lightweight ceiling assemblies consist of USG Metal Lath and gypsum plaster attached to a conventional light channel grillage furred or suspended from construction above. Metal Lath, expanded from rust-resisting sheet steel, is readily shaped to complex contours or used for flat ceilings.

The systems provide an excellent fireproof membrane to hide pipes, ducts, and conduits. Fire resistance ratings up to 4 hours, suitable for protection of beams and girders, can be obtained (see table above).

function and utility

Furred and suspended ceilings serve to conceal and protect structural and mechanical elements with a lightweight fireproof membrane of metal lath and plaster that is easily decorated and maintained.

Fire Protection—Incombustible components make possible established fire-resistance ratings of 1 to 4 hours.

Economy—Lightweight installation; system's excellent fire resistance ratings can reduce insurance premiums.

Versatility—Ceilings with complex contours for acoustical treatment or unusual lighting effects are readily shaped with USG Diamond Mesh Lath.

limitations




1. Non-load bearing ceiling constructions.
2. In ceiling constructions certain precautions concerning construction, isolation and ventilation are necessary for good performance (see Specifications, page 3).







suspended metal lath

components/suspended details




scale: 3" = 1'-0"





USG casing beads
(expanded or short flange)



see "plaster bases" product catalog for full description on accessories & sizes




beam and girder fireproofing




furred details

scale 3' = 1'-0"



detail for concrete joists



detail for steel bar joists

spacing of supports for USG Metal Lath

| lath type | wt. per sq. yd. | max. support spacing |
|--------------|-----------------|----------------------|
| Diamond Mesh | 3.4 lbs. | 13½" |
| ⅜" Z Riblath | 3.4 lbs. | 19" |
| ⅝" Riblath | 3.4 lbs. | 24" |

maximum allowable furring spans

| furring type | furring spacing | | | |
|-----------------|-----------------|------|-----|------|
| | 24" | 19" | 16" | 12" |
| ⅝" pencil rod | — | 2' | 2' | 2'6" |
| ¾" c.r. channel | 3' | 3'6" | 4' | 4' |

maximum allowable runner spans

| cold rolled channel size | runner spacing | | | | |
|--------------------------|----------------|------|----|------|----|
| | 4' | 3'6" | 3' | 2'6" | 2' |
| 1½" | 3' | 3'6" | 4' | 4' | 5' |
| 2" | 4'6" | 5' | 5' | 6' | 7' |

maximum allowable ceiling area

| hanger type | max. area per hanger |
|-------------------|----------------------|
| 8 ga. galv. wire | 16 sq. ft. |
| 9 ga. galv. wire | 12.5 sq. ft. |
| 10 ga. galv. wire | 12 sq. ft. |

specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.

2. Lath and plaster surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and moisture content. It is recommended that lath and plaster surfaces be isolated from all structural elements by control joints or other means where:

- a ceiling abuts any structural element, dissimilar wall or partition assembly, or other vertical penetration.
- the ceiling construction changes within the plane of the ceiling.

Main runners and cross furring members should not be let into masonry walls or partitions, and clearance of at least 1" must be provided at each end of the channels.

Expansive ceiling areas should have control joints spaced not to exceed 50' in either direction and the area within separated sections should not exceed 2,500 sq. ft. The continuity of grillage, lath and plaster should be broken over control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

3. Holes cut in a thin lath and plaster membrane such as vents, grilles, access panels, light troffers, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

4. The spacing of hanger wires and channels are maximum and should not be exceeded. The grillage is designed to support the dead load of lath and plaster and is not designed to support concentrated loads of mechanical equipment or workmen, particularly after the plaster has been applied. Independently supported catwalks and equipment platforms should be provided.

5. Where a plaster surface is flush with metal, metal access panels, light troffers, etc., the plaster should be grooved between the two materials.

6. Where suspended ceilings occur under roof construction, the plenum should be vented according to recommended engineering practice.

7. To retain maximum sound isolation, the integrity of the ceiling should not be voided by openings such as vents, light troffers, etc., so as to create sound leaks. Use sand aggregate only, do not use lightweight aggregates.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. Metal Lath shall be 3.4 lb. (Diamond Mesh) (Z-Riblath) ($\frac{3}{8}$ " Riblath) 27" x 96".
- b. USG Cold Rolled Channels ($\frac{3}{4}$ "), ($1\frac{1}{2}$ "), (2").
- c. USG 1-A Expanded Flange Corner Bead.
- d. USG Casing Bead (specify type from page 2).
- e. USG Control Joint.
- f. (8), (9), (10) ga. Hanger Wire.
- g. (16), (18) ga. Tie Wire.

grillage erection

Select hanger, main runner, furring types and spacing from tables, page 3.

(8) (9) (10) ga. hangers shall be spaced not over (2') (2'6") (3') (3'6") (4') (5') (6') (7') in the direction of the main runner channels, not over (2') (2'6") (3') (3'6") (4') in the direction at right angles to the main runners, and within 6" of the ends of main runner runs and of boundary walls, girders or similar interruptions of ceiling continuity. Hangers shall be securely attached to reinforcing steel in concrete construction or shall be provided with a looped end embedded at least 2" within the concrete.

($1\frac{1}{2}$ ") (2") main runner channels shall be placed not over (2') (2'6") (3') (3'6") (4') o.c., properly positioned, leveled, and hangers shall be saddle tied along runners. Runner

channels shall be located within 6" of walls to support ends of cross furring channels.

Cross furring channels shall be erected at right angles to main runners or framing; spaced ($13\frac{1}{2}$ ") (16") (19") (24") o.c. and securely saddle tied with two strands of 16 ga. tie wire to main runners or steel joists. Hangers from concrete joists shall be securely saddle tied or wrapped around furring channels.

Main runners and furring members shall not be let into nor come into contact with abutting masonry walls. Channels shall be spliced by overlapping ends at least 8" and wire tying with two ties of double strand 16 ga. wire 1" from each end.

plaster base attachment

Metal lath shall be applied with the long dimension of the sheet across the supports. The ends of all lath shall be lapped not less than 1". If end laps are made between supports, they shall be adequately laced or tied with 18 gauge tie wire. The sides of diamond mesh lath shall be lapped not less than $\frac{1}{2}$ ". The sides of riblath shall be lapped by nesting outside ribs, and shall be wire-tied to every support, and between supports not to exceed 9" intervals. Wherever possible, ends of lath in adjacent courses shall be staggered. Metal lath shall be secured to all supports, with 18 gauge tie wire at intervals not exceeding 6". At all interior angles, metal lath shall be formed into the corners and carried out onto the abutting surface, and adequately secured.

steel beam fireproofing

Framework shall be formed, as shown on drawings, of $\frac{3}{4}$ " channels or pencil rods. $\frac{3}{4}$ " channel longitudinal furring brackets shall not be spaced more than 3'-0". Spacing for brackets formed of $\frac{1}{4}$ " pencil rod shall not exceed 19".

Without longitudinal furring bracket, spacing is limited to $13\frac{1}{2}$ " for 3.4 lb. diamond mesh lath and a minimum of one longitudinal channel is required to hold bracket alignment. Grounds shall be installed to insure required plaster thickness shown.

lathing accessories

a. **Metal Corner Bead No. 1-A** shall be provided on all exterior plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten securely with wire-ties, spaced not over 8" o.c.; stagger in two wings.

b. **Casing Bead No. ()** shall be installed where indicated. Ends shall be accurately cut and mitered and the casing bead shall provide full plaster grounds when securely installed. Attach with 18 gauge tie wire 6" o.c.

c. **Control Joint** shall be provided as detailed and where indicated. Attach with 18 gauge tie wire 6" o.c.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); TRUSSTEEL (metal studs); STRUCTO-LITE (plaster).

b-1487

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



UNITED
STATES
GYPSUM

furred or suspended

ceilings

b

Drywall/Metal Furring Channels

1497

A.I.A. File No. 20-B-21

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|----------------------|--|-----------------------|-----------------|------|---------------------|--------------|---|
| | | | 11-f | 16-f | | | |
| 3 hrs. (beam 3 hrs.) | 5/8" SHEETROCK FIRECODE "C" gypsum wallbd—USG met fur chan 24" o.c.—wallbd att with 1" Type S screws 12" o.c.—joints exp or fin—3" conc on riblath over bar joist clg wt 3 | UL Des 82-3 hr (f) | | | | clg matls 40 | b-1497 |
| 2 hrs. | 1/2" SHEETROCK FIRECODE "C" gypsum wallbd—furred or susp—USG met fur chan 24" o.c.—wallbd att with 1" Type S screws 12" o.c.—joints exp or fin—2 1/2" conc on riblath over bar joist clg wt 3 | UL Des 221-2 hr (f) | | | | clg matls 40 | b-1497 |
| 2 hrs. | 5/8" SHEETROCK FIRECODE gypsum wallbd—furred or susp—USG met fur chan 24" o.c.—wallbd att with 1" Type S screws 12" o.c.—joints exp or fin—2 1/2" conc deck on riblath over bar joist clg wt 3 | UL Des 82-2 hr (f) | 40 db est | | | clg matls 44 | Sound estimate based on joints finished b-1497 |
| N/A | 5/8" SHEETROCK FIRECODE gypsum wallbd—1 1/2" cr chan 4" o.c.—USG met fur chan 24" o.c.—wallbd screw att 12" o.c.—joints fin clg wt 3 | USG-5-FT-G&H (s) | 45 db (9-f avg) | | | clg matls 60 | "Up and over" attenuation test—suspension & clg. membrane only b-1497 |
| 2 hrs. | 5/8" SHEETROCK FIRECODE gypsum wallbd—furred or susp—USG met fur chan 12" o.c.—wallbd att with type S screws 8" o.c.—joints fin—2 1/2" conc deck on riblath over bar joist clg wt 3 | UL Des 63-2 hr (f) | 40 db est | | | clg matls 45 | b-1497 |
| 1 1/2 hrs. | 5/8" SHEETROCK FIRECODE gypsum wallbd—furred or susp—USG met fur chan 24" o.c.—wallbd screw att 12" o.c.—joints fin—2" conc on riblath over bar joist clg wt 3 | UL Des 4-1 1/2 hr (f) | 42 db est | | | clg matls 46 | Sound attenuation estimate made for floor & ceiling system b-1497 |
| 1 hr. | 5/8" BAXBORD FIRECODE gypsum wallbd—24 ga nailing chan—wallbd att with ann nails 6" o.c.—joints unfin—2" conc on riblath fur over bar joist clg wt 3 | UL Des 5-1 hr (f) | 35 db est | | | clg matls 45 | b-1497 |

description

This incombustible ceiling assembly consists of SHEETROCK® FIRECODE® Gypsum Wallboard screw attached to USG Metal Furring Channels. This specially designed channel, roll-formed from 25 ga. electro-galvanized steel, is 2 3/4" wide x 7/8" deep with 1/2" wing flanges. It is firmly clipped or wire tied to suspended main runner channels or wire tied to main support members. A specially designed self-tapping steel screw with a rust inhibitive coating, 1" USG Drywall Screw Type S, is used to attach the gypsum board to the furring channels. For long span requirements resulting from the location of large ducts or pipes in the ceiling space, the USG Metal Stud may be used as a ceiling furring member in this construction (see table, page 2). The assembly when completed with joints finished or exposed provides fire ratings up to 3 hours (see table above) for furred ceilings. An alternate 1-hour rated system employs nailing channels.

SHEETROCK for this assembly is available in three thicknesses and five types (see Specifications page 3). With Insulating (foil back) SHEETROCK Wallboard the system is effective as a vapor barrier and provides significant insulating value. Lower cost BAXBORD® Gypsum Backing Board provides a firm base for acoustical tile adhesively applied.

function and utility

Furred and suspended drywall ceilings serve to conceal and protect structural and mechanical elements with a lightweight fire-resistant ceiling of gypsum board that forms an ideal base for acoustical tile or is easily decorated and maintained. In addition the system also provides:

Fire Resistance—Incombustible components make possible established fire resistance ratings of 1 to 3 hours (see table above for constructions).


Versatility—Adaptable for use in virtually all types of new construction and modernization.

Insulation and Vapor Barrier—Insulating (foil back) SHEETROCK is an effective vapor barrier and increases the overall "U" factor of the roof-ceiling assembly (table, page 2).


Economy—Utilizes low cost materials. A minimum number of components and simplified installation procedures result in fast erection.

limitations


1. Not recommended for use where ceilings would normally be exposed to excessive moisture or continued wetting.
2. In ceiling constructions certain precautions concerning construction, isolation and ventilation are necessary for good performance (see Specifications, page 3).



USG metal furring channel




see "gypsum wallboard and joint treatment" product catalogs for full description on accessories & sizes



USG metal stud




USG metal furring channel clip



USG cold rolled channel




1" USG drywall screw type S—bugle head




tapered edge SHEETROCK gypsum wallboard



no. 200-C USG metal trim



USG metal trim



thermal resistance (R) value— insulating SHEETROCK wallboard (1)



| thickness | 3/8" | 1/2" | 5/8" |
|-------------------|------|------|------|
| summer conditions | 4.89 | 5.00 | 5.11 |
| winter conditions | 1.66 | 1.77 | 1.88 |

(1) Ceiling application, including air space of 3/4" or more behind wallboard.

component spacing






| type furring member | | ceiling systems—component spacing | | | | | | | hangers c. to c. |
|------------------------------|--|------------------------------------|-----|-----|--|-------|-------|-------|---------------------|
| | | furring member c. to c. spacing | | | main support member c. to c. spacing | | | | |
| | | for wallboard thickness of: | | | | | | | |
| USG Metal Furring Channel | | ¾" | ½" | ⅝" | ¾" | ½" | ⅝" | 4'-0" | |
| | | 16" | 24" | 24" | 5'-0" | 4'-0" | 4'-0" | | |
| USG Metal Stud | 1½" erected with both flanges up and against main support member | 16" | 24" | 24" | 7'-0" | 6'-0" | 6'-0" | 4'-0" | |
| | 2½" | 16" | 24" | 24" | — | 6'-0" | — | | |
| | 3⅝" | 16" | 24" | 24" | — | 8'-0" | — | | |
| | | | | | | | | | |

USG metal stud furring



details

USG metal furring channel



specifications

notes to architect

1. Gypsum board ceiling surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that gypsum board surfaces be isolated from all structural elements by control joints or other means where:

- a ceiling abuts any structural element, dissimilar wall or partition assembly, or other vertical penetration.
- the ceiling construction changes within the plane of the ceiling.

Main runners and cross furring members should not be let into masonry walls or partitions, and clearance of at least 1" must be provided at each end of the channels.

Expansion ceiling areas should have control joints spaced not to exceed 60' in either direction and the area within separated sections should not exceed 2,400 sq. ft. The continuity of grillage and wallboard should be broken over control joints. Control joints may be positioned to intersect light fixtures, heating vents, air diffusers, etc., which are usually considered weak spots.

2. Holes cut in gypsum board ceilings such as vents, grilles, access panels, light troffers, etc., cause a concentration of stresses in the gypsum board. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy and design, a control joint is not otherwise specified.

3. The spacing of hanger wires and channels are maximum and should not be exceeded. The grillage is designed to support the dead load of the gypsum board ceiling and is not designed to support concentrated loads of mechanical equipment or workmen. Independently supported catwalks and equipment platforms should be provided.

4. Where furred or suspended ceilings occur under roof construction, the plenum should be vented according to recommended engineering practice.

5. To retain maximum sound isolation, the integrity of the ceiling should not be voided by openings such as vents, light troffers, etc., so as to create sound leaks. The use of caulking to seal all cutouts and intersections with the adjoining structure is recommended.

6. Ridging or deformation at the panel joints may occur in gypsum board construction under adverse job or weather conditions. Back blocking end joints will minimize joint ridging and is recommended. Where back blocking is used, float the end joints between furring channels and back block with an 8" wide strip of gypsum board the full length of the joint adhesively applied over abutting ends, or screw-attach floated end joints to a 5' length of channel positioned parallel to and centered over end joint.

To comply with U. L. Designs 82-3 hr. and 221-2 hr., wallboard end joints should be aligned and backed by 2" wide face panel strips laid over the joints. Face panels should be fastened to continuous furring channels centered 2" either side of joint.

7. The PERF-A-TAPE* Joint System treatment of joints and screw heads may be omitted where the gypsum board serves as a base for the adhesive application of acoustical tile.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

In cold weather and during the period of wallboard lamination and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 70° F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Joint Treatment Folder for PERF-A-TAPE Joint System Specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. Furring Channels—USG Metal Furring Channel and/or USG Metal Studs—Nos. 158 (1½"),—212 (2½"),—358 (3½").
- b. USG Metal Furring Channel Clip.
- c. 1½" Cold Rolled Channels.
- d. 9 ga. Galvanized Hanger Wire.
- e. 16 ga. Galvanized Tie Wire.
- f. Gypsum Board—(¾") (1½") (¾") thick, 48" wide Tapered Edge SHEETROCK, (Regular) (Insulating — foil back) (FIRECODE) (FIRECODE "C") Gypsum Wallboard, or BAXBORD Gypsum Backing Board, lengths as required.
- g. 1" USG Drywall Screws—Type S.
- h. Joint Treatment—PERF-A-TAPE or DURABOND Joint System.
- i. USG Metal Trim (specify type from page 2).
- j. USG Control Joint No. 093.

grillage erection

9 gauge hangers shall be spaced not over 4'-0" in the direction of the 1½" main runner channels and not over (4'-0", 5'-0",

6'-0", 7'-0", or 8'-0") in the direction at right angles to the main runners, and within 6" of the ends of main runner runs and of boundary walls, girders or similar interruptions of ceiling continuity. (For hanger, main runner channel and cross furring channel spacing, see table page 2.)

Main runners shall be placed not over (4'-0", 5'-0", 6'-0", 7'-0", or 8'-0") o.c., properly positioned, leveled, and hangers shall be saddle tied along runner.

Main runners shall not be let into nor come in contact with abutting masonry walls. Runner channels shall be located within 6" of the walls to support the ends of the furring channels.

(USG Metal Furring Channels) (USG Metal Studs) shall be spaced (12") (16") (24") o.c. and securely clipped with USG Furring Channel Clips or saddle tied with two strands of 16-ga. tie wire to main runners or main support members and shall not be let into or come in contact with abutting masonry walls. End splices shall be provided by nesting channels or studs no less than 8" and securely wire tying.

Metal Furring Channel Clips shall be installed on alternate sides of the main runner channel. Wire-tie Metal Furring Channel to 1½" channel when clips cannot be alternated and to main support members.

At light troffers or any openings that interrupt the main runner or furring channels, reinforce grillage with ¾" cold rolled channels wire tied atop and parallel to the main runner channels.

panel erection

Gypsum board of maximum practical length shall be applied with the long dimension at right angles to the furring channel and fastened with 1" USG Drywall Screws—Type S spaced (8") (12") o.c. in the field of the board and along abutting ends. All abutting end or edge joints shall occur over the web surface of the furring channel and shall be fitted neatly and accurately with end joints staggered. Gypsum board shall be properly supported around all cut-outs and openings in the ceiling.

wallboard accessories

a. PERF-A-TAPE or DURABOND Joint System shall be used on all gypsum board joints and internal angles formed by the intersections of walls and ceilings.

b. Metal Trim No. () shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.


c. Fasteners shall be as shown on drawings or as herein specified. Fasteners shall be driven not less than ¾" from ends or edges of gypsum board to provide uniform dimple not over 1/32" deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

d. Control Joints shall be provided in the face layer as indicated and where detailed. Staple in place.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); SHEETROCK, FIRECODE (gypsum wallboard); BAXBORD (gypsum backing board); PERF-A-TAPE, DURABOND (joint treatment).

b-1497

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.




UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



UNITED
STATES
GYPSUM

suspended

ceilings

b

QUIETONE* Grid System

CEILING PANELS—MINERAL—WOOD FIBER—LUMINOUS PLASTIC

1506

description

In this system QUIETONE ceiling panels of mineral or wood fiber with acoustical properties—or decorative wood fiber panels—are quickly and easily installed on a suspended, exposed grid consisting of only three basic parts—main tees, cross tees and a wall angle. These specially designed grid components are made of heavy-gauge electro-galvanized steel finished with durable white baked enamel. The parts interlock to create a strong rigid construction that is flush and square. The grid assembles to form either 2'x2' or 2'x4' ceiling modules and provides easy access to the plenum space.

Acoustical ceiling panels for this assembly are 1/2" thick; available in two sizes, 2'x2' and 2'x4', and in two types, mineral fiber (MF) and wood fiber. QUIETONE wood fiber ceiling panels are available in these well-accepted patterns: **Pin Perforated** (plain white) with more than 1,000 perforations psf; a **Fissured** pattern simulating travertine marble; **Custom-Crylic**, a scrubbable finish in pin-perforated pattern. Check your U.S.G. representative for other wood fiber decorative patterns available locally.

QUIETONE MF Acoustical Panels for this assembly are available in two patterns, **Star Pin-Perforated** and **Fissured**. QUIETONE MF Panels are incombustible, strong, washable and offer good light reflectance and sound control characteristics. USG® Luminous Panels of flat white styrene plastic to blend with QUIETONE Ceiling Panels are available for use under fluorescent tube fixtures. The washable matte finish provides smooth diffused light and a 55% light transmission rating. The luminous panels give ready accessibility for fixture maintenance.

function and utility

Acoustical ceiling systems serve to conceal ductwork, open joists or unsightly old ceilings while providing beauty, concealed lighting and sound control. The QUIETONE Ceiling System meets these requirements and in addition offers other features:

Versatility—Adaptable for use in commercial and residential new construction or remodeling; the system's extra strength and moisture resistance suit it for such uses as commercial laundries and kitchens. A choice of patterns and module sizes are available to meet esthetic and design requirements.


Fire Resistance—QUIETONE MF Panels are classified incombustible, Class A, per Fed. Spec. SS-A-0118b and have a flame spread index of 5.

Sound Control—QUIETONE MF (Star Pin-Perforated Pattern) offers sound attenuation of 42 db, 11-frequency average, effectively retards sound travel through the ceiling and over partitions. Sound Transmission Class 39. Sound absorption: .55-.65 NRC.

Light Reflectance—QUIETONE Panels reflect 75% or better of the available light—Class A.

Economy—Simple low cost components and fast installation result in economical erected job costs. The washable vinyl paint surface on QUIETONE Panels keeps maintenance costs low.

QUIETONE ceiling grid



limitations

1. A non-load bearing ceiling construction.
2. Not a fire-resistance rated system.
3. USG Luminous Panels recommended for use with fluorescent fixtures only.
4. In ceiling constructions certain precautions concerning construction and ventilation are necessary for good performance (see Specifications, page 4).

QUIETONE wood fiber ceiling panel




Custom-Crylic Pin-Perforated pattern

QUIETONE MF ceiling panel






Star Pin-Perforated pattern

components




ceiling panels







wall angle attachment



wall angle at corners



cross tee splice at intersection with main tee



main tee splice at intersection with cross tee



specifications

notes to architect

1. The spacing of hanger wires and channels is maximum and should not be exceeded. The grillage is designed to support the dead load of the acoustical ceiling and is not designed to support concentrated loads of mechanical equipment or workmen, particularly after the ceiling tile has been applied. Independently supported catwalks and equipment platforms should be provided.

2. Where suspended ceilings occur under roof construction, the plenum should be vented according to recommended engineering practice.

3. To retain maximum sound isolation, the integrity of the ceiling should not be voided by openings such as vents, light troffers, etc., so as to create sound leaks.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architect Service Department, 101 So. Wacker Dr., Chicago, Ill. 60606.

general provisions

QUIETONE Ceiling Panels shall not be installed when the building is excessively cold and damp or hot and dry. Temperature and humidity conditions shall, as closely as possible, approximate those interior conditions which will exist when the building is occupied. All plastering, concrete and terrazzo work should be complete and dry. The panels shall not be installed unless satisfactory closures for windows and doors are in place and roofs are tight.

The heating system should be installed and operating where necessary to maintain proper conditions before, during and after the panels have been installed.

Poured concrete, gypsum or similar roof decks should be thoroughly dry and the space between such decks and the suspended ceiling adequately vented to the outside.

materials

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. QUIETONE Wood Fiber Ceiling Panel, (Pin-Perforated) (Fissured) (Custom-Crylic) pattern, (2'x2') (2'x4').
- b. QUIETONE MF Ceiling Panel, (Star Pin-Perforated) (Fissured) pattern, (2'x2') (2'x4').
- c. USG Decorative Ceiling Panel, (Custom-Crylic), (Custom), (Snowdrift), (Golden Veil) pattern, (2'x2') (2'x4').
- d. USG Luminous Panel, (2'x2') (2'x4').
- e. Main Tee.
- f. Cross Tee for 2'x2' Design.
- g. Cross Tee for 2'x4' Design.
- h. Wall Angle.
- i. 12 ga. Galvanized Strap Hanger.


erection

12-ga. hangers shall be spaced not over 4' along the main tees and within 6" of the ends of main tees, of main tee splices, of boundary walls, girders or similar interruptions of ceiling continuity. Main tees shall be placed 4' o.c., properly positioned, leveled, and hangers shall be wire tied along tees. Main tees shall not be let into nor come in contact with abutting masonry walls. Cross tees for 2'x4' design shall be spaced 2' o.c. along the main tees with notches securely interlocking the notches in main tees. Cross tees for 2'x2' design shall be placed at mid-point of 4' cross tees with notches securely interlocking the 2'x4' design cross tees. Wall angles securely attached 16" o.c. shall be provided at the wall intersections. At interior corners where angle is to continue, the flange shall be cut and the web bent to form corner overlapping angle flange. Exterior corners shall be neatly butted. Panels shall be inserted where shown on the drawings.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (ceiling panels); QUIETONE MF, QUIETONE (acoustical panels).

NOTE: Since methods and conditions of application and use are beyond our control, the United States Gypsum Company will not be responsible for failure of its products when not used according to our directions and specifications.

b-1506




UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



electric cable

ceiling heating

b

Radiant Heat Plaster Systems

1517

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|--|-------------|------------|------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. | RED TOP Radiant Heat Plaster—1" nom wd sub-fin flr on wd joist—spec ½" Type X plaster base att direct—5d nails 6" o.c.—fiber tape stapled over joints—elect heat cables embedded in ¼" radiant heat plaster clg wt 5 | FPRI 39 (f) | | N/A | clg matls 32 | Better heat emission, allows higher cable temps. than with other plasters | b-1517 |

description

These remarkable ceiling heating assemblies combine the first gypsum products to be specifically formulated for use with electric cable ceiling heat—RED TOP* Radiant Heat Plaster and Plaster Base. Their development represents a major breakthrough in providing ceiling heating assemblies with higher resistance to heat deterioration.

In these systems, special RED TOP Radiant Heat Plaster Base, ½" or ⅝" thick, 4' wide and in lengths of 8' to 14', is nailed directly to wood joists—or screwed directly to USG® Metal Furring Channels or to the RC-1 Resilient Channel for resilient application. Joints are covered with 2½" wide IMPERIAL* glass fiber reinforcing tape, staple applied. The electric cable then is stapled to plaster base in conventional manner. Application of RED TOP Radiant Heat Plaster follows—first a ⅜" fill coat to completely embed the cable; about one to two hours later, a ⅛" finish coat. In monolithic concrete construction Radiant Heat Plaster is applied directly to properly bonded surfaces in two coats to ⅝" thickness.

RED TOP Radiant Heat components maintain their integral strength and hardness at sustained operating temperatures (see Limitations).

function and utility

Wherever radiant electric cable ceiling heat is desired, one of these systems is readily applicable. They can be used in conjunction with walls of plaster, gypsum wallboard or exposed masonry. The ceiling finish can be either smooth troweled or textured. Other features:

Heat Emission—Because of its higher density and total plaster thickness of only ¼", RED TOP Radiant Heat Plaster provides faster, more efficient and more even heat emission than conventional plaster or laminated drywall ceiling heat installations. Gives more rapid response, less over-ride, greater comfort.

Long-Term Performance—Job-proven on more than 300,000 sq. ft. of ceilings applied under average conditions. This system avoids such faults of other methods as separation of lath or wallboard paper from core, delamination of plaster from lath, plaster cracking, "hot voids" in dry cavities, and puncturing of cable by finish nails.

Economy—Offers low applied costs; 1,200 sq. ft. per ton average plaster coverage. Components are quickly applied by conventional means with regular tools.

limitations

1. Cable operating temperature can reach as high as 135°F. provided heating cable wattage of 2.75 watts per lin. ft. and watt density of 25 watts per sq. ft. (a minimum cable spacing of 1.5" o.c. as specified by National Electric Code) are not exceeded. This compares with Gypsum Assn. maximum temperature restriction of 125°F. for heating elements in contact with conventional plaster.

2. A non-load bearing ceiling construction.

3. In ceiling constructions, certain precautions concerning


construction and ventilation are necessary for good performance (see Specifications, Page 4).

4. Maximum support spacing: 16" o.c. with base applied with long edges parallel with joists; 24" o.c. if applied with long edges across joists (see table following).

attachment of
RED TOP Radiant Heat Plaster Base






| thickness of base | type fastener for wood framing |
|-------------------|---|
| 1½" | Ring shank nail, countersunk, polished or blue—min. 1¼" long, 12½-ga., 1⅝" head dia. or Barbed shank nail, countersunk, cement coated—min. 1¼" long, 13-ga. dia., 1⅝" head dia. or 1¼" GWB-54 Annular Ring Nail, 12½-ga., ¼" head dia. with slight taper to small fillet at shank, bright finish, med. diamond point. or 1½", 5d cooler type nail—cement coated or 1¼" USG Drywall Screw, Type W or 13-ga. 1¼" long screw, 1⅝" flat head, blued |
| 5⁄8" | Ring shank nail, countersunk, polished or blue—min. 1⅜" long, 12½-ga., 1⅝" head dia. or Barbed shank nail, countersunk, cement coated—min. 1⅜" long, 13-ga., 1⅝" head dia. or 1⅜" Annular Ring Nail (specifications same as for GWB-54 except for length) or 1½", 6d cooler type nail—cement coated or 1¼" USG Drywall Screw, Type W |

Max. Framing Spacing (c. to c.): 16" with board applied parallel with joists, 24" with board applied across joists. Fastener Spacing (c. to c.): 7". Metal Framing Application: USG 1" Type S Screw, spaced 12" o.c., for attachment to RC-1 Resilient Channel or USG Metal Furring Channel.




components/details


scale: 3" = 1'0"




RED TOP radiant heat ceiling direct to monolithic concrete ceiling




RED TOP radiant heat ceiling IMPERIAL plaster base system/side walls




RED TOP radiant heat ceiling ROCKLATH plaster base system/side walls




floating interior angle system



details



control joint



perimeter isolation

specifications—notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.

2. Radiant heated lath and plaster ceiling surfaces (non-load bearing) will not resist stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that lath and plaster surfaces be isolated from all structural elements by control joints or other means where: (a) a ceiling abuts any structural element, dissimilar wall or partition assembly, or other vertical penetration; (b) the ceiling construction changes within the plane of the ceiling.

The following specifications cover the lathing and plastering materials for use in wood frame residential construction where individual ceiling areas do not exceed 500 sq. ft., or where room lengths do not greatly exceed 25 lin. ft. In unusual cases, where ceiling areas exceed these figures, it is recommended that a control joint be used. Suggested details may be obtained for individual job requirements.

3. Holes cut in a thin lath and plaster membrane such as vents, grilles, access panels, light troffers, etc., cause a concentration of stresses in the plaster. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy and design, a control joint is not otherwise specified.

4. Where contact or furred ceilings occur under roof construction, the plenum or attic space should be vented according to recommended engineering practice.

5. To retain maximum sound isolation, the integrity of the ceiling should not be voided by openings so as to create sound leaks.

6. **Wood Framing Requirements**—Wood framing shall meet the minimum requirements of FHA and local building codes.

7. **Insulation Recommendations**—Type and amount of insulation should be as specified by the heating contractor or the designer of the cable heating system; or, ceiling should be insulated according to minimum All-Weather Comfort Standards—R-24, 6" THERMAFIBER* Insulating Wool Blankets or R-24, 7" THERMAFIBER Blowing Wool. See USG Product Folder on Insulating Wool for additional information.

8. **Electric Cable**—The electric radiant heating cable should be an approved cable, of adequate wattage to properly heat the areas in which it is used (the cable is not sold or supplied by U.S.G.). The designer of the cable heating system should indicate the type, wattage, and spacing no closer than 1½" o.c., as specified by the National Electric Code. The electric radiant heating cable should not be used or placed into operation until the plaster is thoroughly dry.

After the RED TOP Radiant Heat Plaster Base and IMPERIAL Tape have been installed, the electric radiant heating cable should be applied. This should be done by others in accordance with the design requirements and the cable manufacturer's

specifications. The cable should be attached to the ceiling in such a manner that it is kept taut and does not sag away from the plaster base. All cable connectors and non-heating leads should be embedded into but not through the plaster base so they do not project beyond the surface of the plaster base any more than the heating wires.

9. **Painting**—The plaster should be dry, sound, clean, free of dust, grease, or oil. The cable must be de-energized at least 6 hours prior to the start of painting. Supplementary heat, if necessary, should be provided to maintain room conditions at the desired temperature until paint is thoroughly dry.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

The building temperature shall be maintained in a uniform range above 55°F prior to, during, and after the application of the RED TOP Radiant Heat Plaster components. All materials shall be delivered to the job in the original, unopened containers or bundles, stored in a place protected from exposure to the elements and from damage by tampering, and used in strict accordance with the manufacturer's directions.

materials

See USG product folders in this series: Plaster Bases & Accessories Folder for General Lathing Specifications; Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. RED TOP Radiant Heat Plaster Base, square edge (½") (⅝"), in lengths (8', 10', 12', 14') as long as practical to minimize the number of end joints.
- b. Nails and/or USG Drywall Screws as selected from Table, page 1. Nails are not available from U.S.G.
- c. Joint Reinforcement—IMPERIAL Tape.
- d. Staples for attachment of joint reinforcing tape—rosin coated, flattened, galvanized wire with legs not less than ⅜" in length (not available from U.S.G.).
- e. Plaster—RED TOP Radiant Heat Plaster.
- f. RC-1 SHEETROCK* Resilient Channel.
- g. USG Metal Furring Channel.
- h. USG 1½" Cold Rolled Channel.
- i. USG Metal Furring Channel Clips.
- j. 16 ga., 9 ga. Galvanized Wire.
- k. USG Electric Heat Controls—Low-voltage or Line-voltage Thermostats, Silent Thermal Relays.

plaster base attachment for wood framing

RED TOP Radiant Heat Plaster Base shall be applied to ceiling joists before wall materials are placed, and across joists with all end joints occurring over framing members, but staggered in adjacent rows. Nailing shall proceed from central portion of base toward ends and edges.

While nails are being driven, base shall be held in firm contact with underlying support. Nails shall be spaced approx. 7" o.c. and not less than ⅜" from edges and ends, except at floating

wall-ceiling angles. Heads of nails shall be set flush with surface of paper or slightly dimpled but not breaking paper. Plaster base shall be neatly cut and fitted for electrical outlets, etc.

resilient ceiling application

RC-1 Resilient Channels shall be attached at right angles to wood joists and fastened to soffit of joist with USG 1 $\frac{1}{4}$ " Type W screws driven through pre-punched holes in channel flange. *Do not use nails.* Channels shall be located within 6" of wall-ceiling intersection, spaced not more than 16" o.c., extended into all corners and fastened to corner framing. Do not cantilever channels more than 6". Channels shall be spliced directly under joists by spacing channels $\frac{1}{8}$ " apart and screwing both end attachment flanges to joist. Splices shall be staggered and not be made directly over plaster base edge joints. RED TOP Radiant Heat Plaster Base of maximum practical length shall be applied with long dimension at right angles to channels and with end joints centered over channels, staggered and neatly fitted. Plaster base shall be fastened to channels with USG 1" Type S screws spaced 12" o.c. in field of base and along abutting ends. Screws shall be driven at least $\frac{3}{8}$ " from ends or edges.

metal furring channel application

a. Grillage Erection. 9 ga. hangers shall be spaced not over 4' in the direction of main runners, not over 4' in the direction at right angles to 1 $\frac{1}{2}$ " main runner channels, within 6" of ends of main runner runs and boundary walls, girders or similar interruptions of ceiling continuity.

Main runners shall be placed not over 4' o.c., properly positioned, leveled, and saddle tied to hangers. Main runners shall not be let into nor come in contact with abutting masonry walls. Runner channels shall be located within 6" of the walls to support furring channels.

Metal Furring Channels shall be spaced 16" o.c. and securely clipped with Metal Furring Channel Clips or saddle tied with two strands of 16-ga. tie wire to main runners or supports, and shall not be let into nor come in contact with abutting masonry walls.

End splices shall be provided by nesting channels at least 8" and securely wire tying. Clips shall be installed on alternate sides of main runners. Wire tie furring channel to 1 $\frac{1}{2}$ " channel and to supports when clips cannot be alternated.

At light troffers or openings that interrupt main runners or furring channels, reinforce grillage with $\frac{3}{4}$ " cold rolled channels wire tied atop and parallel to main runners.

b. Application of Base. (*Specify last paragraph from Resilient Ceiling Application above.*)

floating ceiling angle application

Recommended framing practices for floating ceiling angles shall be used. RED TOP Radiant Heat Plaster Base must fit snugly into all ceiling angles. At the wall/ceiling intersection, first nail shall be nominally 7" from wall intersection. Nail spacing shall be as specified in the remainder of ceiling.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured and/or sold by that company: USG (metal products); RED TOP (plaster and gypsum plaster base); IMPERIAL (reinforcing tape); THERMAFIBER (insulating wool); SHEETROCK (gypsum wallboard, metal channel).

b-1517

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

On the sidewalls, all wallboard or gypsum plaster base must be applied to overlap and maintain firm contact at ceiling line to support ceiling plaster base previously applied. Along ceiling intersection, nails directly at ceiling angle shall be omitted with the first nail nominally 8" from ceiling intersection.

application of joint reinforcing tape

IMPERIAL Tape shall be applied to all ceiling joints and attached with a spring-driven hand stapler, using specified staples. Tape shall be applied over full length of all edge and butt joints, but shall not overlap at intersections. Two staples, one on each side of joint, shall be placed at end of tape. Keeping tape taut, staples shall then be placed 12" o.c. along tape length, alternating from side to side. The other end of tape shall be secured with two staples, one on each side of joint. In the ceiling/wall angles, tape shall be stapled 12" o.c. to ceiling base only.

mixing and application of plaster

a. Mixing. Plaster shall be mixed according to manufacturer's directions using a heavy-duty drill capable of producing a minimum of 650 rpm *under load*. No more material than can be applied in 30 minutes shall be mixed. Do not retemper.

b. Application. RED TOP Radiant Heating Plaster shall be applied to a total thickness of $\frac{1}{4}$ " over RED TOP Radiant Heat Plaster Base. Apply a fill coat of plaster parallel to the cable direction and of sufficient thickness to *completely cover cable*. Do not use cables as a screed. Fill coat shall be leveled with a trowel, rod or darby to fill any low spots or to remove any high ridges, etc. Fill coat shall be "toothed" to provide a key for finish coat, by using a serrated darby or by lightly brooming prior to set. *The average thickness of fill coat should be $\frac{3}{16}$ ".* After fill coat has developed sufficient suction, a finishing coat of RED TOP Radiant Heat Plaster shall be applied to provide a total thickness of $\frac{1}{4}$ ". Fill all voids and imperfections. Final trowel when surface has become firm. Avoid using edge of trowel during final troweling.

Use water sparingly. Do not over-trowel. Always work to a wet edge. Avoid drying joinings.

Monolithic concrete surfaces shall be prepared with plaster bonding agent in a thin continuous film and plaster shall be applied in same manner prescribed above, except to total thickness of $\frac{3}{8}$ "—consisting of $\frac{5}{16}$ " fill coat to completely cover the cable and anchor device, and $\frac{1}{16}$ " finishing coat.

c. Option for Sand Float Finish. Fill coat application shall not be altered. The finishing coat shall have (up to 20) lb. of clean silica sand per 80-lb. bag of RED TOP Radiant Heat Plaster. (*Note: Specify quantity depending upon texture desired.*) Quantity of sand added per bag shall be consistent. Sand float finish application shall be same as outlined for trowel finish, except that when finish has become firm, but unset, it shall be floated to desired texture, using a sponge, carpet, or other float. Use water sparingly.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

ceiling heating

b

radiant

THERMALUX* Electric Heating Systems

1527

A.I.A. File No. 30-C-44/20-B-2



UNITED STATES GYPSUM

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-------------|---|----------|------------|------|-----------------------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 1 hr. est | THERMALUX elect radiant heated ceiling—2" nom wd sub & fin flr—2x10 wd joist 16" o.c.—1/2" THERMALUX htg panels & filler panels (both Type C core) att with spec insul nails 6" o.c.—1/4" THERMALUX fin panels lamin over base panels—joints fin clg wt 3 | | N/A | | clg mats 38 (excl htg syst costs) | Est. fire rating based on constr. in UL Des 42—1 hr. Completely integrated USG system. Uniform heat, lower operating temps., exceptional comfort | b-1527 |

description

THERMALUX is a highly efficient electric heating system that combines the superior qualities of laminated gypsum board ceilings with the custom comfort, cleanliness, quiet, and trouble-free performance of electric radiant heat. Most significant in the assembly is a patented heating panel consisting of a heating element on an inert, incombustible gypsum board base. These thermostatically controlled panels provide the exact amount of heat needed for comfort while operating at lower temperatures, and consequently lower costs, than other types of electric radiant heating.

In these systems THERMALUX Heating Panels and Filler Panels are attached to wood joists or furring with insulated nails spaced 10" o.c. (6" o.c. for fire-rated construction). For steel bar joist or concrete slab construction, panels are nailed to wood furring strips.

Electric power for the THERMALUX panels is supplied by a standard branch circuit in each room. Any branch circuitry conforming to code regulations may be used between the disconnect device and the lead-in junction box. The power circuit is installed in the wiring recess and attached to electrode clips which are connected to the panels.

After the system is tested for proper installation and performance, a 1/4" thick high-density THERMALUX Finishing Panel is laminated to the base layer panels with special THERMALUX Adhesive. The ceiling is finished with THERMALUX formulated PERF-A-TAPE* Joint System and standard decorating materials.

THERMALUX Electric Heating Systems are approved by Underwriters' Laboratories, Inc., conform to the National Electrical Code and meet Federal Housing Administration standards. Installation is by licensed THERMALUX contractors.

function and utility

Economical, incombustible, safe heating systems for use in virtually every type of new construction or in remodeling—wherever quality permanent heating and the finest ceiling construction are required. In THERMALUX Heating Systems these additional features are offered:

Design Freedom—Being part of the ceiling, THERMALUX permits complete freedom in placement and use of walls and in interior decoration.

Comfort—Quiet, uniform draft-free radiation of warmth is provided. Each room contains its own heating system and control permitting desired selection of comfort level.

Economy—Saves space and original equipment costs. Low-cost materials erect quickly using accepted installation methods. Low operating costs, virtually no maintenance and reduced cleaning and redecorating costs provide continuous savings over other heating systems.

Time Proven and tested through years of research and hundreds of jobs, THERMALUX Electric Heating Panels are warranted for 25 years.

limitations

1. THERMALUX Heating Panels must be attached only to wood framing or furring with THERMALUX insulated nails.

2. Max. frame spacing: 24" o.c. (16" o.c., fire-rated const.).
3. Not recommended as an acoustical tile base.

components

Components used in THERMALUX Electric Radiant Heating Systems have been designed to meet rigid U.S.G. requirements and are coordinated to provide superior-quality radiant heated ceiling construction.

THERMALUX Heating Panels consist of four parts: gypsum board, asbestos insulation, a large area resistor, and 1/2" wide copper electrodes located at least 1" from the panel edge.

THERMALUX Heating panels are designed for 240-volt AC-DC operation at 115° F. temperature or lower and must be connected in parallel. At the design voltage, current input is 0.063 amp/sq. ft., heat output is 15 watts/sq. ft. (nominally 50 btu/sq. ft./hr.). The table below gives the electrical properties of individual panels.


The Heating Panels, manufactured from regular gypsum board or from special fire-rated "Type C" board, are 1/2" thick, 4' wide and available in lengths up to 12'. Two types are available: one with the heating element over the entire area, another with the element over one-half the area for use when narrow panels are needed. Panels are readily cut to exact length on the job or easily cut out for installation of lighting.

(components continued, page 3)

THERMALUX heating panels—electrical properties


| heated area size (ft.) | area (sq. ft.) | heat output | | current req'd (amps) |
|------------------------|----------------|-------------|---------|----------------------|
| | | watts | btu/hr. | |
| 2x10 | 20 | 300 | 1000 | 1.25 |
| 2x12 | 24 | 360 | 1200 | 1.50 |
| 4x10 | 40 | 600 | 2000 | 2.50 |
| 4x12 | 48 | 720 | 2400 | 3.00 |

Note: Special sizes available on order. Max. length: 16 ft.




details


application to wood joists



application to furred concrete



application to bar joists



components (continued from page 1)

THERMALUX Filler Panels are used as a base layer in areas where heating is not required and in wiring recesses. Available in 1/2" thick, 4' wide panels with regular or fire-rated "Type C" gypsum board core and in lengths up to 12'.

THERMALUX Finishing Panels, specially designed for superior heat transmission and radiation, are 1/4" high-density gypsum panels, 4' wide, in lengths up to 12'. Used as face layer ceiling panels.

Insulated Nails, with a nylon sleeve, must be used to attach Heating and Finishing Panels to wood framing.

Circuit Bushings, designed to fit all standard types of raceway/wiring systems, serve as wiring recess entrance for branch circuit conductors.

Electrode Clips are crimped on branch circuit conductors and then positively attached to the copper electrode on installed heating panels.

Finishing Materials required are (1) **THERMALUX Adhesives**, specially formulated for heat resistance, used to apply gypsum finishing panels; (2) **THERMALUX formula PERF-A-TAPE Joint System** for fine quality finished joints.

Temperature Controls are low or line-voltage thermostats and silent thermal relays designed to provide quick response and optimum comfort control.

Insulation—THERMAFIBER® Insulating Wool Blankets, Blowing Wool, or rigid roof insulation are used to provide Installed Thermal Resistance according to NMWIA All-Weather Comfort Standards—Ceilings, R-24; walls, R-11; floors, R-13. See USG Insulating Wool Product Folder for more information.

Electrical Materials are standard products selected according to local regulations and practice.

specifications—notes to architect

1. Advance planning of THERMALUX Heating Systems will assure economical installations and satisfactory performance. The building should be insulated with THERMAFIBER Insulating Blankets, Blowing Wool, or rigid roof insulation, in accordance with National Mineral Wool Insulation Assn. recommendations concerning insulating value, installation methods, venting and vapor barriers for electrically heated buildings. In concrete slab construction, insulation up to 1 1/2" thick is recommended between furring strips in ceilings with living areas above, and additional rigid roof insulation should be installed over the slab in exposed roof areas. The heat loss for each room and the entire building should be calculated by a method such as recommended by the American Society of Heating, Refrigeration & Air Conditioning Engineers.

2. The following specifications cover application of the THERMALUX Electric Radiant Heating System. Reference should be made in the electrical, insulation, roofing, walls and ceilings sections calling attention to work specified here.

3. To retain maximum sound isolation, the integrity of the ceiling should not be voided by openings so as to create sound leaks.

4. **Wood Framing**—shall meet the minimum requirements of FHA and local building codes.

5. Maximum furring spacing for concrete floor/ceiling slabs: 24" o.c.; for bar joists as follows:

maximum furring spacing

| furring size | bar joist spacing | | | |
|--------------|-------------------|-----|-----|-----|
| | 1' | 2' | 3' | 4' |
| 2 x 2 | 24" | 16" | | |
| 2 x 3 | | 24" | 16" | |
| 2 x 4 | | | 24" | 16" |

scope

The contractor doing the work of this section shall be responsible to furnish all labor, materials and equipment to completely install the THERMALUX Electric Heating System as manufactured by the United States Gypsum Company, and as herein described.

The calculation of heat loss and the design of the THERMALUX Heating System shall also be a part of this contract.

general conditions

In cold weather the building shall be heated during the application of the THERMALUX Heating System to maintain a uniform temperature in the range of 45° F to 70° F., and ventilation shall be provided to eliminate excessive moisture. All materials, as specified below, shall be delivered to the job in original unopened containers or bundles, stored in a place protected from exposure to the elements and from damage by tampering.

The installation and application of all THERMALUX materials shall be in accordance with the latest printed directions of the United States Gypsum Company.

Appropriate blocking for wiring recesses and provisions for proper installation of heating branch circuits and temperature and humidity controls shall be provided.

materials

See USG product folders in this series: Joint Treatment Folder for Joint Treatment Specifications; Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- Ceiling Panel—THERMALUX Finish Panel, tapered edges, 1/4" thick, 4' wide—lengths as required.
- Electric Heating Panel—THERMALUX Heating Panel, 1/2" thick, 4' wide (regular) (Type C) core—lengths as required.
- Filler Panel—THERMALUX Filler Panel, 1/2" thick, 4' wide (regular) (Type C) core—lengths as required.
- THERMALUX Insulated Nails.
- THERMALUX Circuit Bushings.
- THERMALUX Electrode Clips.
- Finishing Materials
 - THERMALUX Laminating Adhesive (with supplementary nailing) or THERMALUX Contact Bond Adhesive.
 - THERMALUX formula Ready-Mixed PERF-A-TAPE Joint System.
- Temperature Controls—THERMALUX 820-E low voltage thermostats or THERMALUX 800 line voltage thermostats and THERMALUX silent thermal relays.
- Humidistat shall provide a single-pole double throw control at low or line voltage (by others).
- Exhaust fan shall control humidity (by others).
- Insulation—THERMAFIBER Insulating Blankets or Blowing Wool (specify from Insulating Wool Products Folder).
- Electrical Materials—junction boxes, branch circuits, disconnect devices, connectors and other necessary components to complete the electrical system shall all be standard products, manufactured and distributed nationwide. All electrical components for branch circuits shall be selected according to local regulations and practice and installed in conformance with the National Electrical Code.
- Wood Furring—(2x2)(2x3)(2x4) constr. grade (by others).
- Tie Wire—16 ga. galvanized.
- Concrete Fasteners—Ramset Drive Pins, Type 3330, 11/64" shank diameter, 3" long or equal (by others).



radiant

ceiling heating

b

THERMALUX* Electric Heating Systems 1527

installation

Electrical power shall be supplied to the THERMALUX Electric Heating System by standard heating branch circuits. The choice of raceway system shall be governed by preference and local code regulations and shall be installed in conformance with the National Electrical Code.

Branch circuits for supplying power to the THERMALUX Electric Heating System shall be designed to carry specific heating loads in accordance with the National Electrical Code.

A disconnect device shall be provided to protect conductors and equipment from current overload. The feeder and heating circuits for the THERMALUX System shall be connected independently of electrical circuits for other purposes.

furring erection

Wood furring strips shall be installed where indicated on the drawings, shimmed to a true, level plane and attached to supports as follows:

1. To Bar Joists—Wood furring spaced (16") (24") o.c. (*select from table page 3*) shall be securely saddle tied to joists with a double strand of 16 ga. tie wire. Furring shall not be cantilevered more than 8".

2. To Concrete Slabs—Wood furring spaced 24" o.c. shall be securely fastened to concrete slabs with Ramset Type 3330 Drive Pin or equal having at least 1 3/8" penetration into concrete. Fasteners shall be spaced 24" o.c. and placed at least 5" away from furring ends. Where wiring recesses occur additional furring shall be provided to support the THERMALUX Panels. Wiring recesses shall have 1/2" gypsum board strips attached to exposed furring edge.

Openings that interrupt the furring shall be reinforced at each side with additional furring securely fastened to supports. Furring shall not be let into nor come into contact with abutting masonry walls. At least 1" clearance must be provided at ends of runs and boundary walls.

THERMALUX electric heating panels

The THERMALUX Electric Heating Panels shall be installed (parallel) (perpendicular) to ceiling framing members with insulated nails spaced 10" o.c. (6" o.c. for fire-rated construction). The nails may be driven in any part of the panels except through the 1/2" wide copper electrodes. A 1" wide clear area at panel edges is provided for nailing. Recommended clearance of nails from edge of panels is 3/8". The panel heating element shall not contact any grounded metal devices or combustible materials. Filler panels shall be installed in ceiling area where heating panels are not required. A wiring recess shall be formed so that power connections to heating panels are completely enclosed in incombustible, electrically non-conductive gypsum board.

When necessary, heating panels may be cut to length or cut to width only in a non-heating area.

When Heating Panel is adjacent to stairwells, hatchways,

skylights or soffits, which create "outside" corners, the SHEETROCK gypsum board installed in the vertical wall plane shall be at least 1/2" thick and cover both the Heating Panel and Finish Panel edges. The corner shall be protected with PERF-A-BEAD* reinforcement and PERF-A-TAPE Compound. Panel layout shall be made so that Panels are not installed with ends directly butted, or wired in series. Wiring recess shall be located either at the center with heating panels wired to both sides or at end of panels with connections to one side.

lighting fixtures

Lighting fixtures, other electrical devices and openings shall be installed by positioning the THERMALUX Electric Heating Panels so that the fixtures are preferably located in a strip of filler panel. However, fixtures may be located within a heating panel by removing a section between electrodes. Clearances to be observed between fixtures and openings and electrically energized parts of panels shall be at least 8" from lighting fixtures, outlet boxes and junction boxes, and 2" or more from ventilating openings and other such openings in the ceiling. Cutouts must be spaced at least 6" from panel ends, and 24" or more apart. Limit number of cutouts to one in panels up to 8' in length, and two cutouts in longer panels.

electrical connections

The THERMALUX Circuit Bushing shall be provided for the branch circuit wiring to enter the wiring recess in the ceiling. Electrode clips shall be used to connect branch circuit conductors to upper electrodes in the heating panels. The clips shall be pressure-fitted to the conductors using standard terminal pliers. The clip shall then be slipped onto a corner of the electrical resistance element which has been lifted from the gypsum base of the heating panel; the corner tab of heating circuit conductors stapled into position in the wiring recess.

inspection, testing and control

Electrical inspection and testing of the THERMALUX Electric Heating System shall be done after wiring connections are completed but before THERMALUX Finish Panels are installed. All circuits must be energized to assure that heating panels will function properly. The actual amperage of the circuit measured with an ammeter, shall correspond with the calculated amperage demand based on 0.063 amp per square foot of heating panel installed.

THERMALUX finish panels

THERMALUX Finish Panels shall be firmly laminated to the THERMALUX Electric Heating Panels and THERMALUX Filler Panels with THERMALUX Adhesive. The entire ceiling shall be impacted with a rubber mallet to assure complete bond and positive erection. All joints and nail heads in the THERMALUX Finish Panels shall be treated with THERMALUX formula of Ready-Mixed PERF-A-TAPE Joint Compound and PERF-A-TAPE Reinforcing Tape per manufacturer's directions.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal accessories and other products); THERMALUX (ceiling heat system); SHEETROCK (gypsum wallboard); THERMAFIBER (insulating wool); PERF-A-TAPE (joint treatment); PERF-A-BEAD (corner reinforcement).

b-1527

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

ceilings

b

including exposed grids

AURATONE* Suspension Systems

ACOUSTICAL PANELS & TILE

1547

A.I.A. File No. 39-B-1

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-----------------------|---|------------------------|------------|------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 3 hrs. (beam 5 hrs.) | AURATONE FIRECODE $\frac{5}{8}$ "x24"x48" acoust clg panels in Susp Exp Grid Syst—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $2\frac{1}{2}$ " conc on cellular sti flr clg wt 1.2 | UL Des 65-3 hr (f) | 40 to 44 | | clg matls 72 | See Sound Control Products Folder for STC values of various patterns | b-1547 |
| 3 hrs. (beam 4 hrs.) | AURATONE FIRECODE $\frac{3}{4}$ "x12"x12" acoust clg tile on Concealed Z-Spline Syst—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $2\frac{1}{2}$ " conc deck on cellular sti flr clg wt 1.2 | UL Des 59-3 hr (f) | 40 to 44 | | clg matls 112 | See Sound Control Products Folder for STC values of various patterns | b-1547 |
| 2 hrs. | AURATONE FIRECODE $\frac{5}{8}$ "x24"x48" acoust clg panels in Susp Exposed Grid Syst—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $1\frac{1}{2}$ " PYROFILL gypsum conc roof deck with $\frac{1}{2}$ " SHEETROCK formbd over bar joist clg wt 1.2 | UL Des RC-6-2 hr (f) | 40 to 44 | | clg matls 72 | See Sound Control Products Folder for STC values of various patterns | b-1547 |
| 2 hrs. | AURATONE FIRECODE $\frac{5}{8}$ "x24"x48" or 24"x24" acoust clg panels in Susp Exposed Grid Syst—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $2\frac{1}{2}$ " conc deck on riblath over bar joist clg wt 1.2 | UL Des 72-2 hr (f) | 40 to 44 | | clg matls 72 | See Sound Control Products Folder for STC values of various patterns | b-1547 |
| 2 hrs. | AURATONE FIRECODE $\frac{5}{8}$ "x12"x12" acoust clg tile on Concealed Z-Spline Syst—clg interrupted—light fixt prot by $\frac{1}{4}$ " min wool bd— $2\frac{1}{2}$ " conc on riblath over bar joist clg wt 1.2 | UL Des 84-2 hr (f) | 40 to 44 | | clg matls 105 | See Sound Control Products Folder for STC values of various patterns | b-1547 |
| 2 hrs. | AURATONE FIRECODE $\frac{5}{8}$ "x12"x12" acoust clg tile on Concealed Z-Spline Syst—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd—2" THERMOFILL gypsum conc roof deck with $\frac{1}{2}$ " SHEETROCK formbd over bar joist clg wt 1.2 | UL Des RC-13-2 hr (f) | 40 to 44 | | clg matls 105 | See Sound Control Products Folder for STC values of various patterns | b-1547 |
| 1½ hrs. (beam 3 hrs.) | AURATONE FIRECODE $\frac{1}{2}$ "x24"x48" acoust clg panels in Susp Exposed Grid Syst—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd—2" conc deck on riblath over bar joist clg wt 1.2 | UL Des 18-1½ hr (f) | 40 to 44 | | clg matls 65 | See Sound Control Products Folder for STC values of various patterns | b-1547 |
| 1 hr. | AURATONE FIRECODE $\frac{5}{8}$ "x24"x48" or 24"x24" acoust clg panels in Susp Exposed Grid Syst—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd—2" nom wd sub & fin flr over 2x10 wd joist clg wt 1.2 | UL Des 31-1 hr (f) | 40 to 44 | | clg matls 72 | See Sound Control Products Folder for STC values of various patterns | b-1547 |
| incomb. class A | AURATONE $\frac{1}{2}$ "x24"x24" or 24"x48" acoust clg panels in Susp Exposed Grid Syst clg wt 1.0 | authority ASTM E84-61T | 40 to 44 | | clg matls 53 | Basic incombustible lay-in acoustical panels; NRC varies with pattern | b-1547 f-1927 |
| incomb. class A | AURATONE $\frac{5}{8}$ "x24"x24" or 24"x48" acoust clg panels in Susp Exposed Grid Syst clg wt 1.0 | authority ASTM E84-61T | 40 to 44 | | clg matls 60 | Basic incombustible lay-in acoustical panels; NRC varies with pattern | b-1547 f-1927 |

description

AURATONE Ceilings are chosen over other systems because they provide balance in functional requirements—fire protection, superior sound attenuation, subtle beauty, accessibility—plus economy.

AURATONE Acoustical Panels and Tile are composed of prepared mineral fiber and lightweight perlite, formed by a special process. In these systems they are mechanically suspended (Mounting No. 7) from the overhead construction. AURATONE systems are installed by expert U.S.G. approved acoustical contractors.


Where the economy of large size panels and greater accessibility to plenum space is desired, AURATONE Ceiling Panels are installed by the lay-in method on any of several exposed inverted tee grid systems commercially available. These grids are made from steel or aluminum and may be fire-rated or non-rated.

The panels are available in either regular AURATONE or fire-rated AURATONE FIRECODE* grades, 24"x24" and 24"x48" sizes, $\frac{1}{2}$ " and $\frac{5}{8}$ " thicknesses, four different patterns (see page 2), and with painted or plastic-coated surface finish. See USG

Sound Control Products Folder in this series for full product description and detailed sound control properties of AURATONE.

As tile, this material is available in regular AURATONE and fire-rated AURATONE FIRECODE grades, 12"x12" and 24"x24". Tile ceilings may be erected on the concealed or concealed accessible USG Z-spline Systems (see USG Folder on ACOUSTONE* Tile Suspension Systems for details).


(continued on page 4)




U. L. Design No. 65—
3 Hour (5-hour beam)

U. L. Design No. 72—
2 Hour


AURATONE patterns/details



Pin-Perforated



Random




Fissured




Snowdrift

concrete on cellular steel form with beam

U.L. Design No. 65—3 Hour (5-hour beam)







U.L. Design No. 59—3 Hour (4-hour beam)



gypsum roof deck on bar joists

U.L. Design No. RC 13—2 Hour





including exposed grids

ceilings

b



AURATONE® Suspension Systems
ACOUSTICAL PANELS & TILE

1547

details


gypsum roof deck on bar joists

U.L. Design No. RC 6—2 Hour




concrete on riblath over bar joists

U.L. Design No. 84—2 Hour




wood deck on wood joists


U.L. Design No. 31—1 Hour



light fixture protection shield—1 1/4" THERMAFIBER mineral wool light fixture cover



box assembly



tent assembly



including exposed grids

ceilings



AURATONE* Suspension Systems
ACOUSTICAL PANELS & TILE

1547

function and utility

Fire Resistance—Incombustible components provide up to 3-hour fire resistance ratings (5-hour beam) for floor-ceiling constructions (see table, page 1). Fire hazard classification: flame spread 25, fuel contributed 25, smoke developed 5.

Sound Control—Sound absorption range of .60 to .80 in NRC average, sound attenuation up to 49 db (11-freq. avg.) depending on pattern. Optimum balance of sound absorption and attenuation properties.

Light Reflectance—Class "A."

Versatility—Wide variety of patterns and sizes of acoustical panels and tile available. Adaptable for use in all types of new construction or alteration. Easily combined with lighting fixtures or with AIRSON* Air Distribution Systems to meet exact comfort requirements.

Economy—Large size AURATONE panels erect quickly; offer low maintenance costs.

limitations

1. AURATONE Acoustical Panels and Tile are not recommended for use where exposed to steam or very high humidity. They should not be used below wainscot height nor where exposed to impact, abrasion or tampering.

2. In ceiling constructions certain precautions concerning construction and ventilation are necessary for good performance (see Specifications).

specifications

notes to architect

1. The spacing of hanger wires and channels are maximum and should not be exceeded. The grillage is designed to support the dead load of the acoustical ceiling and is not designed to support concentrated loads of mechanical equipment or workmen, particularly after the ceiling tile has been applied. Independently supported catwalks and equipment platforms should be provided.

2. Where contact, furred or suspended ceilings occur under roof construction, the plenum should be vented according to recommended engineering practice.

3. To retain maximum sound isolation, the integrity of the ceiling should not be voided by openings such as vents, light troffers, etc., so as to create sound leaks.

4. The THERMAFIBER* Rated Light Fixture Protection, a 1 1/4" thick semi-rigid mineral wool board shipped in a standard modules and job assembled using standard tie wire, is required for use on fire-rated construction in accordance with Underwriters' Laboratories specifications.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured and/or sold by that company: USG (metal products); AURATONE, ACOUSTONE, FIRECODE (acoustical panels and tile); AIRSON (air distribution systems); THERMAFIBER (insulation products); PYROFILL, THERMOFILL (gypsum concrete).

b-1547

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

5. Allowable openings for light fixtures and diffuses are dependent upon the type of construction used. Refer to the specific test for this data.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general provisions

AURATONE units shall not be installed unless satisfactory closures for window and other openings are in place and roofs are tight. Temperatures in the working areas shall be well above freezing. Conditions during installation shall as closely as possible approximate those conditions which will exist when the building is occupied.

The recommendations for construction conditions found in the latest Acoustical Materials Association Bulletin shall apply.

materials

See USG Folder on Sound Control Products for technical information.

Acoustical Materials by the United States Gypsum Company shall be:

1. AURATONE Acoustical Ceiling Panels, square edge
Type: (Regular) (FIRECODE)
Size: (24"x24") (24"x48")
Thickness: (1/2") (3/8")
Pattern: (Fissured) (Random) (Pin-Perforated) (Snowdrift)
Finish: (White) (Plastic coated)
2. AURATONE Acoustical Tile
Type: (Regular) (FIRECODE)
Size: (12"x12") (24"x24")
Edge: (Beveled) (Kerfed T&G)
Thickness: (1/2") (3/8") (3/4")
Pattern: (Fissured) (Random) (Pin-Perforated) (Snowdrift)
Finish: (White) (Plastic coated)

Systems for Application Shall Be:

1. Exposed Grid System by (specify manufacturer).
2. USG (Concealed) (Concealed Accessible) Z-Spline.

Note: For complete specification see ACOUSTONE Suspension Systems Folder.

installation

Grid suspension system and acoustical (panels) (tile) shall be installed in accordance with manufacturers' directions.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

ceilings

b

ACOUSTONE* Suspension Systems

ACOUSTICAL TILE

1557



A.I.A. File No. 39-B-1

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|-----------------------|--|------------------------|------------|------|---------------------|---|------------------|
| | | | 11-f | 16-f | | | |
| 3 hrs. | ACOUSTONE 180 Fissured or MOTIF'D ¾"x12"x12" min acoust tile on Concealed Z-Spline Syst—2½" conc deck on riblath over bar joist clg wt 1.3 | UL Des 96-3 hr (f) | 39 est | | clg matls 112 | | b-1557 |
| 2 hrs. (beam 2 hrs.) | ACOUSTONE 120 Fissured or Glacier or MOTIF'D ¾"x12"x12" min acoust tile on Concealed Z-Spline Syst—clg interrupted—light fixt prot by 1¼" THERMAFIBER min wool bd—2½" conc deck on cellular stl flr clg wt 1.3 | UL Des 85-2 hr (f) | 39 est | | clg matls 112 | | b-1557 |
| 2 hrs. | ACOUSTONE 120 Fissured or Glacier or MOTIF'D ¾"x12"x12" min acoust tile on Concealed Z-Spline Syst—2½" conc deck on riblath over bar joist clg wt 1.3 | UL Des 41-2 hr (f) | 39 est | | clg matls 112 | | b-1557 |
| 1½ hrs. (beam 3 hrs.) | ACOUSTONE 90 Fissured or Glacier or MOTIF'D ¾"x12"x12" min acoust tile on Concealed Z-Spline Syst—2" conc deck on riblath over bar joist clg wt 1.3 | UL Des 6-1½ hr (f) | 47 est | | clg matls 105 | | b-1557 |
| 1 hr. | ACOUSTONE 90 Fissured or Glacier or MOTIF'D ¾"x12"x12" min acoust tile on Concealed Z-Spline Syst—2" nom wd sub & fin floor over wd joist 16" o.c. clg wt 1.3 | UL Des 15-1 hr (f) | 47 est | | clg matls 112 | | b-1557 |
| incomb. class A | ACOUSTONE "F" ¾"x12"x12" or 12"x24" min acoust tile on Concealed Z-Spline Syst | authority ASTM E84-61T | 29 est | | clg matls 83 | Basic concealed spline acoustical tile system; several patterns available | b-1557 f-1927 |
| incomb. class A | ACOUSTONE "F" ¾"x12"x24", 12"x36", or 12"x48" min acoust tile on Exp Z-Spline Syst | authority ASTM E84-61T | 26 est | | clg matls 83 | Basic exposed spline acoustical tile system for accessibility | b-1557 f-1927 |

description

In these systems ACOUSTONE Mineral Fiber Acoustical Tile is mechanically suspended (mounting No. 7) by concealed or exposed USG® Z-Splines, special metal clips and wall finish channels to provide an economical, incombustible, rigid ceiling. The USG Z-Spline systems are suitable for use in all types of new construction or in remodeling to provide accessible attachment of acoustical ceilings to 1½" carrying channel grille, steel bar or wood joists or wood furring strips. Flat metal, tee or angle splines provide full support across the Z-Splines and prevent breathing through the tile. Lighting and air conditioning fixtures are readily coordinated with this system.

ACOUSTONE Mineral Fiber Acoustical Tile for this assembly is available in several different types, sizes, patterns and finishes (see Specifications, page 6). ACOUSTONE "F", white, featuring a natural fissure texture, has Class A light reflectance and is available with either square or beveled edges. Variations of this texture such as ACOUSTONE Glacier provide sound absorption as high as .75-.85 N.R.C. A third dimension of light and shadow may be achieved by deviating from the flat ceiling with bold relief Shadowline patterns of ACOUSTONE "F" and Glacier. MOTIF'D* ACOUSTONE is available in seven different basic relief patterns or in custom patterns to suit design requirements. Foil-backed ACOUSTONE "db" erected on the concealed Z-Spline system eliminates the need for extra backing and provides sound attenuation of 40 STC. Fire resistance ratings for floor and ceiling assemblies up to 3 hours are available using ACOUSTONE 180 Mineral Acoustical Tile (see table above).

These systems are also ideally suited for use with AURATONE* Tile. See separate Systems Folder for detailed information on AURATONE Ceiling Panels and Tile. For complete data on ACOUSTONE and AURATONE types and styles, see separate USG Folder in this series on Sound Control Products.

function and utility

Acoustical ceiling systems serve to conceal mechanical and electrical equipment and services while providing beauty, comfort and sound control. The USG Z-Spline system with appropriate acoustical treatment meets these requirements and in addition offers these features.

Versatility—Adaptable for use in all types of new construction—commercial, institutional, industrial and residential—or in the remodeling or alteration of existing buildings. A great variety of patterns and textures of acoustical tile and panels are available to meet esthetic design requirements.

Fire Resistance—Assembled from incombustible components. Fire resistance ratings up to 3 hours for steel and concrete construction and 1 hour for wood frame construction have been established.

Sound Absorption—Wide range available up to .75-.85 N.R.C.

Sound Attenuation—Up to 40 STC with foil-backed ACOUSTONE "db" which efficiently retards sound travel through the ceiling and over partitions.

Light Reflectance—Class A.

Accessibility—Acoustical tiles are easily removed and replaced providing complete or partial accessibility to the plenum space.

Flexibility—Easily combined with lighting and air conditioning fixtures. For information on AIRSON* Air Distribution Systems, see separate USG Systems Folder in this series.

Economy—Few parts needed, resulting in fast, low-cost erection. Easily cleaned and spray or brush painted for low maintenance costs.

limitations


1. ACOUSTONE Mineral Acoustical Tile is not recommended for use where exposed to steam or very high humidity. It should not be used below wainscot height or where exposed to impact, abrasion or tampering.

2. Limiting span, 1¼" USG Z-Spline: 5'.

3. In ceiling constructions certain precautions concerning construction and ventilation are necessary for good performance (see Specifications, page 6).

*Reg. U.S. Pat. Off.

components



concealed Z-Splines attached to 1½" carrying channel grille

This method offers an economical, simple, rigid construction and permits the use of flush joints where lighting conditions are not too severe.

This suspension method provides metal spline supports in kerfs along the four edges of each unit. Splines also act as a continuous seal to minimize air travel through the joints. Self leveling of the tile joints is assured since intersecting corners of four adjacent units are supported on the same member.

concealed Z-Splines direct to bar joists

This method may be employed when bar joists are spaced a maximum of 5 feet o.c. The Z-Splines are attached direct to the bottom chord of the bar joist with the No. 87 clip. The saving gained by eliminating the 1½" channel is often lost in "shimming" since bar joists seldom form a true ceiling plane. It is therefore suggested this method only be used where head-room is critical.


concealed accessible Z-Spline system

The concealed accessible system is a modified Z-Spline method designed to provide complete (or partial, where desired) accessibility to the plenum area above the ceiling. Modern architectural demands requiring use of the plenum for piping, electrical equipment, sheet metal work, and other mechanical devices have made accessibility a much desired feature of the acoustical ceiling.

This system completely conceals the fact that tile are removable for access. The finished ceiling appearance is that of an ACOUSTONE "F" mineral tile ceiling with beveled edges. Due to the special characteristics of the system only bevel edge tile is recommended. It is further suggested that ¾", 12"x24" tile be used, although the system can accommodate ¾", 12"x12" tile as well.





"E-Z-S" Z-Spline metal suspension system

Because of its ease of installation, this method is economical and provides a low-cost acoustical ceiling with complete accessibility to the area above the ceiling. Any type lighting arrangement is easily adaptable to the E-Z-S Suspension System. Lighting troffers can be installed quickly and economically. Full advantage can be taken of the economy of gravity-held diffusers laid directly in the Z-Spline to replace equivalent area of ACOUSTONE tile. This permits maximum flexibility of lighting arrangement. See details, next page.




details

USG 1-1/2" channels
4'-0" o.c.






details




concealed Z-Spline system



concealed accessible Z-Spline system



"E-Z-S" Z-spline suspension system



details

fire-rated construction

U. L. Design No. 96—3-Hour




ACOUSTONE 180 Mineral Acoustical Tile suspended on a standard concealed Z-spline system provides a 3-hour rating for bar joist and concrete floor (or roof) construction.

U. L. Design No. 41—2-Hour

ACOUSTONE 120 Mineral Acoustical Tile suspended on a standard concealed Z-spline system provides a 2-hour rating for bar joist and concrete floor (or roof) construction.





U. L. Design No. 6—1½-Hour

ACOUSTONE 90 Mineral Acoustical Tile suspended on a standard concealed Z-spline system provides a 1½-hour rating for bar joist and concrete floor (or roof) construction.



U. L. Design No. 85—2-Hour (2-hour beam)

ACOUSTONE 120 Mineral Acoustical Tile suspended on a standard concealed Z-spline system provides a 2-hour rating for 8-in. steel beam (also rated 2 hours) and concrete floor (or roof) construction.




details


fire-rated wood frame construction

U.L. Design No. 15—1-Hour

ACOUSTONE® 90 Mineral Acoustical Tile suspended on a standard concealed Z-spline system provides a 1-hour rating for wood joist and deck (or floor) construction.



cross section parallel to joist





cross section transverse to joist


wood furring direct attachment of Z-Spline

This method is particularly adaptable to existing ceilings where the surface is in such condition that it is impractical to attach ACOUSTONE tile by cementing.

This system is installed by nailing wood furring strips, maximum spacing of 4' o.c., and attaching Z-Splines to the furring strips with the No. 90 Clip. The No. 90 Clip may also be used to attach Z-Splines directly to existing wood joists or to wood furring strips nailed to exposed concrete surfaces.



detail at wall—A





detail at wall—B

details


Shadow-Line ceilings

3/4"x24"x24"

Shadow-Line ACOUSTONE "F"
acoustical tile



detail at wall—A



detail at wall—B

specifications

notes to architect

1. The spacing of hanger wires and channels are maximum and should not be exceeded. The grillage is designed to support the dead load of the acoustical ceiling and is not designed to support concentrated loads of mechanical equipment or workmen, particularly after the ceiling tile has been applied. Independently supported catwalks and equipment platforms should be provided.

2. Where contact, furred or suspended ceilings occur under roof construction, the plenum should be vented according to recommended engineering practice.

3. To retain maximum sound isolation, the integrity of the ceiling should not be voided by openings such as vents, light troffers, etc., so as to create sound leaks.

4. The THERMAFIBER* Rated Light Fixture Protection, a 1 1/4" thick semi-rigid mineral wool board shipped in standard modules and job assembled using standard tie wire, is required for use on fire rated construction in accordance with Underwriters' Laboratories specifications.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general provisions

Bases to receive acoustical units and the units themselves shall not be installed unless satisfactory closures for windows and other openings are in place and roofs are tight. Temperatures in the working areas shall be well above freezing.

The area or room in which acoustical units are to be installed shall not be damp; i.e. plaster, terrazzo floor, etc. shall be previously installed and dry.

materials

See USG Product Folder in this series for technical information on Sound Control Products.

Acoustical Tile By the United States Gypsum Company Shall Be:

ACOUSTONE "F"—(White or Ivory)

3/4"x12"x12" (square or bevel edge)

3/4"x12"x24" (square or bevel edge centerscored)

3/4"x12"x24" (bevel edge centerscored for Concealed Accessible System)

3/4"x12"x36" (square edge)

3/4"x24"x24" nom. (square edge)

ACOUSTONE "db"

See ACOUSTONE "F" sizes

ACOUSTONE "90", "120" and "180"

3/4"x12"x12" (square edge)

MOTIF'D ACOUSTONE—(White or Ivory)

3/4"x12"x12" Pattern No. (1, 2, 3, 11, 19, 33, or 40)

ACOUSTONE Finesse

See ACOUSTONE "F" sizes

ACOUSTONE Glacier

3/4"x12"x12" (square edge)

3/4"x12"x24" (square edge)

3/4"x24"x24" nom. (square edge)

**Shadow-Line ACOUSTONE "F"** $\frac{3}{4}$ "x12"x24" (special rabbeted edge) $\frac{3}{4}$ "x24"x24" (special rabbeted edge)**Domino ACOUSTONE "F"** $\frac{3}{4}$ "x12"x12" (square edge)**Base for Application Shall Be:**

1½" cold rolled carrying channel grillage supported by No. 10 ga. hanger wire.

Wood Grillage Shall Be:

2"x2" or 2"x3" wood nailing strips—straight grain, kiln dried and free from knots

1"x3" wood furring strips—straight grain, kiln dried and free from knots

Systems for Application Shall Be:

USG Concealed Z-Spline for ACOUSTONE and MOTIF'D ACOUSTONE of 12"x12" and 12"x24" sizes.

$\frac{3}{4}$ " USG Z-Spline

Flat Spline of galvanized steel—for flush joints

Spring steel spacer

USG finish channel and finish channel corner plate

82-A clips—to attach Z-Spline to 1½" c.r. carrying channel

85 or 87 clip—to attach Z-Spline direct to bar joist

90 clip—to attach Z-Spline direct to wood furring

Concealed Accessible Z-Spline System for ACOUSTONE.

$\frac{3}{4}$ " or 1¼" Z-Spline

T-Spline of galvanized steel

Angle Splines—23½" and 10 15/16" of galvanized steel

Finish channel and finish channel corner plate

82-A clips to attach Z-Splines to 1½" carrying channels

E-Z-S Suspension System — for ACOUSTONE and MOTIF'D ACOUSTONE of 12"x24", 12"x36", 12"x48", and 24"x24" nom. sizes.

1¼" Z-Spline painted white

T-Spline of galvanized steel

Angle spline of galvanized steel

Spring steel spacer

USG finish channel and finish channel corner plate

82-A clip—to attach Z-Spline to 1½" (C.R.) carrying channel

85 or 87 clip—to attach Z-Spline direct to bar joist

90 clip—to attach Z-Spline direct to wood furring

installation

Base—1½" cold rolled channel grillage—No. 10 ga. hanger wires shall be securely attached at 4' o.c. 1½" carrying channels shall be tied to the hanger wires and shall be hung level at a maximum spacing of 4' o.c. The 1½" channel adjacent to an intersecting wall shall be placed not more than 12" from the wall.

Wood Grillage—main members (2"x2" or 2"x3") shall be suspended not more than 36" o.c. 1"x3" furring strips shall be nailed in place not more than 12" o.c.

metal suspension**Concealed Z-Spline Installation Method:****1. MOTIF'D ACOUSTONE****2. ACOUSTONE "F"**

$\frac{3}{4}$ " Z-Splines shall be attached 12" o.c. and at right angles to:

- Metal Grillage by No. 82-A clip
- Bar Joist by No. 85 or 87 clip.
- Wood Framing by No. 90 clip.

The tile shall be supported by inserting the Z-Spline flanges into the kerfed edges of the tile. Abutting edges shall be aligned by inserting flat steel splines into the kerfs of the transverse edges of the tile. ACOUSTONE finish channel moulding shall be provided at the wall intersections and spring steel spacers placed into the channel 12" o.c. Finish channel corner plate shall be used at all exterior corners. At interior corners where channel is to continue, flanges shall be cut and the web bent to form corners, overlapping channel flanges.

ACOUSTONE F for Concealed Accessible System:

- $\frac{3}{4}$ " or 1¼" Z-Splines shall be attached 24" o.c. and at right angles to the metal grillage by No. 82-A clips.
- Accessible Tile—USG $\frac{7}{16}$ "x $\frac{7}{16}$ "x23½" Angle Splines shall be inserted in the kerf on each 24" edge with both angles on one end extending ½" beyond the edge to support the tile on the Z-Splines.

The tile is installed by seating one end of the tile in the Z-Spline and seating the protruding angles on the adjoining Z-Spline.

E-Z-S Z-Spline Metal Suspension Installation Method:**ACOUSTONE "F"**

1¼" painted Z-Spline shall be attached 24" o.c. and at right angles to:

- Metal Grillage by No. 82 clip.
- Bar Joists by No. 85 or 87 clip.
- Wood Furring or Framing by No. 90 clip.

$\frac{3}{4}$ "x12"x24" tile shall be placed on top of the lower flange of the Z-Spline; Angle Splines or T-Splines shall be inserted in the kerf of the abutting or transverse edges of the tile.



ceilings

b

ACOUSTONE* Suspension Systems
ACOUSTICAL TILE

1557

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ACOUSTONE, MOTIF'D ACOUSTONE (mineral acoustical tile); AIRSON (air distribution systems); AURATONE (ceiling tile, panels); THERMAFIBER (insulation products).

b-1557

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

ceilings

b

AIRSON* Air Distribution Systems

PRESSURIZED ACOUSTICAL CEILINGS

1567



A.I.A. File No. 39-B-1

| fire rating | description | test no. | stc rating | | relative cost index | comments | folder reference |
|----------------------|---|------------------------|-------------------------|------|-----------------------------------|--|------------------|
| | | | 11-f | 16-f | | | |
| 3 hrs. (beam 5 hrs.) | AIRSON AURATONE FIRECODE Air Distr Syst on Exposed Grid— $\frac{3}{4}$ "x24"x48" acoust panels 50% AIRSON A-5 or 100% AIRSON A-2—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $2\frac{1}{2}$ " conc deck on cellular stl fir clg wt 1.2 | UL Des 65-3 hr (f) | 41 est | | clg matls 102 | Includes air controls in panels; "cost index" excludes zone barriers & plenum insul. | b-1567 |
| 3 hrs. (beam 4 hrs.) | AIRSON AURATONE FIRECODE Air Distr Syst on Concealed Z-Splines— $\frac{3}{4}$ "x12"x12" acoust tile 100% AIRSON A-2 or 50% AIRSON A-5—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $2\frac{1}{2}$ " conc deck on cellular stl fir clg wt 1.2 | UL Des 59-3 hr (f) | 40 to 44 | | clg matls 142 | Includes air controls in tile—"cost index" excludes zone barriers & plenum insul. | b-1567 |
| 2 hrs. | AIRSON AURATONE FIRECODE Air Distr Syst on Exposed Grid— $\frac{3}{4}$ "x24"x48" acoust panels 50% AIRSON A-5 or 100% AIRSON A-2—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $1\frac{1}{2}$ " PYROFILL gypsum conc roof deck with $\frac{1}{2}$ " SHEETROCK formbd over bar joist clg wt 1.2 | UL Des RC-6-2 hr(f) | 41 est | | clg matls 102 | Includes air controls in panels; "cost index" excludes zone barriers & plenum insul. | b-1567 |
| 2 hrs. | AIRSON AURATONE FIRECODE Air Distr Syst on Exposed Grid— $\frac{3}{4}$ "x24"x48" or 24"x24" acoust panels 50% AIRSON A-5 or 100% AIRSON A-2—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $2\frac{1}{2}$ " conc deck on riblath over bar joist clg wt. 1.2 | UL Des 72-2 hr (f) | N/A | | clg matls 102 | Includes air controls in panels; "cost index" excludes zone barriers & plenum insul. | b-1567 |
| 2 hrs. (beam 2 hrs.) | AIRSON ACOUSTONE 120 Air Distr Syst on USG Concealed Z-Spline Susp Syst— $\frac{3}{4}$ "x12"x12" min acoust tile 50% AIRSON A-5 or 100% AIRSON A-2—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $2\frac{1}{2}$ " conc deck on cellular stl fir clg wt 1.3 | UL Des 85-2 hr (f) | 39 est | | clg matls 142 | Includes air controls in tile; "cost index" excludes zone barriers & plenum insul. | b-1567 |
| 2 hrs. | AIRSON AURATONE FIRECODE Air Distr Syst on Concealed Z-Splines— $\frac{3}{4}$ "x12"x12" acoust tile 100% AIRSON A-2 or 50% AIRSON A-5—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $2\frac{1}{2}$ " conc deck on riblath over bar joist clg wt 1.2 | UL Des 84-2 hr (f) | 40 to 44 | | clg matls 135 | Includes air controls in tile—"cost index" excludes zone barriers & plenum insul. | b-1567 |
| 2 hrs. | AIRSON AURATONE FIRECODE Air Distr Syst on Concealed Z-Splines— $\frac{3}{4}$ "x12"x12" acoust tile 100% AIRSON A-2 or 50% AIRSON A-5—clg interrupted—light fixt prot by $\frac{1}{4}$ " THERMAFIBER min wool bd— $2\frac{1}{2}$ " THERMOFILL gypsum conc roof deck with $\frac{1}{2}$ " SHEETROCK formbd over bar joist clg wt 1.2 | UL Des RC-13-2 hr(f) | 40 to 44 | | clg matls 135 | Includes air controls in tile—"cost index" excludes zone barriers & plenum insul. | b-1567 |
| incomb. class A | AIRSON AURATONE Air Distr Syst on Exposed Grid— $\frac{3}{4}$ "x24"x24" or 24"x48" acoust panels slotted AIRSON A-5 or A-2 on a 100%, 50% or 25% basis clg wt 1.2 | authority ASTM E84-61T | N/A | | clg matls 102 | Air controls in panels; "cost index" excludes zone barriers & plenum insul. | b-1567 f-1927 |
| incomb. class A | AIRSON ACOUSTONE "F" Air Distr Syst on USG Concealed Z-Spline Susp Syst— $\frac{3}{4}$ "x12"x12" or 12"x24" min acoust tile—slotted AIRSON A-2 or A-5 clg wt. 1.3 | authority ASTM E84-61T | 36 est based on 50% A-5 | | clg matls 112 | Basic concealed system; "cost index" excludes zone barriers & plenum insul. | b-1567 f-1927 |
| incomb. | AIRSON Grid Air Distr Syst—Exposed AIRFLO grid systems for standard acoust panels—adjustable air distr through grid itself | — | N/A | | clg matls 102 excl plenum treatmt | Basic exposed grid system with unslotted panels—steel or aluminum grid | b-1567 f-1927 |


description

In the AIRSON* Air Distribution Systems, primary equipment supplies properly conditioned air to the plenum chamber above a suspended ceiling of acoustical tile or panels. The air is forced through controlled jets in the acoustical ceiling material or in the grid system to provide draft-free air distribution and a controllable comfort level throughout the space. Suitable for both heating and cooling, the AIRSON Systems may be zoned to account for varying design requirements within the occupied space. The systems described below offer proper air distribution together with the beauty, high sound absorption, sound attenuation and light reflection of incombustible acoustical ceilings.

Where air distribution through the acoustical material is desired, ACOUSTONE* Mineral Tile suspended mechanically on the USG Concealed Z-Spline System or AURATONE Non-combustible Acoustical Panels on an exposed grid system are used. Specially designed $\frac{3}{4}$ " thick AIRSON ACOUSTONE tiles 12"x12", 12"x24" or 24"x24" are foil-backed, fire-resistant,

available in either the natural fissured pattern or the bas relief patterns of MOTIF'D* ACOUSTONE tile. AURATONE panels for this assembly are $\frac{3}{8}$ " thick and available in two different patterns (see Specifications). Fire resistance ratings for floor and ceiling assemblies up to 3 hours are available using AURATONE FIRECODE* Ceiling Panels (see table above).










(continued on page 7)




A.I.A. File No. 39-B-1

components/details


AIRSON ACOUSTONE system




Top and bottom views of AIRSON ACOUSTONE A-5 tile (above) show adjustable slides located on back of unit, and adjustment from face of unit made easily with ordinary ice pick for air flow control.




AIRSON ACOUSTONE A-2 Tile




A-2 or A-5
3/4"x12"x12" AIRSON
ACOUSTONE "F"
or AIRSON MOTIF'D
ACOUSTONE mineral
acoustical tile



detail at wall—B



detail at wall—A



removable
split angle detail

AIRSON Air Distribution Systems safe blowing distance †

| uninterrupted AIRSON space height—in. | parallel to joists—ft. | perpendicular to open steel joists—ft. |
|---|------------------------------|--|
| 5 to 6 | 20 to 25 | 14 to 18 |
| 7 to 8 | 25 to 30 | 18 to 21 |
| 9 to 10 | 30 to 40 | 21 to 28 |
| 11 to 12 | 40 to 50 | 28 to 35 |
| 13 to 18 | 50 to 55†† | 35 to 38†† |
| 19 to 30 | 55 to 60†† | 38 to 42†† |
| 31 to 40 | 60 to 65†† | 42 to 46†† |
| over 40 | 65 to 75†† | 46 to 53†† |

†From supply duct end to opposite wall. Determined from job test data. ††Includes 5% to 10% variation in static pressure and jet velocity.

components / details

AIRSON AURATONE system




100% A-2 Fissured



100% A-5 Pin-Perforated



50% A-5 Pin-Perforated




50% A-2 Fissured



25% A-2 Fissured




25% A-5 Pin-Perforated



Adjustable damper slide provides control of air passing through the two openings in A-2 panels without removing the panel.


The AIRSON AURATONE system combines all the qualities of the AIRSON Air Distribution System with the added flexibility of AURATONE Panels. The panels are available in two patterns with two jet arrangements (A-2 and A-5) and 25%, 50% or 100% slotting as shown above. When erected on a commercially available exposed grid system, these panels also offer fire resistance plus an optimum balance between sound attenuation and sound absorption. For more information on construction and details, see separate USG Systems Folder on AURATONE Suspension Systems.

U.L. Design No. 65—3-Hour (5-hour beam)
 (2-hour bar joist Design Nos. 72 and RC-6 also available)




details

AIRSON AIRFLO grid system






The AIRSON AIRFLO grid system utilizes acoustical materials in 2'x2' or 2'x4' panel sizes and provides for air distribution through the grid. Hollow-tee sections, fabricated of steel, have air-flow slots that are fully adjustable and provide 100% control without removing acoustical panels.



AIRSON LOK grid system

The AIRSON LOK grid is an extruded aluminum grid system that uses 2'x2' or 2'x4' acoustical panels. It is designed with two parallel orifices in the runner. Each pair of orifices is spaced 4" o.c., with factory installed dampers available as an optional feature. Generally, the AIRSON LOK grid system is specified for average or higher-than-average ceiling heights or where unusual moisture conditions prevail.









ceilings

b

AIRSON® Air Distribution Systems
PRESSURIZED ACOUSTICAL CEILINGS

1567

technical data


AIRSON ACOUSTONE A-2 $\frac{3}{4}$ " x 12" x 12" FOIL BACKED TILEAIRSON ACOUSTONE A-5 $\frac{3}{4}$ " x 12" x 12" FOIL BACKED TILEAIRSON AURATONE A-2 $\frac{3}{8}$ " x 24" x 48" CEILING PANELSAIRSON AURATONE A-5 $\frac{3}{8}$ " x 24" x 24" CEILING PANELS

Graphs based on 70° F air flow into 70° F space.


*Reg. U.S. Pat. Off.

technical data

AIRSON AIRFLO T-2 grid $\frac{3}{8}$ " x $23\frac{3}{8}$ " x $47\frac{3}{8}$ " AURATONE PANELS




AIRSON LOK grid $\frac{3}{8}$ " x $23\frac{3}{8}$ " x $47\frac{3}{8}$ " AURATONE PANELS




4" Spot Jet

DAMPER OPEN



6" Spot Jet

DAMPER OPEN



Graphs based on 70° F air flow into 70° F space.



description (continued from page 1)

For air flow through the acoustical material, two jet arrangements are offered: the A-5 with 5 orifices per sq. ft. meets large flow requirements and normal ceiling height conditions; the A-2 with 2 orifices per sq. ft. gives deeper penetration for high ceiling requirements. Adjustable dampers installed on the back of the ceiling permit air flow to be controlled after installation. Each AURATONE panel pattern is available with 25%, 50% or 100% slotting in either jet arrangement.

Where the economy of large size panels and greater accessibility are required, plain, unslotted AURATONE Ceiling Panels may be erected on the AIRSON AIRFLO® grid or AIRSON LOK® grid suspension system. In these exposed grid systems, conditioned air is distributed through controllable orifices in the grid members. The AIRSON AIRFLO grid consists of steel fabricated, hollow tee sections with air distribution slots in the face of the tee. The AIRSON LOK grid, consisting of aluminum tee-sections with orifices spaced 4" o.c., is recommended for use where high moisture and humidity conditions prevail. Adjustable dampers are available for the tee-sections to provide controllable air distribution.

To assure high quality installation, AIRSON Systems are available through dependable contractors carefully selected and licensed by the United States Gypsum Company.

function and utility

Job Proven—Thousands of applications have shown the adaptability of AIRSON Systems to all types of new construction or modernization wherever air conditioning is required and the ultimate in environmental comfort is desired. AIRSON Systems are backed by far more actual job experience than any other pressurized plenum type of air distribution.

Comfort—Uniform air distribution of conditioned air is provided through controlled air velocity and air penetration over the entire conditioned space. Undesirable drafts and air stagnation are eliminated.

Control and Balancing—Slide controls in every active tile or grid permit adjustment of air velocity and balance of air motion in the occupied space without removing tile.

Appearance—The timeless beauty of ACOUSTONE® Mineral Acoustical Tile with its natural fissures masking the AIRSON orifices, or the two distinctive patterns of AURATONE, provide a pleasant aesthetic appointment to any architectural project.

Fire Resistance—Incombustible components offer fire resistance ratings up to 3 hours.

Sound Control—Good sound attenuation effectively retards sound travel through the ceiling and over partitions. Sound absorption properties effectively quiet the occupied space (ACOUSTONE: 39.8 db, 70-80 NRC).

Versatility—A wide variety of ceiling materials, patterns and constructions meet most design requirements. The uninterrupted ceiling surfaces with ceiling-wide air distribution are ideal for quick, economical allocation of partitions or space alteration. Comfort adjustments are readily made with controls found in the system.

Economy—Maintenance costs for cleaning and repainting are low because the air flow keeps dirt away from the ceiling. If required, AIRSON ACOUSTONE and AURATONE can be cleaned easily with a vacuum cleaner or damp sponge or can be repeatedly spray or brush painted. The elimination of supply diffusers and reduction in terminal ductwork frequently provides substantial savings over conventional systems.

limitation

AIRSON ACOUSTONE and AURATONE products are not recommended for use where exposed to steam or very high humidity.

specifications

notes to architect

1. The AIRSON Systems can be adapted to almost any heating and cooling requirements. Application information and the necessary design data required to establish system static pressure, penetration and percentage of open tile or lineal feet of open grid or runners is available from U.S.G. In addition, the AIRSON Contractor can support you in making design, installation and service decisions and also provide a preliminary cost survey without obligation.
2. AIRSON ACOUSTONE Tile should not be used for air returns; separate grilles are recommended.
3. AIRSON AIRFLO System may not be suitable for use in salt water coastal areas; the AIRSON LOK System is recommended.
4. Where large quantities of conditioned air are required, specially engineered Spot Jets should be placed in the center of the acoustical tile.
5. To insure proper system performance, exterior plenum walls should be insulated, care must be taken to insure that the AIRSON space is tight and free from leakage, and all mouldings should be tightly caulked. Sound attenuation and noise reduction coefficient range of the acoustical tile should be specified.
6. The spacing of hanger wires and channels is maximum and should not be exceeded. The grillage is designed to support the dead load of the acoustical ceiling and is not designed to support concentrated loads of mechanical equipment or workmen, particularly after the ceiling tile has been applied. Independently supported catwalks and equipment platforms should be provided.
7. The THERMAFIBER® Rated Light Fixture Protection, a 1¼" thick semi-rigid mineral wool board shipped in standard modules and job assembled using standard tie wire, is required for fire-rated construction in accordance with Underwriter's Laboratories specifications.
8. The heating and cooling plants, including all supply and return air ductwork to and from the areas incorporating the AIRSON System, all included wall and ceiling return air grilles, and any auxiliary heating and cooling units should be installed by others.
9. Vinyl ivory painted ACOUSTONE or ACOUSTONE PC is recommended for applications subjected to high density smoke or cooking fumes such as in restaurants, snack shops, bars, etc.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

scope—This contractor shall furnish and install AIRSON System of air distribution for heating (and cooling) where shown on the drawings. All material shall be furnished and installed by an applicator licensed by the United States Gypsum Company. All overhead architectural, mechanical, and electrical work shall be completed, all opening closures shall be installed, and room areas shall be free from excessive moisture prior to the installation of the system.

general provisions—Bases to receive acoustical units and the units themselves shall not be installed unless satisfactory closures for windows and other openings are in place and roofs are tight. Temperatures in the working areas shall be well above freezing.

The area or room in which acoustical units are to be installed shall not be damp; i.e. plaster, terrazzo floor, etc. shall be previously installed and dry.

system performance—The air distribution ceiling system shall contain an incombustible dampering method for balancing air flow into the conditioned space and shall be adjustable from the room side of the ceiling, without removal of the acoustical tile or board. Each slotted tile shall have not more than 1/2 of 1% open area to produce an air velocity of not less than 25 feet per minute (FPM) and no more than ____ FPM at ____ inches above the floor (data obtainable from AIRSON Penetration Charts). The noise reduction coefficient range of the tile shall be no less than ____ (see USG Sound Control Products Folder for specific values). The ceiling attenuation must average no less than ____ db (see published values for AIRSON ACOUSTONE and AIRSON AURATONE).

materials—See USG Product Folder in this series for technical information on Sound Control Products.

Acoustical Tile by the United States Gypsum Co. Shall Be:

AIRSON ACOUSTONE Mineral Acoustical Tile—Foil Backed.

- a. 3/4" x 12" x 12" (A-2, A-5 slotted, unslotted).
- b. 3/4" x 12" x 24" (A-2, A-5 slotted, unslotted).
- c. 3/4" x 24" x 24" (A-2, A-5 slotted, unslotted).

AIRSON MOTIF'D ACOUSTONE—Foil Backed.

3/4" x 12" x 12" (A-2, A-5 slotted, unslotted), Pattern No. (1, 2, 3, 11, 19, 33 or 40).

AIRSON AURATONE (FIRECODE) Acoustical Ceiling Panels.

5/8" x 24" x (24", 48") (A-2, A-5 slotted or unslotted) (25%, 50%, 100%), Pattern (Fissured, Pin-Perforated).

Base For Application Shall Be:

1 1/2" cold rolled carrying channel grillage supported by No. 10 ga. hanger wire.

Materials For AIRSON ACOUSTONE System Shall Be:

- a. 3/4" USG Z-Spline.
- b. Flat Spline of galvanized steel.
- c. Spring steel spacers.
- d. Finish channel and finish channel corner plates.
- e. 82-A Clips—to attach Z-Spline to 1 1/2" cold rolled carrying channels.
- f. R & L Split Angles & L-Splines with tabs for access.

Materials For AIRSON AIRFLO Shall Be:

- a. AIRFLO Main Runners of .020 steel having a baked enamel finish.
- b. AIRFLO Cross-Runners, Open (and closed) Type (as required by the mechanical engineer from the AIRSON charts).
- c. AIRFLO Mouldings.

Materials For AIRSON LOK System Shall Be:

- a. AIRSON LOK Main Runners.
- b. AIRSON LOK Cross Runners, Vented (and solid) Type (as required by the mechanical engineer from the AIRSON charts).
- c. AIRSON LOK Mouldings.

installation

Base—1 1/2" cold rolled channel grillage—No. 10 ga. hanger wires shall be securely attached at 4' o.c. 1 1/2" carrying channels shall be tied to the hanger wires and shall be hung level at a maximum spacing of 4' o.c. The 1 1/2" channel adjacent to an intersecting wall shall be placed not more than 12" from the wall.

AIRSON ACOUSTONE—3/4" Z-Splines shall be attached 12" o.c. and at right angles to metal grillage by No. 82-A clip. The tile shall be supported by inserting the Z-Spline flanges into the kerfed edges of the tile. Abutting edges shall be aligned by inserting flat steel spline (or R & L Split Angle & L-Spline for access) into the kerfs of the transverse edges of the tile. ACOUSTONE finish channel shall be provided at the wall intersections and spring steel spacers placed into the channel 12" o.c. Finish channel corner plate shall be used at all exterior corners. At interior corners where channel is to continue, flanges shall be cut and the web bent to form corners, overlapping channel flanges.

AIRSON Slides—Attach to the back side of all tile with jets.

AIRSON Space—AIRSON Space shall be provided above the suspended ceiling. The contractor shall check all drawings and job conditions and ascertain code or other requirements for covering and sealing the top and sides of the AIRSON Space and furnish and install the same. He shall make certain under any circumstances that the space is sealed tight against air leakage. *He shall insulate, if necessary, any walls of the space exposed to outside temperatures with a minimum of 1" thick 3/4 pcf density glass fiber insulation.*

AIRSON Zone Barriers—AIRSON Zone Barriers shall be furnished and installed where shown on the drawings. Zone Barriers shall be constructed of AIRSONITE*-FT. Top edge shall be turned at least 2", coated with adhesive, and held permanently in place with a sheet metal angle fastened securely. All edges shall be lapped at least 2" and cemented together. Bottom edges must be lapped at least 3" on the back of the ACOUSTONE Mineral Acoustical Tile and cemented directly to the tile.

AIRFLO and AIRSON LOK Grillage—Installation of the AIRFLO and AIRSON LOK grillage shall be in accordance with the manufacturers' recommendations and with the details shown in their literature.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ACOUSTONE, MOTIF'D ACOUSTONE (mineral acoustical tile); AIRSON (air distribution systems); AURATONE FIRECODE (ceiling panels); AIRFLO, AIRSON LOK (metal grillage); AIRSONITE (zone barriers); THERMAFIBER (insulation products); SHEETROCK (formboard); PYROFILL, THERMOFILL (gypsum concrete).

b-1567

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



floor—ceilings

b**USG® Floor Plank Systems****1607**

A.I.A. File No. 10-D/23-D



| fire rating | description | test no. | sound rating ⁺ |
|-----------------|---|--------------------------------|-------------------------------------|
| 2 hrs. | USG Dry Floor System - 1/2" MASTICAL gypsum cement concrete - 2" USG Floor Plank welded to bar joists 48" o.c. - USG metal furring channels 24" o.c. wire tied to joists - 5/8" SHEETROCK FIRECODE "C" gypsum wallboard attached 12" o.c. with 1" Type S screws - joints finished subflr wt 17 | UL-266 CK-6612-26 | (11-freq.) STC INR 48 -14 |
| 2 hrs. (est) | USG Dry Floor System - Same construction as above but with Sound Insulative Floor Underlayment of 1/2" USG mineral fiber sound deadening board and 1-1/8" MASTICAL cement concrete over floor plank subflr wt 24 | CK-6612-28 | STC INR 50 -4 |
| 2 hrs. (est) | USG Dry Floor System - Same construction as above but with Sound Insulative Floor Underlayment of 1" USG mineral fiber sound deadening board and 1-1/2" MASTICAL cement concrete applied over floor plank subflr wt 27 | BBN-670114 & 670115 | STC INR 53 +1 |

+ Sound tests based on 1/2" thick SHEETROCK wallboard

description

USG Dry Floor Systems are lightweight, incombustible assemblies ideally suited for use with bar joists and floor loads normally found in apartment buildings. With suitable framing and attachment, these systems resist uplift and lateral forces from winds and earthquakes. USG Floor Plank with T & G metal edges is laid dry, without grout and welded to the joists. A 1/2" thick layer of MASTICAL Gypsum Cement concrete underlayment is applied over these planks to provide a structural subfloor system suitable for resilient tile, wood parquet, or carpet and pad. Where improved airborne and impact sound resistance is required, a thicker layer of MASTICAL concrete is applied over USG Mineral Fiber Sound Deadening Board (see table above). A furred drywall ceiling (see USG Folder b-1497) is installed beneath the joists to complete the assembly.

USG Floor Plank for this assembly, a precast, metal-edged, structural unit 2" thick, 15" wide, 10' long, weighing 11.8 psf, has a special moisture-resistant core reinforced with 16 ga.



A.I.A. File No. 10-D/23-D

galvanized wire mat. MASTICAL, a super strength mastic cement, is mixed with asphalt emulsion, water and sand, and sets quickly and uniformly into a crack-resistant, non-shrinking surface that does not require curing. MASTICAL concrete may be walked on the next day and is ready for finish flooring when dry.

function and utility

These systems are particularly suited for high-rise or garden apartments where bar joists are used in steel frame or load-bearing masonry construction. Pipe and conduits are readily carried in the bar joist space or conduits may be placed within the MASTICAL layer above the plank. Most floor finishes, including resilient tile, wood parquet, carpet and pad, are easily accommodated. Any USG Ceiling System consisting of plaster or drywall is easily installed beneath joists.

Fire Resistance--Incombustible components provide a 2-hour fire-resistance rating (see table page 1).

Sound Control--The Sound Insulative Floor Underlayment systems offer up to 53 STC and +1 INR values. A carpet and pad improve the INR to meet most requirements.

High Strength--USG Floor Plank supports normal apartment floor loads on joist spacings up to 4' o.c. Interlocking T & G metal edges function as built-in "I" beams for superior strength and load distribution. Plank ends may occur off supports, greatly reducing material waste and labor cost. When adequately welded, the floor assembly provides effective diaphragm resistance to wind and earthquake loads. Ultimate shear values, up to 830 lbs. per ft. of diaphragm depth, may eliminate diagonal bracing within the plane of the floor.

Lightweight--USG Floor Plank topped with 1/2" MASTICAL underlayment weighs 17 psf or 43% less than 2-1/2" concrete on metal forms weighing 30 psf.

Fast Erection--Planks are laid dry - no grouting or curing required. Large T & G edges on plank fit together easily. Planks are quickly welded in place from above or below with lightweight short-arc welding equipment. Installed planks make an immediate working platform to speed building construction.


Economical--Simple, fast erection, a minimum waste for cutting (normally 2%) and opportunity for 48" bar joist spacing result in an economical assembly.

limitations

1. Maximum bar joist spacing: 4' o.c. See table page 6 for maximum allowable loads.
2. Not recommended for areas subject to sustained excessive humidity conditions.
3. Sound insulative floor underlayment not recommended for bathroom areas or as a base for partitions.
4. Minimum MASTICAL underlayment thickness: 1/2".

technical design data


The graph at right indicates the allowable uniformly distributed load that can be superimposed on USG Floor Plank supported on various joist spacings. None of the loads indicated will produce a deflection greater than $1/360$ of the span or induce flexural stresses greater than 20,000 psi in the metal edging. Load-carrying capacities are shown for simple and continuous span conditions.




details

scale: 1½" = 1'-0"


subfloor layout welded from above



overhead welding attachment (alternate method)




column details



details

scale: 1 1/2" = 1'-0"


exterior wall details



curtain wall across joists

floor plank closure detail



load bearing masonry




curtain wall parallel to joists

load bearing masonry

framing for openings




section X-X




section Y-Y

details


scale: 1½" = 1'-0"




partition runner attachment




**partition base with
sound floor underlayment**



**partition base with
sound floor underlayment**



door frame and runner attachment



ceramic tile floor

specifications--notes to architect

1. All supports should provide smooth level bearing surface, free of burrs, bridging, welds or other irregularities.
2. At least 1-1/2" continuous bearing should be provided for the floor plank at the floor perimeter and at all openings and columns. Where continuous support is not available, the longitudinal edge of cut plank may be finished with a USG Capping Channel grouted in place over the cut edge and supported 4' o.c. At column openings, the capping channel should be suitably supported or anchored to the column.
3. Where shear transfer is required between the floor diaphragm and structure, suitable structural connection should be provided for welding perimeter floor plank to structure 24" o.c. along edges and 15" o.c. at ends.
4. Door jamb anchors, partition plates and metal runner tracks should be fastened directly to the metal edges of the floor plank or to 3/4"x15"x26-ga. galv. steel strips screwed to metal plank edges. Ends of metal strips and metal runners should be secured with 3/8" USG Brand Screws Type S-12. Use 2-1/4" USG Brand Screws Type S for 2x4 wood plates. Power-driven concrete fasteners are not recommended. Partition runners may be fastened to MASTICAL underlayment with screw anchors or 1-3/4" square cut masonry nails.
5. For welding USG Floor Plank, use a short arc automatic wire feed lightweight welder, MIG type, using silicon-bronze wire shielded with argon gas. For cutting, use a power saw with a carborundum blade.
6. The minimum thickness of MASTICAL underlayment over electrical conduit or cables should be 1/2".
7. Between the floor plank installation and the application of sound deadening board or MASTICAL underlayment, the floor plank may become damaged and if so, should be repaired. Openings at utility cut-outs should be filled by the trade making the opening.
8. MASTICAL Gypsum Cement Underlayment System should be installed only by a U.S.G. approved MASTICAL Flooring Contractor.
9. The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements. Handle and store floor plank on edge. Use temporary wood planking over the floor plank areas exposed to repetitive impact or wheel loads during construction.

In cold weather, the temperature of the building shall be maintained in the uniform range above 50°F. for an adequate period prior to the application of MASTICAL, while the underlayment is

being applied, and after the MASTICAL is dry. The heat shall be well distributed in all areas, with deflection or protective screens used to prevent concentrated or irregular heat on MASTICAL areas near source.

Ventilation shall be provided to properly dry the MASTICAL during and subsequent to its application. In glazed buildings, this shall be accomplished by keeping windows open sufficiently to provide air circulation; in enclosed areas lacking normal ventilation, provisions must be made to mechanically remove moisture-laden air.

The installation and application of all materials shall be in accordance with the latest printed directions of specifications of United States Gypsum Company.

materials

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. USG Floor Plank - 2" thick, 15" wide, 10'-0" long with 22-ga. galvanized metal edges.
- b. USG Capping Channels - 2", 22-ga., 10' long.
- c. USG Mineral Fiber Sound Deadening Board - (1/2")(1") thick, 4'0" wide, 8'0" long.
- d. MASTICAL Gypsum Cement Underlayment System.
- e. USG No. 15 Asphalt Felt.
- f. SUPER-TITE Asphalt Primer or equal.
- g. RED TOP Gauging or Wood Fiber Plaster (for repairs).

plank erection

All subfloor shall be constructed with USG Floor Planks and MASTICAL Cement Underlayment, unless otherwise shown on drawings. Welding pattern shall be as shown on the drawings.

Starting at one corner of each independent area, floor plank shall be laid dry with marked side up and with the groove side advancing. Plank shall be installed across supporting joists with joints tightly interlocked. End joints shall be staggered at least 24" and shall not fall within the same joist space in either of next two adjacent plank rows. Matched T & G end joints in field of plank may occur off supports.

Each plank or part thereof shall bear on two supports. At the floor perimeter, openings and columns, the plank shall have at least 1-1/2" bearing on supports. Longitudinally cut plank shall have at least 1-1/2" continuous support or USG Capping Channel grouted in place along cut edge and either suitably supported or anchored to framing. Where less than full length planks are used, cut end joints shall occur over supports.

If continuous support is not provided along longitudinal edge of perimeter plank, a full width plank or a cut plank with capping channel supported 4' o.c. shall be used. Such plank shall have both end joints over supports.

Flat welding: each plank shall be secured to each support at the advancing groove with a 3/16" fillet weld 5/8" long. The top longitudinal metal edges of adjacent plank shall be

connected by 5/8" long welds placed at ends of each plank and no more than 2' o.c. along sides.

Alternate for overhead welding: underside of plank shall be secured to supports at each metal edge joint intersection with a 3/16" fillet weld 5/8" long on one side of supports. Where end joints occur over supports each plank shall be welded to the underside of support. Between joists top longitudinal metal edges of adjacent plank shall be welded together with 5/8" long welds placed midway between joists and at end joints.

All openings through the subfloor for mechanical passage shall be neatly fitted to the framed opening. All voids, openings or damaged floor plank shall be repaired to receive MASTICAL or sound deadening board underlayment as specified.

sound insulative underlayment erection

USG mineral fiber sound deadening board shall be installed as herein specified in the areas indicated on the drawings. Before applying the floor underlayment, a 1/2"x1-5/8" strip of sound deadening board shall be applied vertically for perimeter relief at all floor intersections with walls, partitions, columns, pipes and other building elements. Over the floor plank, full sheets of sound deadening board shall be laid dry with joints neatly cut and accurately fitted. End joints shall be staggered.

MASTICAL floor underlayment application

The surface to receive MASTICAL Underlayment shall be clean, sound, smooth and true with all voids filled. Before direct MASTICAL application to plank, a uniform coating of SUPER-TITE Asphalt Primer shall be applied to the plank and allowed to dry thoroughly. Over sound deadening board a layer of No. 15 Asphalt Felt shall be applied. This felt shall be lapped 4", shown stapled in place, neatly fitted and extended vertically at least 1" above top of vertical board. MASTICAL underlayment shall be mixed according to manufacturer's directions, spread and screeded to a smooth true, level surface finishing to the required thickness. Finished underlayment shall be protected from freezing and ventilation provided to dry the underlayment quickly after set.

TRADEMARKS: The following trademarks are owned and/or registered in the U. S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (floor plank, metal products); MASTICAL (gypsum cement); SHEETROCK, FIRECODE (gypsum wallboard); RED TOP (plaster); SUPER-TITE (asphalt primer).

b-1607

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606



UNITED
STATES
GYPSUM

seismic data—see page 11

roof decks

C

Gypsum Concrete Roof Systems

1647

| fire rating | description | test no. | relative cost index | comments | folder reference |
|-------------|--|----------------------|---|--|------------------|
| 2 hrs. | PYROFILL Gypsum Concrete Roof Deck poured 2½" min. thickn over ½" SHEETROCK formbd—178 BT-1214 reinf mesh slab wt 12.8 thickn 3" | NBS-406 (f) | 52 | Thickn. includes formboard—prot. of primary steel required | c-1647 |
| 2 hrs. | THERMOFILL Gypsum Concrete Roof Deck poured 2" min thickn over 1" Fissured FIRECODE formbd—Keydeck trussed tee—Keydeck reinf mesh slab wt 8 thickn 3" | UL RC-15 (f) | 60 | Thickn. includes formboard—prot. of primary steel required | c-1647 |
| 2 hrs. | PYROFILL Gypsum Concrete Roof Deck poured 1½" min thickn over ½" SHEETROCK formbd—bulb or clip tee on bar joist—susp (1) AURATONE FIRECODE or (2) AIRSON acoust clg panels slab wt 8.5 thickn 2" | UL RC-6 (f) | 100 (1) 120 (2) incl clg assembly | Thickn. includes formboard excluding ceiling—air control valves in AIRSON panels | c-1647 |
| 2 hrs. | THERMOFILL Gypsum Concrete Roof Deck poured 2" min thickn over ½" SHEETROCK formbd—bulb tee on bar joist—susp (1) AURATONE FIRECODE or (2) AIRSON acoust clg tile slab wt 8.2 thickn 2½" | UL RC-13 (f) | 105 (1) 140 (2) incl clg assembly | Thickn. includes formboard excluding ceiling—air control valves in AIRSON tile | c-1647 |
| 1 hr. | PYROFILL Gypsum Concrete Roof Deck poured 2" min thickn over ½" SHEETROCK formbd—178 BT-1214 reinf mesh slab wt 10.7 thickn 2½" | GA-NBS-400 (f) | 50 | Thickn. includes formboard—prot. of primary support steel required | c-1647 |
| incomb. | PYROFILL or THERMOFILL Gypsum Concrete poured over incomb formbd—rated incombustible by NBFU definition | SS-S-00118C fed spec | — | Thickness of fill may be 1½" or 2" min. | c-1647 |

description

In these lightweight fire-resistant systems, quick-setting gypsum concrete is poured-in-place over galvanized reinforcing mesh and formboards supported by steel sub-purlins to provide a structurally strong monolithic roof deck slab ready for immediate roofing. These high-strength systems meet normal live and dead load requirements for roof purlin spacings up to 12' and, in addition, provide high safety factors for vertical loads and seismic forces.

Gypsum concrete roof decks have proved themselves in over 50 years of application to be ideally suited for use over steel roof framing on flat or nearly flat roofs. They are readily adapted to low-pitched or geometric roof constructions where roof framing is steel, concrete or wood.

Gypsum concrete roof decks are available in 2" to 3½" thicknesses, depending on the thickness of fill and type of formboard, and in two types of gypsum concrete fill. PYROFILL* Gypsum Concrete, the original standard roof deck fill, provides universal application and fire-resistance ratings up to 2 hours (see table above). THERMOFILL* Gypsum Concrete offers the same proven features of PYROFILL and in addition, offers a combination of light weight and higher insulation value. Where light weight and cost are the most important requirements, the Economy System, using a 1½" PYROFILL slab, may be specified for 40 psf live loads or less.

Six types of formboards are available for use, singly or in combination, to meet specific design requirements. Suitable for use in concealed or exposed roof decking, these formboards provide sound control, insulation, fire protection, economy and light reflection as needed. See page 2.

U.S.G. Gypsum Roof Decks are installed (according to specifications) by expert approved contractors who offer consultation on details and special requirements, accurate shop drawings and the skills necessary for smooth coordination with other trades. Unit responsibility by a contractor and United States Gypsum is an important factor in obtaining satisfactory results with PYROFILL and THERMOFILL Roof Decks.

function and utility

Fire Protection—constructed of incombustible components, these systems have demonstrated a one and two-hour fire endurance, without a suspended ceiling. This means fire insurance rates may be reduced as much as 30%.

High Strength—The monolithic construction, structurally integrated to the roof framing, actually reinforces the building. These decks are rigid diaphragms that resist seismic forces and uplift caused by hurricane winds.

Light Weight—These systems weigh 6 to 12 psf (excluding sub-purlins); offer possibility for savings in structural framing.


Fast Installation—As much as 30,000 sq. ft. can be poured in one day by a single crew. The quick setting action of gypsum concrete permits roofing within hours after the deck is poured.

Versatility—A wide variety of formboards, sub-purlins and fills makes these systems adaptable to all types of roof design.


Economy—Available at low, competitive costs, gypsum roof decks offer possible savings through elimination of supplementary fireproofing, ease of application, lighter structural framing, earlier occupancy, low maintenance costs, and reduced fire insurance rates.

limitations

1. Gypsum roof decks are suitable for normal temperature and humidity conditions. Where abnormal conditions prevail, consult U.S.G. for recommendations.
2. Acid fumes, generally not harmful to gypsum, may affect framing materials. Consult U.S.G. for recommendations.
3. Certain recommendations concerning drying and ventilation, expansion and contraction, decorating and roofing must be adhered to for satisfactory performance of gypsum roof decks. See Specifications, page 14 for details.



bulb tee & 48-1214 mat



trussed tee & KEYDECK

products

gypsum concrete fill

PYROFILL Gypsum Concrete is mill-formulated and composed of calcined gypsum and wood chips or shavings. It is mixed with clean water, only, at the job site and poured-in-place over permanent formboards. PYROFILL complies with ASA-A59.1-1954 and A.S.T.M. C 317-55 Standards.

THERMOFILL* Gypsum Concrete is mill formulated and composed of calcined gypsum and graded perlite aggregate. It is mixed with clean water, only, at the job site and poured-in-place over permanent formboards. THERMOFILL complies with ASA 59.1-54 and A.S.T.M. C 317-55 Standards. Not available north of 40th Parallel from Oct. 1 to April 1.

formboards



SHEETROCK* Formboard



FIRECODE* Formboard—Fissured



FIRECODE* Formboard—Economy



Plastic-Faced SHEETROCK Formboard



USG Insulation Formboard



Asbestos-Cement Formboard

SHEETROCK* Formboard is a rigid type gypsum board, $\frac{1}{2}$ " thick by 32" wide (or 48" wide), and made to specified lengths to fit purlin spacings. Treated to resist mildew effectively where adequate ventilation is provided. Tested for 1- and 2-hour fire ratings when used with 2" or $2\frac{1}{2}$ " thick gypsum slab and exposed bulb tees.

Uses—Ideal for almost every roof deck need, concealed or exposed. Economical for warehouses, light manufacturing buildings, schools—in any construction where durability and low cost are desired.

Plastic-Faced SHEETROCK Formboard is a rigid type gypsum board $\frac{1}{2}$ " thick by 32" wide, treated to resist mildew, incombustible, predecorated with a white vinyl plastic surface that is washable, highly light-reflective and durable; for interior ceilings or exterior soffits. Available in standard 8' lengths (for information regarding availability of other sizes, contact your U.S.G. representative).

Uses—Durable and easy to maintain, also offers fine appearance in such exterior uses as exterior deck under-surfaces, eave overhangs, open walkways, and other areas exposed to intermittent weather, steam and moisture. Attractive white plastic finish resists dust accumulation; reduces maintenance costs.

USG Insulation Formboards are rigid type, natural color or shop-primed white wood fiber boards sized 1" thick, 32", 36" or 48" wide, cut to specified lengths to fit purlin spacings. Also available $\frac{3}{4}$ " thick, 32" wide, cut to fit purlin spacings. The natural color of Insulation Formboards will vary slightly so that field painting is required if a uniform appearance is desired. USG Insulation Formboards are treated to resist

mildew effectively where adequate ventilation is provided.

Uses—Unexcelled for concealed interior construction areas that will have suspended ceilings. Provides a wide range of insulative factors to suit your requirements.

FIRECODE* Mineral Fiber Formboard is an incombustible, highly-insulative, rigid board with inorganic fibers that will not contribute to mildew growth. Available in highly attractive **Pin-perforated** and **Fissured** textured surface with a white factory-applied finish. It provides a 2-hour fire-resistant roof/ceiling construction (see page 1 for details). Available in 1" x 32" or 24" widths x 48" length only.

Uses—Excellent for exposed ceilings in school gymnasiums, all-purpose rooms, shop areas and wherever built-in acoustical and insulative properties are desired. The result is a major saving under cost of separate ceiling treatment.

FIRECODE* Mineral Fiber Formboard—Economy has a natural matte surface and a medium tan color. Available 1" thick by 24" or 32" widths; cut to purlin lengths up to 6'8".

Uses—Incombustible, offers excellent insulation, and is ideal for concealed areas where a ceiling will be suspended below the deck.

Asbestos-Cement Formboard is rigid industrial type asbestos cement board, $\frac{1}{4}$ " thick, cut to 32" wide by 48" long. Supplemental tees are required to support exposed end joints when they are not supported by the sub-structure.

Uses—Ideal for use on outdoor eave overhangs, covered walkways and applications above heat-producing machinery.

| formboard characteristics | SHEETROCK formboard | plastic-faced SHEETROCK formboard | insulation formboard | FIRECODE mineral fiber formboard | | asbestos formboard |
|------------------------------|---|-----------------------------------|---|---|---|----------------------------------|
| | | | | fissured and pin perforated | economy | |
| thickness | 1/2" | 1/2" | 1" 3/4" | 1" | 1" | 1/4" |
| width | 32" or 48" (4) | 32" | 32" 36" 48" (4) only | 32" and 24" | 32" and 24" | 32" |
| length | up to 12' max. | 8' | up to 12' max. | 48" | up to 6' 8" max. | 48" |
| flame spread | 15-20(1) | 20-25(1) | (3) | 5-10(2) | 0-5(2) | 0 |
| noise reduction coefficient | — | — | (mill primed) .25 (plain) .35 | .40 | — | — |
| light reflection coefficient | 66% | 75% | (mill primed) 78% (plain) 40% | 65% | — | 40% |
| specification compliance | ASTM C-318-55 C-472-64 Federal Spec. SS-L-30b Type V | | ASTM 208-55 Class A Federal Spec. LLL-I-535 | Federal Spec. SS-A-118b Class A (Incombustible) | Federal Spec. SS-A-118b Class A (Incombustible) | Federal Spec. SS-b-755 Type U |

(1) Flame spread ratings determined by Underwriters' Laboratory testing.

(2) Flame spread rating determined by Southwest Research Institute.

(3) USG Insulation PYROFILL and USG Acoustical PYROFILL Decks are usually

classified as incombustible with a deficiency penalty when combustible formboard is used.

(4) 48" wide formboard may be used with light sub-purlin sections only if main supporting steel is spaced not to exceed 36" o.c.

Reinforcing mesh for PYROFILL is one of the following types:

1. **KEYDECK**—A galvanized wire mesh, woven with 16 ga. straight wires and 19 ga. diagonal wires.
2. **48-1214**—A galvanized, welded, wire mesh with 12 ga. longitudinal wires at 4" o.c. and 14 ga. transverse wires at 8" o.c.

The effective cross-sectional area of reinforcing mesh placed at 90° to the sub-purlins is .026 sq. in. per foot of mesh width. U.S.G. neither manufactures nor sells reinforcing mesh.

PYROFILL and THERMOFILL gypsum concrete with prestressed concrete roof framing

In these systems the gypsum roof deck slab is used in combination with prestressed concrete roof framing sections which may be spaced up to 16' o.c. With structural units such as the LIN-TEE, the gypsum deck is poured over the entire area to form a monolithic slab. With the DYNACORE type unit the gypsum slab is located between the prestressed concrete framing members.

In these systems, steel sub-purlins are spaced 24 3/8" or 32 3/8" o.c. and securely welded to steel bars or plates embedded in the prestressed concrete roof framing sections. Formboards are placed atop the bottom flanges of the sub-purlins.

When used with LIN-TEES, paper-backed 3.4 lb. 3/8" Riblath or galvanized wire mesh over 2" strips of 1/2" formboard is placed on top of the LIN-TEES. Reinforcing mesh is laid over the entire area in the LIN-TEE systems; only across the sub-

Steel sub-purlins vary in size, weight and shape and are selected according to required span and loading. They provide lateral bracing, anchorage against uplift, and restrict deck movement due to temperature change. Sub-purlin spacing accommodates 24", 32", or 48" formboard widths with a slight tolerance for ease of formboard placement. Sub-purlins are spaced approximately 24 3/8", 32 3/8" or 48 3/8" o.c. and are welded to the structural framing members. When 48" wide formboard is used with light sub-purlin sections, supporting steel spacing should not exceed 36" o.c. U.S.G. neither manufactures nor sells steel sub-purlins.

purlins when DYNACORE prestressed concrete members are used.

With these systems, PYROFILL or THERMOFILL Gypsum Concrete is poured and screeded to a uniform 2" thickness over the formboard.

Gypsum roof decks used in combination with prestressed precast concrete structural elements provide a number of highly desirable features:

1. Clear spans up to 100' with shallow structural depths.
2. Incombustible construction without additional fireproofing.
3. Simplicity of construction for fast erection.
4. Economical initial cost and low maintenance.

These features make this system ideal for use where long clear unsupported spans are required such as in warehouses, shopping centers and school gymnasiums.

design data

design, weight and insulation values


(btu per sq. ft., per hr., per deg. F. in temperature)
 "U" factor for complete deck including built-up roof covering
 (supporting steel not included)

| (calculated) thermal insulation values of | no insulation | | ½" insulation | | 1" insulation | | plaster ceiling (1) | | dry wt. of deck psf (2) |
|--|---------------|-----|---------------|-----|---------------|-----|---------------------|-----|-------------------------|
| | s | w | s | w | s | w | s | w | |
| 2½" SHEETROCK PYROFILL Roof Deck (2" PYROFILL Gypsum Concrete over ½" SHEETROCK or ½" Plastic-Faced SHEETROCK Formboard) | .33 | .38 | .22 | .24 | .17 | .18 | .22 | .25 | 11 |
| 2" SHEETROCK PYROFILL Roof Deck (1½" PYROFILL over ½" SHEETROCK Formboard) | .34 | .41 | .21 | .23 | .15 | .16 | .23 | .26 | 9 |
| 2½" SHEETROCK THERMOFILL Roof Deck (2" THERMOFILL over ½" SHEETROCK or ½" Plastic-Faced SHEETROCK Formboard) | .27 | .30 | .18 | .19 | .14 | .14 | .19 | .22 | 8 |
| 3" USG Insulation PYROFILL Roof Deck (2" PYROFILL over 1" USG Insulation Formboard) | .18 | .19 | .14 | .15 | .12 | .13 | .14 | .15 | 10 |
| 2½" USG Insulation PYROFILL Roof Deck (1½" PYROFILL over 1" Insulation Formboard) | .20 | .22 | .15 | .16 | .13 | .12 | .15 | .17 | 8 |
| 3" USG Insulation THERMOFILL Roof Deck (2" THERMOFILL over 1" USG Insulation Formboard) | .17 | .18 | .13 | .14 | .10 | .11 | .14 | .15 | 8 |
| 2¾" USG Insulation PYROFILL Roof Deck (2" PYROFILL over ¾" Insulation Formboard) | .21 | .23 | .15 | .16 | .12 | .13 | .16 | .18 | 10 |
| 2¼" USG Insulation PYROFILL Roof Deck (1½" PYROFILL over ¾" Insulation Formboard) | .23 | .25 | .16 | .17 | .13 | .14 | .17 | .19 | 8 |
| 2¾" USG Insulation THERMOFILL Roof Deck (2" THERMOFILL over ¾" Insulation Formboard) | .19 | .21 | .14 | .15 | .11 | .12 | .15 | .16 | 7 |
| 3" FIRECODE PYROFILL Roof Deck (2" PYROFILL over 1" FIRECODE Formboard) | .16 | .17 | .13 | .14 | .11 | .11 | .15 | .15 | 10 |
| 3" FIRECODE THERMOFILL Roof Deck (2" THERMOFILL over 1" FIRECODE Formboard) | .14 | .15 | .12 | .13 | .10 | .11 | .14 | .14 | 8 |
| 2½" Asbestos Board PYROFILL Roof Deck (2¼" PYROFILL over ¼" Asbestos Board) | .34 | .39 | .21 | .23 | .15 | .16 | .24 | .26 | 12 |
| 2½" Asbestos Board THERMOFILL Roof Deck (2¼" THERMOFILL over ¼" Asbestos Board) | .28 | .32 | .18 | .20 | .14 | .15 | .20 | .22 | 9 |


S—Summer W—Winter

(1) Suspended ¾" plaster ceiling & vented air space, no added insulation.

(2) Weight of sub-purlin or roofing is not included. PYROFILL density: 50 lb. per cu. ft., THERMOFILL density: 39 lb. per cu. ft.



trussed tee



bulb tee

technical data

KEYDECK trussed tee

| | wt. lbs./lin. ft. | wt. lbs./sq. ft. | max. eave overhang (1) |
|-------------|-------------------|------------------|------------------------|
| 5-9-18-½ | 0.78 | 0.29 | — |
| 5-9-18-2 | 0.78 | 0.29 | 2'9" |
| 4-5-18-2 | 0.90 | 0.34 | 2'10" |
| 1-5-17-2 | 1.26 | 0.47 | 3'5" |
| 1-3-17-2½ | 1.32 | 0.50 | — |
| 00-5-15-2 | 1.58 | 0.59 | 3'11" |
| 00-3-15-2½ | 1.64 | 0.62 | — |
| 000-5-14-2 | 1.78 | 0.67 | 4'1" |
| 000-3-14-2½ | 1.85 | 0.69 | — |

rolled tees

| | wt. lbs./lin. ft. | wt. lbs./sq. ft. | max. eave overhang (1) |
|------|-------------------|------------------|------------------------|
| 1120 | 1.25 | 0.46 | 2'2" |
| 112 | 1.40 | 0.51 | 2'5" |
| 158 | 1.60 | 0.54 | 2'9" |
| 168 | 2.00 | 0.74 | 3'4" |
| 178 | 2.50 | 0.91 | 3'11" |
| 200 | 3.00 | 1.10 | 4'7" |
| 218 | 3.00 | 1.10 | 4'10" |
| 228 | 3.65 | 1.34 | 5'10" |
| 258 | 4.67 | 1.72 | 6'10" |

1. Values shown are for a total load of 45 pounds per square foot. Bending moment $M = \frac{1}{2} WL^2$ spaced as indicated. Values based on manufacturer's tee with minimum section modulus.

2. Caution must be used in selecting sub-purlins for eave overhangs where heavy wood nailers, angles, gutters or soffits are supported by sub-purlins. Where these conditions are noted, the maximum eave overhang for a given sub-purlin must be checked by calculating the maximum moment developed, since loads applied beyond or at the end of the sub-purlin greatly increase the total moment. Deflection should be taken into account on overhang designs. Safe uniform load: $W = 2M$ (eave overhang) Max. Bending Moment $M = fsS$

Deflection eave overhang (assume uniform loading) $d = \frac{WL^2}{8EI}$

3. All properties shown are taken from data furnished by manufacturer.



design data

sub-purlins for PYROFILL and THERMOFILL slabs over formboards

KEYDECK trussed tee

Safe load values are for the sub-purlin acting alone and are determined by truss analogy using design stress of 48,000 psi for chord and truss wires, 27,000 psi for 17 and 18 ga. angles and 30,000 psi for 14 and 15 ga. angles, or limiting deflection of L/240. Deflections consider only live load and are based on composite sub-purlin and slab action or L/240 limitation.

| span | type | continuous span | | double span | | single span | |
|------|------------|-----------------|--------------|-------------|--------------|-------------|--------------|
| | | safe load | defl. in in. | safe load | defl. in in. | safe load | defl. in in. |
| 3'0" | 5-9-18-2 | 191 | .040 | 153 | .025 | 153 | .060 |
| 3'6" | 5-9-18-2 | 141 | .053 | 113 | .033 | 113 | .078 |
| 4'0" | 5-9-18-2 | 108 | .067 | 86 | .040 | 86 | .096 |
| | 4-5-18-2 | 118 | .073 | 94 | .044 | 94 | .105 |
| 4'6" | 5-9-18-2 | 85 | .081 | 68 | .048 | 68 | .115 |
| | 4-5-18-2 | 93 | .088 | 74 | .052 | 74 | .125 |
| 5'0" | 5-9-18-2 | 69 | .094 | 55 | .055 | 55 | .131 |
| | 4-5-18-2 | 75 | .103 | 60 | .060 | 60 | .145 |
| | 1-5-17-2 | 105 | .132 | 84 | .079 | 84 | .190 |
| 5'6" | 5-9-18-2 | 57 | .107 | 46 | .061 | 46 | .148 |
| | 4-5-18-2 | 62 | .117 | 50 | .068 | 50 | .164 |
| | 1-5-17-2 | 87 | .154 | 70 | .092 | 70 | .221 |
| 6'0" | 00-5-15-2 | 118 | .194 | 94 | .117 | 92 | .275 |
| | 5-9-18-2 | 48 | .118 | 38 | .064 | 38 | .154 |
| | 4-5-18-2 | 52 | .130 | 42 | .074 | 42 | .178 |
| 6'6" | 1-5-17-2 | 73 | .175 | 58 | .101 | 58 | .243 |
| | 00-5-15-2 | 99 | .224 | 79 | .134 | 74 | .300 |
| | 5-9-18-2 | 41 | .127 | 33 | .068 | 33 | .163 |
| 6'8" | 4-5-18-2 | 45 | .144 | 36 | .078 | 36 | .188 |
| | 1-5-17-2 | 62 | .194 | 50 | .113 | 50 | .271 |
| | 00-5-15-2 | 85 | .257 | 68 | .152 | 62 | .325 |
| 6'8" | 000-5-14-2 | 93 | .269 | 74 | .159 | 65 | .325 |
| | 5-9-18-2 | 39 | .129 | 31 | .066 | 31 | .160 |
| | 4-5-18-2 | 42 | .143 | 34 | .078 | 34 | .187 |
| 6'8" | 1-5-17-2 | 59 | .201 | 47 | .114 | 47 | .274 |
| | 00-5-15-2 | 81 | .268 | 65 | .159 | 58 | .333 |
| | 000-5-14-2 | 88 | .278 | 70 | .164 | 61 | .333 |

| span | type | continuous span | | double span | | single span | |
|-------|------------|-----------------|--------------|-------------|--------------|-------------|--------------|
| | | safe load | defl. in in. | safe load | defl. in in. | safe load | defl. in in. |
| 7'0" | 4-5-18-2 | 38 | .147 | | | | |
| | 1-5-17-2 | 53 | .210 | 42 | .116 | 42 | .279 |
| | 00-5-15-2 | 73 | .285 | 58 | .165 | 52 | .350 |
| | 000-5-14-2 | 80 | .300 | 64 | .177 | 55 | .350 |
| 7'6" | 4-5-18-2 | 33 | .150 | | | | |
| | 1-5-17-2 | 47 | .232 | 38 | .130 | 38 | .311 |
| | 00-5-15-2 | 64 | .316 | 51 | .182 | 46 | .375 |
| | 000-5-14-2 | 69 | .328 | 55 | .190 | 48 | .375 |
| 8'0" | 1-5-17-2 | 41 | .242 | 33 | .130 | 33 | .311 |
| | 00-5-15-2 | 56 | .341 | 45 | .195 | 40 | .400 |
| | 000-5-14-2 | 61 | .360 | 49 | .208 | 42 | .400 |
| 8'6" | 1-5-17-2 | 36 | .247 | | | | |
| | 00-5-15-2 | 50 | .370 | 40 | .205 | 36 | .425 |
| | 000-5-14-2 | 54 | .388 | 43 | .217 | 37 | .425 |
| 9'0" | 1-5-17-2 | 32 | .248 | | | | |
| | 00-5-15-2 | 44 | .383 | 35 | .204 | 35 | .491 |
| | 000-5-14-2 | 48 | .410 | 38 | .222 | 38 | .534 |
| 9'6" | 00-5-15-2 | 40 | .407 | 32 | .214 | 32 | .514 |
| | 000-5-14-2 | 43 | .430 | 34 | .226 | 34 | .542 |
| 10'0" | 00-5-15-2 | 36 | .417 | | | | |
| | 000-5-14-2 | 39 | .450 | 31 | .231 | 31 | .555 |
| 10'6" | 00-5-15-2 | 32 | .405 | | | | |
| | 000-5-14-2 | 35 | .451 | | | | |
| 11'0" | 000-5-14-2 | 32 | .458 | | | | |
| 11'6" | 000-5-14-2 | 30 | .479 | | | | |

rolled tees

Safe load values are for 33,000 psi design stress for the rolled tee acting alone. Maximum allowable design load shall not exceed the safe load shown. Deflection load values show the live load required for L/240 deflection and are shown only to indicate the slab stiffness. Deflection loads consider only live load deflection and are based on composite bulb tee and slab action.

| span | type | continuous span | | double span | | single span | |
|------|------|-----------------|------------|-------------|------------|-------------|------------|
| | | safe load | defl. load | safe load | defl. load | safe load | defl. load |
| 3'0" | 1120 | 123 | 381 | 98 | 486 | 98 | 201 |
| 3'6" | 1120 | 90 | 258 | 72 | 328 | 72 | 136 |
| | 112 | 104 | 277 | 83 | 355 | 83 | 147 |
| 4'0" | 1120 | 69 | 184 | 55 | 235 | 55 | 97 |
| | 112 | 79 | 198 | 63 | 253 | 63 | 105 |
| | 158 | 108 | 220 | 86 | 282 | 86 | 117 |
| 4'6" | 1120 | 54 | 136 | 43 | 175 | 43 | 72 |
| | 112 | 62 | 147 | 50 | 187 | 50 | 78 |
| | 158 | 85 | 162 | 68 | 208 | 68 | 85 |
| | 168 | 119 | 196 | 95 | 250 | 95 | 103 |
| 5'0" | 1120 | 44 | 105 | 35 | 135 | 35 | 55 |
| | 112 | 50 | 112 | 40 | 144 | 40 | 60 |
| | 158 | 69 | 124 | 55 | 159 | 55 | 66 |
| | 168 | 97 | 148 | 77 | 189 | 77 | 78 |
| 5'6" | 1120 | 36 | 82 | 29 | 106 | 29 | 43 |
| | 112 | 42 | 88 | 33 | 114 | 33 | 46 |
| | 158 | 57 | 97 | 46 | 124 | 46 | 51 |
| | 168 | 80 | 115 | 64 | 147 | 64 | 60 |
| | 178 | 113 | 144 | 90 | 184 | 90 | 76 |
| 6'0" | 112 | 35 | 72 | 28 | 91 | 0 | 0 |
| | 158 | 48 | 78 | 38 | 99 | 38 | 40 |
| | 168 | 67 | 91 | 53 | 117 | 53 | 48 |
| | 178 | 95 | 114 | 76 | 145 | 76 | 60 |
| 6'6" | 158 | 41 | 63 | 32 | 81 | 0 | 0 |
| | 168 | 57 | 73 | 45 | 94 | 45 | 39 |
| | 178 | 81 | 91 | 65 | 117 | 65 | 48 |
| | 200 | 110 | 112 | 88 | 144 | 88 | 58 |
| 7'0" | 158 | 35 | 52 | 28 | 67 | 0 | 0 |
| | 168 | 49 | 61 | 39 | 78 | 39 | 31 |
| | 178 | 70 | 75 | 56 | 96 | 56 | 39 |
| | 200 | 94 | 91 | 75 | 117 | 75 | 48 |
| 7'6" | 168 | 43 | 51 | 34 | 64 | 0 | 0 |
| | 178 | 61 | 63 | 48 | 79 | 48 | 33 |
| | 200 | 82 | 75 | 66 | 96 | 66 | 39 |

| span | type | continuous span | | double span | | single span | |
|-------|------|-----------------|------------|-------------|------------|-------------|------------|
| | | safe load | defl. load | safe load | defl. load | safe load | defl. load |
| 8'0" | 168 | 37 | 43 | 30 | 55 | 0 | 0 |
| | 178 | 53 | 52 | 42 | 67 | 42 | 27 |
| | 200 | 72 | 63 | 58 | 81 | 58 | 33 |
| | 218 | 81 | 85 | 64 | 109 | 64 | 45 |
| 8'6" | 168 | 33 | 36 | 26 | 46 | 0 | 0 |
| | 178 | 47 | 45 | 38 | 57 | 0 | 0 |
| | 200 | 64 | 54 | 51 | 69 | 51 | 28 |
| | 218 | 71 | 72 | 57 | 93 | 57 | 37 |
| 9'0" | 178 | 42 | 37 | 33 | 49 | 0 | 0 |
| | 200 | 57 | 45 | 45 | 58 | 45 | 24 |
| | 218 | 64 | 63 | 51 | 79 | 51 | 33 |
| | 228 | 90 | 75 | 72 | 96 | 72 | 39 |
| 9'6" | 178 | 38 | 33 | 30 | 42 | 0 | 0 |
| | 200 | 51 | 39 | 41 | 51 | 0 | 0 |
| | 218 | 57 | 54 | 46 | 69 | 46 | 28 |
| | 228 | 81 | 64 | 65 | 84 | 65 | 34 |
| 10'0" | 178 | 34 | 28 | 27 | 37 | 0 | 0 |
| | 200 | 46 | 34 | 37 | 43 | 0 | 0 |
| | 218 | 51 | 46 | 41 | 60 | 0 | 0 |
| | 228 | 73 | 57 | 58 | 72 | 58 | 30 |
| 10'6" | 200 | 42 | 30 | 33 | 39 | 0 | 0 |
| | 218 | 47 | 42 | 37 | 52 | 0 | 0 |
| | 228 | 66 | 49 | 53 | 63 | 53 | 25 |
| | 258 | 95 | 69 | 76 | 87 | 76 | 36 |
| 11'0" | 200 | 38 | 27 | 30 | 33 | 0 | 0 |
| | 218 | 42 | 36 | 34 | 46 | 0 | 0 |
| | 228 | 60 | 43 | 48 | 55 | 0 | 0 |
| | 258 | 87 | 60 | 69 | 76 | 69 | 31 |
| 11'6" | 218 | 39 | 33 | 31 | 42 | 0 | 0 |
| | 228 | 55 | 39 | 44 | 49 | 0 | 0 |
| | 258 | 79 | 52 | 63 | 67 | 63 | 27 |
| 12'0" | 228 | 51 | 34 | 40 | 43 | 0 | 0 |
| | 258 | 73 | 46 | 58 | 60 | 58 | 24 |

1. To determine loads for 20,000 psi design stress, multiply safe load by 0.606.
2. To determine loads for 24" o.c. tee spacing, multiply safe load by 1.325.







3. To determine load for L/360, multiply defl. load by 0.67; for L/180, multiply defl. load by 1.325.
4. Safe and defl. loads are calculated by U.S.G. based on data furnished by bulb tee manufacturers.

details




application over beams and bar joists

scale: $\frac{3}{4}" = 1'-0"$

wall details





eaves



eave & gable overhang




(overhang based on $45\#/\text{sq ft}$ total load)




(1) Expansion strips are not recommended for seismic Approved Diaphragm design. See page 12 for Seismic Detail.

details


application over beams and bar joists




ridge detail




valley detail



expansion joint




skylight detail




typical framing around openings larger than 30"

openings less than 30" to be framed with sub-purlins







note: — all miscellaneous structural steel, such as channels, wood nailers, and angles, hangers & channel grillage, attached to roof framing are not by USG Roof Deck Contractor.






suspended ceilings

details

LIN-TEE system






alternate LIN-TEE system



Note: In the following areas, the lath may be omitted and the gypsum slab poured directly on the concrete Tee Sections, providing the slabs are left open to dry before roofing is applied: the entire states of Arizona and New Mexico; that part of Texas west of and including the counties of Ector, Winkler, Ward, Reeves, Jeff Davis, and Brewster; that part of California south of and including the counties of Orange and Riverside, and the city of Los Angeles.


details

DYNACORE system (not recommended for seismic design)




miscellaneous data


roof attachment to concrete joists







hanger details for suspended ceilings



hanger and hanger clips - not by USG Roof Deck Contractors (a conventional lathers wire tie may be used for suspension)

**PYROFILL nail holding power (see footnotes)**

resistance to direct pull in pounds per nail for penetration shown

| type of nail | | Screw-Tite squarehead (B) | La Belle square cut nails (D) | | gypsum deck nails (A) (C) | | wire nails |
|---------------------------|-------------|---|---|------------|---|-------------|---|
| | | | 6d common | 6d cornice | 1½" | 1¾" | 7d common |
| finish of nail tested | | plain | plain | plain | plain | plain | plain |
| head dimension | | 1½" square | .27"x.21" | .34"x.28" | dia. .975" | dia. .975" | ¼" round |
| shank at head | | .125" | .19"x.114" | .23"x.14" | .152"x.103" | .197"x.125" | 11.5 ga. |
| shank at point | | .125" | .10"x.07" | .13"x.08" | .092"x.071" | .125"x.115" | 11.5 ga. |
| lengths | | 1¾" | 2" | 2" | 1½" | 1¾" | 2¼" |
| penetration | | 1½" | 1.75" | 1.75" | 1.25" | 1.50" | 2.0" |
| holding power in PYROFILL | wet (1 day) | 46.5 | 26.5 | 34.0 | 14.5 | 28.0 | — |
| | dry | 62.0 | 226.0 | 180.0 | 116.0 | 181.0 | 28.0 |
| details | |  |  | |  | |  |

NOTES: 1. Values are from tests conducted at USG Research Laboratories and provide relative holding power for the type of nail shown. (Under conditions described in Notes 2 & 3 below: Selection of nails will depend on the roofing manufacturer's recommendations and spacing of nails.)

- Nails were driven by hand with a hammer and withdrawn immediately by means of a weighted lever arm.

3. The dry density of the PYROFILL was approximately 52 pounds per cu. ft.

4. Other nails of the same shank size and penetration should give equal holding power.

(A) Manufactured by Crescent Brass & Pin Co., Detroit.

(B) Manufactured by Independent Nail & Packing Co., Bridgewater, Mass.

(C) Manufactured by Simplex Nail & Manufacturing Corp., Americus, Ga.

(D) Manufactured by Wheeling Corrugating Co., Wheeling, W. Va.

THERMOFILL nail holding power

resistance to direct pull in pounds per nail

| age of concrete when nailed | 5d common nail pulled after | | | La Belle square cut nail, non-galvanized (Wheeling) | | | | | | 6d shingle nail pulled after | | |
|-----------------------------|-----------------------------|--------|-----|---|--------|-----|-----------------------------|--------|-----|------------------------------|--------|-----|
| | | | | 5d shingle nail pulled after | | | 6d common nail pulled after | | | | | |
| | 1 day | 7 days | dry | 1 day | 7 days | dry | 1 day | 7 days | dry | 1 day | 7 days | dry |
| 4 hours | 19 | 50 | 340 | 21 | 37 | 327 | 20 | 55 | 318 | 22 | 65 | 344 |
| 3½ days | 29 | 56 | 327 | 32 | 55 | 327 | 32 | 74 | 427 | 30 | 63 | 295 |
| 7 days | 18 | 50 | 288 | 18 | 51 | 280 | 29 | 76 | 275 | 30 | 70 | 423 |
| penetration | 1½" | | | 1½" | | | 1¾" | | | 1¾" | | |

NOTES: 1. Dry density of the THERMOFILL slab was 40 lb./cu. ft.

2. Nails were hand driven with a hammer, 4 hours, 3½ days and 7 days after the slab was poured.

3. THERMOFILL dried at a normal rate under winter room temperature and humidity, and was substantially dry at 6 weeks.

4. Nails were removed hydraulically 1 day, 7 days, and 6 weeks after nailing.

5. Values are average results of tests conducted at U.S.G. Research Laboratories.

approved seismic diaphragm

description

Gypsum Concrete Roof Decks consisting of incombustible, reinforced gypsum concrete slabs poured in place over permanent formboards have been approved as rigid diaphragms in the City of Los Angeles, County of Los Angeles and many of the 1,000 cities which use the Uniform Building Code. See Allowable Diaphragm Values in the Technical Data table, page 13. See formboard data on pages 2, 3 and 4.

Design procedure is similar to that of reinforced concrete, using the gypsum stress values allowed by the applicable code. Expensive rod or angle bracing systems can be eliminated, making PYROFILL Roof Deck very low in cost. See Diaphragm Details, page 12.

diaphragm tests

Large Scale Diaphragm Tests—S. B. Barnes, prominent West Coast Consulting Engineer, in 1954, 1956, 1957 and 1962 designed and executed four separate series of horizontal load tests on a total of 31 panels, one panel was 16' x 48'. The testing was done by Frederick J. Converse, Professor of Civil Engineering, California Institute of Technology, and by the Smith-Emery Testing Laboratory of Los Angeles.

PYROFILL Gypsum Roof Deck panels were subjected to heavy vibrating loads in the comprehensive tests.

Extracts from the Barnes Report of this test (1): "The picture gives an idea of the size and setting of 'Galloping Gertie'. The rotating wheels balance the vertical components at the center of the wheel. However, the location of the center of horizontal thrust was high above the test slab and the whole machine was eccentric in its position on the panel. This produced a severe vertical rocking. The recording instruments indicated that the vertical component was about equal to and in some cases greater than the horizontal component. This was anticipated and was felt to be proper since earthquakes usually have both horizontal and vertical components.

"When static test loading was continued after vibration the ultimate strength of panels was affected very little."

Engineer Barnes states "This machine, in my opinion, produced vibrations more severe and over a longer period of time than would be anticipated in most earthquakes."

The highly favorable performance of PYROFILL, Roof Deck as a rigid diaphragm in each series of tests resulted in a recommendation by Engineer Barnes for increases in the shear and dowel values then allowed by the Building codes.

(1) Copy available upon request.

classes—allowed values

Class "A" PYROFILL containing not more than 12½% wood fiber has a minimum ultimate compressive strength of 500 lbs. per sq. in.



vibrating machine

Class "B" PYROFILL containing not more than 3% wood fiber has a minimum ultimate compressive strength of 1000 lbs. per sq. in. The shear value on each Class of PYROFILL Roof Deck currently allowed under the various codes is stated in the following paragraphs.

City of Los Angeles, County of Los Angeles and Areas following the Uniform Building Code currently allow shear values shown in the table, page 13.

City of San Francisco allows the Bulb Tee shear values shown in the table below, but has not acted on the Keydeck Tee shear values.

Title 21 allows the use of poured gypsum roofs for diaphragms. Consult your local U.S.G. representative for values.

uniform building code

The Research Committee of the International Conference of Building Officials recommends that shear in poured gypsum concrete diaphragms be determined by the formula

$$Q = [.16fgt C_1 + 1,000 (k_1 d_1 + k_2 d_2)] C_2$$

Q = Allowable shear per foot on diaphragm in pounds per lineal foot which includes a one-third increase for short time loading.

f_g = Compressive strength of gypsum.

C_1 = 1.0 for Class A gypsum; 1.5 for Class B gypsum.

t = Thickness of gypsum between subpurlins in inches.

k_1 = Number of mesh wires per foot passing over subpurlins.

d_1 = Diameter of mesh wires passing over subpurlins in inches.

k_2 = Number of mesh wires per foot parallel to subpurlins.

k_2 = 8.5 for Keydeck mesh.

d_2 = Diameter of mesh wires parallel to subpurlins.

C_2 = 1.4 for Class A gypsum using trussed tee and one for Class B gypsum.


The application of this equation for commonly used thicknesses and mesh types for each class of gypsum are shown in the table, page 13.

seismic details


scale: $\frac{3}{4}" = 1'-0"$

application over beams and bar joist


sub-purlins parallel to shear resisting elements




rod dowel attachment



trussed tee dowel attachment





rod dowel at beam



trussed tee dowel at beam

sub-purlins perpendicular to shear resisting elements





seismic design data

allowable shear values for gypsum concrete roof decks

| deck type (3) | compressive strength psi | gypsum concrete thickness, in. | mesh | allowable shear values, lbs. per lin. ft. | |
|------------------------------|--------------------------------|--------------------------------------|---------------|--|-------------|
| | | | | bulb tees | keydeck tee |
| PYROFILL class A (1) | 500 | 2" | 4"x8" #12-#14 | 600 | 840 |
| | | 2" | 6"x6" #10-#10 | 700 | 980 |
| | | 2" | KEYDECK | 760 | 1060 |
| | | 2½" | 4"x8" #12-#14 | 640 | 890 |
| | | 2½" | 6"x6" #10-#10 | 740 | 1040 |
| | | 2½" | KEYDECK | 800 | 1120 |
| PYROFILL class B (1) | 1000 | 2" | 4"x8" #12-#14 | 920 | 920 |
| | | 2" | 6"x6" #10-#10 | 1020 | 1020 |
| | | 2" | KEYDECK | 1080 | 1080 |
| | | 2½" | 4"x8" #12-#14 | 1040 | 1040 |
| | | 2½" | 6"x6" #10-#10 | 1140 | 1140 |
| | | 2½" | KEYDECK | 1200 | 1200 |
| THERMOFILL class A (2) | 500 | 2" | 4"x8" #12-#14 | 510 | 710 |
| | | 2" | 6"x6" #10-#10 | 590 | 840 |
| | | 2" | KEYDECK | 650 | 910 |
| | | 2½" | 4"x8" #12-#14 | 540 | 760 |
| | | 2½" | 6"x6" #10-#10 | 630 | 890 |
| | | 2½" | KEYDECK | 680 | 960 |

NOTE: For availability of Class B PYROFILL and THERMOFILL check with your local U.S.G. representative.

(1) See Research Recommendation 1269.3 and 1312.2, International Conference of Building Officials.

(2) See Research Recommendation 1683.2, International Conference of Building Officials.

(3) California Administrator Code—Title 21 data varies slightly in shear calculations and field application. Consult your U.S.G. representative for assistance.

(4) For safe load, see tables, page 5.

allowable shear on anchor bolts and dowels in reinforced gypsum concrete-bulb tee construction

| bolt or dowel size, in. | Uniform Building Code | | City of Los Angeles | |
|-------------------------|-----------------------|-------------|---------------------|-------------|
| | embedment, in. | shear, lbs. | embedment, in. | shear, lbs. |
| ⅜ Bolt | 4 | 250 | 4 | 325 |
| ½ Bolt | 4 | 350 | 5 | 450 |
| ⅝ Bolt | 4 | 500 | 5 | 650 |
| ¼ Plain Dowel | 6 | 200 | 6 | 250 |
| ⅜ Deformed Dowel | 6 | 250 | 6 | 325 |
| ½ Deformed Dowel | 6 | 350 | 6 | 450 |

NOTE: Embedded Bolts or Dowels not required when keydeck tee construction is used as shown in detail for trussed tee dowel attachment. Also see Note 3 above.

specifications

notes to architect

1. Formboards should always be stored in a dry place. The normal moisture from a gypsum concrete slab has no effect on the performance of the formboards. Soaking of the formboard prior to the pouring of the slab can result in excessive deflection. The roof covering should be applied as soon as possible after erection to protect the construction from precipitation. Discoloration or staining of the formboard may occur if subjected to prolonged exposure to moisture. If staining will be objectionable, the formboard may be painted; see recommendations below.

2. **Drying**—Gypsum concrete roof slabs dry out from the underside (through the formboard). Adequate heat and ventilation below the slab are required to permit the escape of this moisture. In buildings without windows or with fixed windows, adequate mechanical (forced) ventilation is required to remove all construction moisture. Gypsum concrete is not recommended as a fill over concrete slabs, steel decks and other decks of low permeability.

3. **Ventilation** should be provided for any plenum or joist space between all roof deck and ceiling constructions. The venting of enclosed air spaces should be accomplished by natural or artificial means, both during and after construction of the building. Such venting accomplished by roof vents or soffit louvers to the outside does not appreciably affect plenum or interior temperatures. Consult the Heating, Ventilating & Air Conditioning Guide, latest edition, published by the American Society of Heating, Refrigerating & Air Conditioning Engineers, for data on ventilating attic spaces and location of vapor barriers.

4. **Decorating**—Gypsum roof decks provide a presentable undersurface that usually does not require further decorating. Where the formboard is to be left exposed and appearance of the formboard is critical, further decoration may be necessary.

When decoration is desired, painting should not be done until the slab is thoroughly dry. Before painting, the slab should be checked for dryness throughout its entire thickness. An electric type moisture meter can be used if contacts are driven well into interior of slab. Exposed metal, such as sub-purlin flanges, should be protected with a suitable metal primer before finish coats are applied.

For SHEETROCK, USG Insulation and USG FIRECODE Formboards, a breather type paint such as TEXOLITE* Alkyd Latex paint is recommended, applied by brushing, rolling or spraying. A fungicide must be added to the TEXOLITE Alkyd Latex— $\frac{1}{2}$ oz. of Super Ad-It per gallon of TEXOLITE Alkyd Latex for use on all formboards except asbestos cement formboards. (TEXOLITE Vinyl Exterior paint is recommended on cement asbestos formboard, and does not require additional inhibitor.) For fungicides in other paints, check manufacturer's specific recommendation.

5. **Expansion and Contraction**—PYROFILL and THERMOFILL Roof Decks, like all roof decks, are subject to expansion and contraction due to temperature changes. Bulb tees welded to steel framing limit slab movement that would exert itself at right angles to the direction of the bulb tees. The following is suggested as a guide:

- a. Provide expansion joints in the deck and the roofing wherever they are provided in the main structure.
- b. Long narrow buildings should have expansion joints through the deck and the supporting structure spaced not more than 200 ft. apart.

c. Wings of "L", "U" and "T"-shaped buildings should be separated with expansion joints.

d. A mineral fiber filler strip should be installed at all structural roof penetrations and at walls crossing the ends of sub-purlins. See details on pages 6 and 7; note seismic design recommendations.

To resolve specific problems, the coefficients of linear expansion should be considered. They are: for gypsum concrete, .0000085 in./in./F°; for steel, .0000065 in./in./F°. See Steel Construction Manual of the A.I.S.C., for method of calculating expansion of bodies by heat.

6. **Uplift**—All roof decks are subject to uplift forces and must be anchored to supports to resist this uplift. In developing adequate resistance, the total dead load of the roof deck can be considered as part of the total resistance. In laboratory tests, PYROFILL Roof Decks, using steel rails or bulb tee sub-purlins welded to the steel framing, have an average uplift resistance equivalent to more than 125 lbs. per sq. ft.

Reference: Armour Research Foundation Test M1068.

7. **Roofing**—Once PYROFILL and THERMOFILL have set they can withstand the effects of normal rainfall, snow, freezing and thawing; however, the complete built-up roofing must be installed not later than one day after the deck has been poured to protect the formboard under surface from possible damage by excessive water from rain or snow. For the application of built-up roof covering, U.S.G. recommends that a 43# coated base sheet, or equal, be nailed dry for the first ply. A gypsum deck nail with a metal roofing cap attached is recommended. See table of nail holding values, page 10.

8. **Heavy Loads**—Although the reinforced PYROFILL gypsum deck slab will carry loads in excess of 100 lbs. per sq. ft. with an adequate safety factor, the sub-purlins or bar joists govern the safe load limit. All superimposed concentrated loads, such as flagpole bases, water tanks and ventilating fans, must be directly or indirectly supported on steel framing, not on the gypsum slab.

9. **Steep Roofs**—PYROFILL and THERMOFILL roof slabs are designed to receive built-up roof coverings. On steep roofs, where slate, ceramic tile or rigid type shingle roof coverings are required, the use of USG Metal Edge Gypsum Plank is recommended (see separate USG Systems Folder).

10. **Suspended Ceilings**—Suspended ceilings under gypsum roof decks should be hung from the structural steel frame. If they are hung from the roof deck, the hangers should be attached to the sub-purlins, never to the gypsum slab alone. When hung from the sub-purlins, the sub-purlins must be capable of supporting the total weight including the ceiling load with a resultant deflection not to exceed 1/360 of their span. Attachment hangers and channel grillage are not furnished by the USG Roof Deck Contractor.

The most expedient way to obtain additional information on fire resistance ratings, sound transmission or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

scope—The contractor shall furnish all labor, material and equipment and install completely in accordance with the manufacturers' recommendations the poured gypsum roof decks, together with cants, curbs and drainage fills as shown and specified. Approved shop drawings are required before work proceeds.

general conditions

All formboards and dry fill, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements. No more formboard shall be laid than can be covered by a completed slab on the same day.

materials

a. **Steel Sub-Purlins**—Steel sub-purlins shall be an approved type capable of carrying the required dead load and live load, all to be cut to length and shop painted with one coat of an approved paint.

b. **Formboards**—Permanent formboards shall be (select as required):

1. SHEETROCK formboards (1/2"x32") (1/2"x48") wide, treated, in lengths equal to main purlin spacings. Up to 12'-0" lengths maximum.
2. Plastic-Faced SHEETROCK Formboard 1/2"x32"x8', treated.
3. USG Insulation Formboard 1"x32" or 36" or 48" (see page 3), also 3/4"x32", in lengths equal to main purlin spacings. Up to 12'-0" lengths maximum.
4. FIRECODE Mineral Fiber Formboard—Economy 1"x24" or 32" wide, in lengths equal to main purlin spacings. Up to 6'-8" lengths maximum.
5. FIRECODE Mineral Fiber Formboard—(Pin-perforated) (Fissured) 1"x32" wide x 48" long. Galvanized or painted sheet metal tees, 24" or 32", shall be placed in each formboard joint to provide end support where not supported by roof framing.
6. Asbestos Cement Formboard 1/4"x32"x48".

c. Reinforcing Mesh

Over Sub-Purlins—Reinforcement in the poured gypsum slab shall be 48-1214 galvanized, welded wire mesh or KEYDECK galvanized, woven wire mesh. The effective cross-sectional area of reinforcing mesh, at right angles to the sub-purlins, shall be not less than 0.026 sq. in. per ft. of mesh width.

Over LIN-TEE—KEYFORM woven reinforcing mesh shall be made from 1 1/2"x18 ga. galvanized mesh with 18 ga. galvanized longitudinal wires 3" o.c. and waterproof paper backing complying with Federal Spec. UU-P147b, Type 1, Class B (required only for alternate LIN-TEE system).

d. **Paper Top Riblath**—Riblath to be 3/8" 3.4 Riblath (with paper on top side) 27" wide by length equal to 2" shorter than width of concrete members (required only for LIN-TEE system).

e. **Gypsum Concrete**—Gypsum concrete shall be (PYROFILL) (THERMOFILL).

f. **Prestressed Concrete Members**—As furnished by fabricator and in accordance with the latest design recommendations of the joint ACI-ASCE committee. For alternate LIN-TEE system tees shall have slots 1/4"x1/4" across entire width of tee. Slot spacing: 1" o.c.

g. **Galvanized or painted sheet metal cross tees.**

installation—steel framing system

1. **Steel Sub-Purlins**—Place and weld each sub-purlin to main purlins at each contact point, using fillet welds 1/2" minimum length placed on alternate sides of sub-purlins where accessible. All end joints are to bear on roof supports (stagger the line of end joints). (See page 12 for welding specifications in seismic design.)

2. **Formboards**—Place formboards on sub-purlin flanges with all end or cross-joints supported, forms to fit neatly on all four edges. Cut forms to fit at walls, curbs and openings as required. Install approved sheet metal tees to support end joints of square edge formboards not supported by roof framing.

3. **Reinforcement**—Place 48-1214 reinforcing mesh with the 12 ga. wires at right angles to sub-purlins. If KEYDECK is used, place 16 ga. wires at right angles to sub-purlins. Lap mesh ends at least 6". Do not lap sides of mesh. In seismic design, lap mesh at least 6" at sides and ends. Cut mesh to fit at wall, curbs and openings, and carry mesh into all areas where gypsum concrete is poured.

4. **Gypsum Concrete**—Mix gypsum concrete with clean water only, as directed on bags. Pour over formboards to minimum depth of (1 1/2"—PYROFILL only) (2"). Minimum cover over sub-purlins shall be 1/4". Screed all surfaces to a smooth, even plane ready to receive waterproof roof covering specified in another section. Pour cants, curbs and drainage fills as shown or required. After pouring, leave roof deck free and clean for other trades.

installation—LIN-TEE system

1. **Steel Sub-Purlins**—Place with a minimum 12" overlap on slabs and attach each sub-purlin to top of LIN-TEES by welding to an embedded steel bar or plate (installed by LIN-TEE manufacturer) with a 3/4" long fillet weld on both sides of the sub-purlin at both ends. Spacing as specified 24 3/8" or 32 3/8".

2. **Riblath**—Place 3/8" 3.4 Riblath sheets, ribs down, over concrete members between sub-purlin so ends of sheets are within 1" of each edge of concrete tees. Bend #3 reinforcing rods (installed by LIN-TEE manufacturer) down over Riblath.

3. **Formboards**—Place formboards on sub-purlin flanges. Formboard must extend to end of sub-purlins and rest on top of riblath a minimum of 4". Cut forms to fit at walls, curbs and openings, as required.

4. **Reinforcement**—Place reinforcing mesh with heaviest gauge wires (12 ga. or 16 ga.) at right angles to sub-purlins over entire area. Lap ends of mesh 6". Gap sides of mesh at least 3". Gaps must not occur along ends of sub-purlins.

5. **Gypsum Concrete**—(same as in steel framing system).

installation—alternate LIN-TEE system

1. **Steel Sub-Purlins**—Place with a minimum 12" overlap on slabs and weld each sub-purlin to a metal plate or continuous metal strip inserted into the concrete member at the time of its fabrication. Use a minimum 3/4" fillet weld on both sides of sub-purlins at both ends. Spacing as specified 24 3/8" or 32 3/8". (See page 12 for welding specifications in seismic design.)

2. **Formboards**—Formboard lengths to be 2" longer than sub-purlin section. Place formboard on sub-purlin flanges with all ends or cross-joints supported. Install so board extends approximately 1" beyond both ends of sub-purlin. Place 2" strips of 1/2" formboard across LIN-TEE every 32" o.c.

3. Reinforcing Mesh

Over Sub-Purlins—Place 48-1214 reinforcing mesh with the 12 ga. wires at right angles to sub-purlins. If KEYDECK is used, place 16 ga. wires at right angles to sub-purlins. Lap mesh ends at least 6". Do not lap sides of mesh. Mesh must extend over ends at sub-purlin a minimum of 6". Cut mesh to fit all wall, curbs and openings and carry mesh into all areas where gypsum concrete is poured.

Over LIN-TEE—Place KEYFORM mesh with the 18 ga. wires parallel with length of LIN-TEE. Lap mesh over protruding ends of formboard flush with sub-purlin ends. Lap mesh a minimum of 2" at center of tee. Bend #3 reinforcing rod, (installed by LIN-TEE manufacturer) down over mesh.

4. Gypsum Concrete: (same as in steel framing system).

installation—DYNACORE system

1. Steel Sub-Purlins—Place sub-purlins between slabs by grouting each end of the sub-purlin into a dovetailed slot (furnished in prestressed member). Allow a minimum 2" bearing for the ends. Spacing as specified 24 $\frac{3}{8}$ " or 32 $\frac{3}{8}$ ".

2. Formboards—Place formboards on sub-purlin flanges with all ends or cross-joints supported, forms to fit neatly on all four edges. Cut forms to fit at walls, curbs and openings as required.

3. Reinforcement—Place reinforcing mesh with heaviest gauge wires (12 ga. or 16 ga.) at right angles to sub-purlins. End laps to be at least 6", side laps to be 4".

4. Gypsum Concrete—(same as in steel framing system).

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products, formboards, paints); PYROFILL, THERMOFILL (gypsum concrete); SHEETROCK, FIRECODE (formboards); AIRSON (air distribution system); AURATONE FIRECODE (ceiling panels or tile); TEXOLITE (paint products).

c-1647

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

roof decks

C

USG® Metal Edge Gypsum Plank

1657

description

In this assembly, incombustible, precast USG Metal Edge Gypsum Plank is quickly and easily erected over steel, concrete or wood joists to form a high strength, structural reinforced roof deck ready for the application of built-up roofing, shingle or tile. The gypsum planks are laid dry, without grout, by interlocking tongue-and-groove metal edges. The units are attached directly through the plank to wood or concrete joists or clipped to steel purlins or bar joists with galvanized anchor clips nailed to the metal edging. Curbs, cant and saddles are easily formed using PYROFILL® Gypsum Concrete.

This time-proven reliable roof deck construction provides excellent resistance to uplift forces and can be used on a variety of purlin spacings. The system will span up to 7' under normal design roof loads and may be applied on flat, pitched and curved roofs.

USG Precast Metal Edge Gypsum Plank is available in two types: new MEP-4, offering economy of section, for spans up to 4', and MEP-7 for spans up to 7' (see Design Properties, page 2, for load-carrying capacities). Each structural unit, 2" thick, 15" wide, 10' long, weighing 10.5 lbs. per sq. ft., is reinforced with galvanized steel T & G edges and a 16 ga. galvanized wire mat. The top of the plank has a nailable surface for the application of roofing (for nail holding power, see table, page 2). The under surface is readily painted or, if left exposed, provides a highly reflective white gypsum ceiling. USG Metal Edge Gypsum Plank conforms to Federal Specifications SS-S-439 and ASTM C 377-63.

function and utility


This incombustible reinforced precast plank is suited to all types of construction, for large size or small jobs, and is particularly adaptable where ready availability and economy of simplified all-weather assembly by the general contractor are desired.

High Strength—the interlocking tongue-and-groove edges provide built-in "I" Beam action for superior strength and load distribution. The plank ends may occur off supports, making a uniform spacing of roof purlins possible.

Uplift Resistance—laboratory tests show standard attachment clips will resist uplift loads of 470 lbs. per clip.

Fast Erection—the large accurately formed edges fit together easily. Each plank is quickly clip attached or anchored in place. No special skills or tools are required for erection.

Versatile—suitable for all normal roof loads on simple or continuous spans. Can be used on flat or pitched roofs or




applied to curved or warped areas where the radius of curvature exceeds 150'.

Nailable—the dense gypsum provides good nail-holding power for built-up roofing, shingles or tile.

Economical—simple erection, few components and a minimum waste for cutting (normally 2%) results in an economical precast roof assembly.

limitations

1. Gypsum plank roofs are practical for all buildings having normal humidity conditions and normal or moderately high temperature conditions. Where continuous high humidity or unusually high temperatures are expected, consult U.S.G.
2. Precautions should be taken to prevent thrust accumulations on steeply pitched roofs (see Specifications, page 2).
3. Maximum eave overhang based on 45 lb. total load is 3' 2" for MEP-7 and 1' 9" for MEP-4.



design properties | specifications


technical design data

The graphs below indicate the allowable uniformly distributed loads that can be superimposed on USG Metal Edge Plank supported on various joist spacings. No load indicated on the


graph will induce deflection greater than 1/240 of the span nor exceed a design stress of 20,000 psi in the metal edging. Load-carrying capacities are shown for simple and continuous span conditions.

allowable uniform superimposed loads

MEP - 4



MEP - 7



Maximum allowable bending stress in metal edging is 20,000 psi. Values are based on simple and 2-span continuous bending moments at $\frac{wl^2}{8}$; three or more continuous spans bending moments at $\frac{wl^2}{10}$. Deflections are limited to 1/240 of the span and based on deflection constant as follows: $0.013 \frac{wl^4}{EI}$ for simple spans, $0.0054 \frac{wl^4}{EI}$ for 2 continuous spans and $0.0069 \frac{wl^4}{EI}$ for three or more continuous spans. Contact your United States Gypsum representative for information on high concentrated loads. For bar joints spaced 7'-0" o.c., the effective clear span is only 6'-8" between the bar joint flanges and the allowable superimposed load for MEP-7 is found at 6'-8" on the above chart.

nail-holding power

| type of roofing | description of nail | holding power dry plank— $1\frac{1}{2}$ " penetration |
|-----------------|---|---|
| built up | $1\frac{3}{4}$ " LaBelle square cut | 140 lbs. |
| | $1\frac{3}{4}$ " independent screw-tite square-hed | 46 lbs. |
| | $1\frac{1}{2}$ " galv. roofing nail ($1\frac{1}{4}$ " penetration) | 25 lbs. |
| shingles & tile | bright smooth 9 ga. | 107 lbs. |
| | galvanized smooth 9 ga. | 80 lbs. |
| | copper clout nail, square cut† bronze smooth round 9 ga. | 72 lbs. 68 lbs. |

Tests conducted at U.S.G. Research Laboratories
†Mfd. by Atlas Tack Corp., Fairhaven, Mass.

specifications

notes to architect

1. A thrust angle is recommended for all pitches. However, where resistance is provided by a parapet wall or other structural masonry bearing, the thrust angle may be omitted on pitches 30° or less.

Standard clip attachment is sufficient for pitches less than 30°. For pitches greater than 30°, use standard clip attachment plus $\frac{1}{2}$ " standard bolts as detailed on page 3. Bolt spacing is determined by resultant thrust per unit of roof area.

Based on the National Building Code vertical live load design requirement of 20 lbs. per sq. ft. on the horizontal projection, $\frac{1}{2}$ " bolts spaced one per 30 sq. ft. of roof area will effectively resist the thrust from the resulting total roof load including a

thermal insulation values

| "U" Factor for complete roof slab including built-up roof covering (btu per sq. ft., per hr., per deg. F. diff. in temperature) | winter | summer |
|---|----------|---------|
| | | |
| plank without added insulation | 0.51 btu | .43 btu |
| plank with $\frac{1}{2}$ " added insulation | 0.30 btu | .27 btu |
| plank with 1" added insulation | 0.21 btu | .20 btu |

NOTE: The insulation considered is a rigid type wood fiber board (such as USG Roof Insulation) with a "k" factor of .36.

shingle weight up to 10 psf. This recommendation applies on pitches from 30° to 75°.

The perimeter of each plane of pitched roof area should be continuously supported. Ridge and eave details are shown on page 3. Support must also be provided along hip and valley members.


2. **Built-up Roof.** Apply built-up roof covering in accordance with roofing manufacturer's specifications as soon as possible after the installation of USG Metal Edge Gypsum Plank. Recommended application: nail the first sheet dry using nails providing minimum penetration of $1\frac{1}{4}$ " into slab. Penetration should not exceed $1\frac{1}{2}$ " (see Nailing Data). If roofing is mopped on, take precaution to prevent leakage of roofing pitch or asphalt through joints in the plank.

Shingles and Tile. Asphalt, asbestos, slate, and clay tile shingles may be satisfactorily attached by nailing directly to USG Metal Edge Gypsum Plank.


specifications cont. page 4

architectural details


application



parapet & end walls scale: 3/4" 1'-0"



steep pitch roofs no scale



**specifications** (continued from page 2)

At least one ply of roofing felt should be applied to the plank surface after it is in place, prior to shingle or tile application.

Select a nail which will insure as near as possible $1\frac{1}{2}$ " penetration into the plank (see Nailing Data.)

Where non-ferrous nails are specified, tapping or punching may be necessary where nails occur at the metal edging.

3. Venting of Enclosed Spaces. All enclosed spaces beneath roof decks should have outside venting. Such venting by small louvers or openings does not appreciably affect attic temperatures. Please refer to the annual ASHRAE Guide (Chapters 10 and 12) for complete information.

4. Painting. Plank must be dry before painting with sealing type oil or latex base paints. Galvanized edging must be freed from grease or oil by cleaning with mineral spirits or a similar solvent.

Edging can be painted with a zinc dust metal primer of the type meeting Federal Specification TTP-641-b, dated 1-23-53, Type II.

Seal gypsum surfaces with USG Vinyl Sealer or SHEETROCK® Sealer.

Allow metal primer and sealer to dry. Apply one or two coats of GRAND PRIZE® latex paint, oil paint, or alkyd flat paint. If it is necessary to paint before plank is dry, prime metal edging as above: Paint edging and gypsum with TEXOLITE® Standard casein paint which has been reinforced by additional fungicide such as $1\frac{1}{2}$ oz. Dovicide "G" per gallon of paste.

5. For information on poured-in-place PYROFILL Gypsum Roof Decks, please refer to Gypsum Concrete Roof Systems Folder in this series.

The most expedient way to obtain details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

general conditions

During job storage, gypsum plank shall be protected from exposure to rain or snow. Handle and store on edge. Use temporary wood planking over gypsum plank areas exposed to repetitive impact or wheel loads during construction.

materials

- a. Gypsum plank shall be 2"x15"x10'-0" (MEP-4) (MEP-7) Metal Edge Gypsum Plank, manufactured by United States Gypsum Company.
- b. Clips and nails. The manufacturer of the gypsum plank shall furnish standard galvanized clips for attachment to main purlins, (200 clips per 1000 sq. ft.). Nails (2 per clip) shall be 4d galvanized slaters of 1" smooth shank No. 11 ga. galvanized roofing nails.
- c. PYROFILL Gypsum Concrete, manufactured by United States Gypsum Company.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (gypsum plank, paint products); PYROFILL (gypsum concrete); SHEETROCK, GRAND PRIZE, TEXOLITE (paint products).

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

erection

Unless otherwise shown on plans, all roof areas shall be covered with gypsum plank, and all curbs, cants, saddles, etc., shall be as shown or specified herein.

Placing of Plank. Start laying plank at one corner of each independent area.

All plank shall be laid dry with marked side up and with the groove side advancing. Plank shall be placed on supporting steel with joists tightly interlocked.

Where no wall supports are provided along the longitudinal edge of the starting and final rows of plank, plank in these rows shall be cut so that end joints occur over roof supports. (When supports are provided along the wall, end joints may occur off the supports.)

End joints in adjacent rows shall be staggered not less than 30". Alternate rows shall be started with full units or cut pieces long enough to have bearing at not less than two supports. End of rows shall be finished similarly. The remaining rows can be started (or finished) with cut plank long enough to have not less than one support. Cut plank to fit at walls, ridges, valleys and around openings as indicated or required.

Anchorage of Plank to Supports. Each plank shall be anchored to supporting members by the following method:

- a. **Steel Purlins**—Use one galvanized clip at every point of support; where span is 3'-6", or less, use clip on alternate supports. Where possible, alternate position of clips so that each clip is facing in opposite direction to the next one. Secure each clip to plank with 2 nails.
- b. **Steel Purlins**—Weld metal edging of plank to each support using a short arc automatic wire feed lightweight welder, MIG type.
- c. **Concrete Joists**—Use power driven studs fired through the plank, 2 studs per plank at each intersection, with penetration into the joist adequate for secure attachment. If steel plates are imbedded in concrete joists, use method in "b" above.
- d. **Wood Joists**—Use two 16d nails at each intersection of plank with purlin. Drive nails so that their heads are flush with the top surface of the plank.
- e. For pitches greater than 30°, standard #91 anchor clip attachment shall be employed plus additional anchorage provided by $\frac{1}{2}$ " standard bolts spaced one per 30 sq. ft. of roof area.

Ridges and Hips. Fill joints at ridges and hips with mortar consisting of USG Gypsum Grouting Cement and sand mixed in the proportion of 1 part cement to 2 parts clean sharp sand by volume.

Cants and Drainage Fills. All curbs, cants, drainage saddles, etc., shall be installed as indicated or required using PYROFILL Gypsum Concrete mixed with clean water only in the proportion of 8 gallons of water to each 80 lb. bag of PYROFILL.

c-1657



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

column fireproofing

d

USG* Metal Lath Fireproofing

1706



UNITED STATES GYPSUM

| fire rating | description | test no. | relative cost index | folder reference |
|-------------|---|---------------------|---------------------|------------------|
| 4 hrs. | Metal Lath & Plaster Fireprfg—3.4# dm met lath fur ½" from face of col—1½" STRUCTO-LITE plaster with fill betw flange face & lath | UL Des 3-4 hr (f) | 120 | d-1706 |
| 4 hrs. | Metal Lath & Plaster Fireprfg—3.4# dm met lath—¾" cr chan spaced 24" o.c. vert—1½" 100:2-100:3 gypsum perlite plaster | UL Des 7-4 hr (f) | 109 | d-1706 |
| 4 hrs. | Metal Lath & Plaster Fireprfg—3.4# sf dm met lath wrapped around col—1¾" STRUCTO-LITE or 100:2-100:3 gypsum perlite plaster | UL Des 6-4 hr (f) | 108 | d-1706 |
| 3 hrs. | Metal Lath & Plaster Fireprfg—3.4# sf dm met lath wrapped around col—1¾" 100:2-100:3 gypsum perlite plaster | UL Des 6-3 hr (f) | 97 | d-1706 |
| 2 hrs. | Metal Lath & Plaster Fireprfg—3.4# sf met lath wrapped around col—1" 100:2-100:2 gypsum perlite plaster | UL Des 2-2 hr (f) | 85 | d-1706 |
| 1 hr. | Metal Lath & Plaster Fireprfg—3.4# dm met lath wrapped around col—¾" 100:2-100:3 gypsum sand plaster | BMS-92 table 40 (f) | 80 | d-1706 |

description

In these assemblies USG* Metal Lath, plain or self-furring, is wire-tied in place around the structural steel columns and plastered with gypsum cement plasters to provide lightweight, thin, compact fireproofing. USG Self-Furring Diamond Mesh Metal Lath utilizes a dimpled design to hold the lath away from the column and allow mechanical keying of the plaster. Plain USG Diamond Mesh Metal Lath furred from the column with ¾" cold rolled channels is an alternate method of construction which can be extended to enclose and protect adjacent ducts and other mechanical components. The fire protection afforded depends on the type of metal lath, the type and proportioning of aggregate to gypsum plaster, and the plaster thickness (see table above).


function and utility

Fire Protection—The component parts are incombustible. In addition, the gypsum calcines slowly, retarding flame and resisting heat transfer by giving up its chemically combined water of crystallization. The aggregate acts as a bulking agent for the plaster, and some types serve additionally as an insulating material against heat transfer. For example, lightweight aggregates provide more fire resistance than sand.


Economy—The thin lightweight plaster assembly reduces the dead load and saves floor area. The plaster surface provides the base for final decoration. Increased fire protection of primary structural framing members usually permits lower insurance premiums.

limitations

To resist impact damage from cartage equipment, etc., metal corner reinforcement must be provided at column corners.



1-2-3-4 hour
COLUMN FURRING



4 hr. (ALT. METHOD)



specifications

notes to architect

1. In cold weather, all glazing should be complete and the building must be heated to a minimum of 55° F. Before lathing, ventilation should be provided to carry off excess moisture.
2. The gypsum plaster thickness, proportioning, and type of aggregate for the fire resistance rating desired should be chosen and shown in the plaster specification.

| fire resistance rating | plaster thickness | proportioning | type of aggregate |
|------------------------------|----------------------|---|-----------------------------|
| 4 hrs. | 1 7/8" | STRUCTO-LITE* Plaster | mill-mixed |
| 4 hrs. | 1 3/4" | STRUCTO-LITE Plaster or 100:2-100:3 | mill-mixed or perlite |
| 4 hrs. | 1 1/2" | 100:2-100:3 | perlite |
| 3 hrs. | 1 3/8" | 100:2-100:3 | perlite |
| 2 hrs. | 1" | 100:2-100:2 | perlite |
| 1 hr. | 3/4" | 100:2-100:3 | perlite |

The most expedient way to obtain additional information on fire resistance ratings or details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architect Service Department, 101 South Wacker Dr., Chicago, Ill. 60606.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. Metal Lath shall be 3.4 lb. (Self-Furring) Diamond Mesh Metal Lath 27" x 96".
- b. USG 1-A Expanded Flange Corner Bead.
- c. USG 3/4" Cold Rolled Channel.
- d. 18 Ga. Galvanized Tie Wire.


column fireproofing erection

Self-furring Diamond Mesh Lath shall be formed to neatly fit the column and wire tied not over 6" o.c. at laps. Alternate: Install 3/4" channel spacers or furring brackets (as required for fire ratings) and studs as shown to provide required chase. Tie diamond mesh lath to channels with 18-gauge tie wire. USG 1-A Corner Bead shall be wire-tied to metal lath corners to provide plaster grounds shown.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products), STRUCTO-LITE (plaster).

NOTE: Since methods and conditions of application and use are beyond our control, the United States Gypsum Company will not be responsible for failure of its products when not used according to our directions and specifications.

d-1706




UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



UNITED
STATES
GYPSUM

column fireproofing

d

ROCKLATH* Fireproofing PLASTER BASE

1716

A.I.A. File No. 4-F/29-E

| fire rating | description | test no. | relative cost index | folder reference |
|-------------|---|----------------|---------------------|------------------|
| 4 hrs. | Gypsum Lath & Plaster Fireprfg—2 layers ½" ROCKLATH pl base—1" 20-ga hex mesh—1½" 100:2½ gypsum perlite plaster | GA-NBS-278 (f) | 125 | d-1716 |
| 3 hrs. | Gypsum Lath & Plaster Fireprfg—¾" perf ROCKLATH pl base—1¾" 100:2½ gypsum perlite plaster | GA-NBS-321 (f) | 100 | d-1716 |
| 3 hrs. | Gypsum Lath & Plaster Fireprfg—¾" perf ROCKLATH pl base—2" 100:2-100:3 gypsum sand plaster | GA-NBS-344 (f) | 106 | d-1716 |
| 2 hrs. | Gypsum Lath & Plaster Fireprfg—¾" perf ROCKLATH pl base—1¾" 100:2-100:3 gypsum sand plaster | GA-NBS-351 (f) | 100 | d-1716 |
| 1 hr. | Gypsum Lath & Plaster Fireprfg—¾" perf ROCKLATH pl base—½" 100:2½ gypsum sand plaster | GA-NBS-273 (f) | 76 | d-1716 |

description

These assemblies consist of ROCKLATH Plaster Base, wire-tied in place and plastered with gypsum cement plasters to provide lightweight, thin, compact fireproofing for structural steel columns. The fire protection afforded depends on the type and thickness of ROCKLATH, the type and proportioning of aggregate to gypsum plaster, and the plaster thickness. To obtain higher fire resistance ratings, in certain assemblies 20 gauge galvanized 1" hexagonal wire mesh is used over the ROCKLATH. See table above.


function and utility

Fire protection—The component parts are incombustible. In addition, the gypsum calcines slowly, retarding flame and resisting heat transfer by giving up its chemically combined water of crystallization. The aggregate acts as a bulking agent for the plaster, and some types serve additionally as an insulating material against heat transfer. For example, lightweight aggregates provide more fire resistance than sand.


Economy—The thin lightweight plaster assembly reduces the dead load and saves floor area. The plaster surface provides the base for final decoration. Increased fire protection of primary structural framing members usually permits lower insurance premiums.

limitations

To resist impact damage from cartage equipment, etc., metal corner reinforcement must be provided at column corners.



1, 1½, 2 & 3 hr. assembly



4 hr. assembly

specifications

notes to architect

1. *In cold weather, all glazing should be complete and the building must be heated to a minimum of 55°F. Before lathing, ventilation should be provided to carry off excess moisture.*
2. *The gypsum plaster thickness, proportioning and type of aggregate for the fire resistance rating desired should be chosen and shown in the plaster specification.*

| fire resistance rating | plaster thickness | proportioning | type of aggregate |
|------------------------------|----------------------|---------------|----------------------|
| 4 hrs. | 1½" | 100:2-100:3 | perlite |
| 3 hrs. | 1⅝" | 100:2-100:3 | perlite |
| 3 hrs. | 2" | 100:2-100:3 | sand |
| 2 hrs. | 1⅜" | 100:2-100:3 | sand |
| 1 hr. | ½" | 100:2½ | sand |

The most expedient way to obtain additional information on fire resistance ratings or details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architect Service Department, 101 S. Wacker Dr. Chicago, Ill. 60606.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. ROCKLATH Plaster Base (⅜" Perforated 16" x 48") (½" Long Length 24" x ceiling height).
- b. USG 1-A Expanded Flange Corner Bead.
- c. 18 Gauge Galvanized Tie Wire.
- d. 20 Gauge Galvanized 1" Hexagonal Wire Mesh (not available from U.S.G.).

column fireproofing erection

1, 2, 3-hour construction—Apply ⅜" x 16" x 48" Perforated ROCKLATH vertically against the column flanges and across the web spaces; cut as required; and fasten with double strands of 18 gauge galvanized tie wire, 2" from ends of the lath and no more than 15" o.c. at intermediate points. At each corner wire tie USG 1-A Expanded Flange Corner Bead to the double strands of 18 gauge wire and set to (½"—for 1-hour rating) (1"—for 2-hour rating) (1⅜" or 2"—for 3-hour rating) grounds over ROCKLATH.

4-hour construction—Apply a double thickness of ½" x 24" Long Length ROCKLATH vertically against column flanges and bridging the web spaces; cut as required; and fasten with a double strand of 18 gauge galvanized tie wire 4" from top and bottom and no more than 24" o.c. at intermediate points. Wrap 20 gauge galvanized 1" hexagonal wire mesh tightly around the column over the ROCKLATH Plaster Base. At each corner wire tie USG 1-A Expanded Flange Corner Bead to the ROCKLATH and set to 1½" (for 4-hour rating) grounds over ROCKLATH.

***TRADEMARKS:** The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ROCKLATH (plaster base).

NOTE: Since methods and conditions of application and use are beyond our control, the United States Gypsum Company will not be responsible for failure of its products when not used according to our directions and specifications.

d-1716



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



UNITED
STATES
GYPSUM

column fireproofing

d

PYROBAR* Fireproofing PARTITION TILE

1727

A.I.A. File No. 10-D/4-F/29-E

| fire rating | description | test no. | relative cost index | folder reference |
|-------------|--|--|---------------------|------------------|
| 4 hrs. | PYROBAR Gypsum Tile & Plaster Fireprfg—3" hollow— $\frac{5}{8}$ " gypsum sand plaster—sanded basecoat & lime putty fin recom | BMS-92 table 40 (f) | 172 | d-1727 |
| 4 hrs. | PYROBAR Gypsum Tile & Plaster Fireprfg—2" solid— $\frac{5}{8}$ " 100:3 gypsum sand plaster | BMS-92 table 40 (f) | 174 | d-1727 |
| 4 hrs. | PYROBAR Gypsum Tile & Plaster Fireprfg—2" solid—2" met band placed 24" from ea end—22-ga contin met angles screw att to bands— $\frac{5}{8}$ " IMPERIAL pl base screw att to angles— $\frac{1}{16}$ " IMPERIAL plaster | UL Des 31-4 hr (f) UL Des 34-4 hr (f) (based on 3" hol tile) | 172 170 | d-1727 |
| 2 hrs. | PYROBAR Gypsum Tile Fireprfg—3" hollow—unplastered | BMS-92 table 40 (f) | 112 | d-1727 |
| 2 hrs. | PYROBAR Gypsum Tile Fireprfg—2" solid—unplastered | BMS-92 table 40 (f) | 114 | d-1727 |

description

These assemblies consist of a PYROBAR Gypsum Partition Tile base left unplastered or finished one side with $\frac{5}{8}$ " gypsum sand plaster or IMPERIAL* Plaster Base and Plaster. They provide economical lightweight column fireproofing for new construction or alteration work. Precast into a 2" thick solid or a 3" thick hollow tile, 12" x 30", PYROBAR is easily laid up with gypsum mortar. Indented surfaces and kiln-drying make PYROBAR an ideal plaster base for gypsum basecoat plaster. When plastered on one side with sanded plaster, PYROBAR provides fire resistance ratings that meet most requirements (see table above).

function and utility

Column fireproofing with PYROBAR Gypsum Partition Tile as a base and gypsum plaster or high-strength veneer plaster provides lightweight, high-performance fire-protection and finished surfaces for structural framing members, that are naturally combined with PYROBAR partitions. (See USG Systems Folder on PYROBAR Partitions for additional details on the specification and use of PYROBAR; IMPERIAL Plaster Systems for high-strength veneer plaster details.)


Fire Protection—The component parts are incombustible. In addition, the gypsum calcines slowly, retarding flame and resisting heat transfer by giving up its chemically combined water of crystallization. Due to the excellent protection provided by the PYROBAR itself, lightweight aggregate plaster is not required for the fire ratings.

Economy—These thin lightweight plaster assemblies reduce the dead load and save floor area. The finished surface provides


the base for final decoration. Increased fire protection of primary structural framing members usually permits lower insurance premiums.

limitation

To resist impact damage from cartage equipment, etc., metal corner reinforcement must be provided at column corners.



2-hrs 4-hrs
BMS-92 table 40



34-4 hrs 31-4 hrs
UL Designs

specifications

notes to architect

Please refer to notes to architect, *USG Systems Folder on PYROBAR Partitions*, items 1, 4, 5, 6, 7, 8 and 9 that apply to this construction.

The most expedient way to obtain additional information on fire resistance ratings or details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. PYROBAR Gypsum Partition Tile (2" Solid) (3" Hollow).
- b. RED TOP® Partition Tile Cement.
- c. Clean, sharp sand, complying with ASTM C35 (not available from U.S.G.).
- d. USG Metal Base—2½" (18) (20) ga.
- e. USG Masonry Base Clip.
- f. USG Corner Bead (1-A) (800-A) (800-B).
- g. USG 1⅜" x ⅞" x 22 Ga. Galvanized Metal Angles.
- h. USG Screws—⅜" Type S Pan Head, 1" Type S.
- i. IMPERIAL Plaster Base, ⅝" thick, type X, lengths as required.
- j. 2" x 26 ga. galvanized steel straps (not available from U.S.G.).

masonry erection

All mortar shall be mixed in proportions of 1 part Partition Tile Cement to 3 parts sand, by weight. Mortar shall not be retempered.

PYROBAR Gypsum Tile (2" Solid) (3" Hollow) shall be laid

plumb and true around columns as shown on the plans. After rough plumbing and wiring is in, place the first course with core holes horizontal by bedding mortar to a true and straight line. Set tile to provide ½" minimum clearance from the edges and faces of all columns. Lay succeeding courses in ½" thick full mortar beds uniformly level in each course. Stagger vertical joints and interlock tile at corners. Cut all joints flush. Use no broken tile. Chinks and crevices shall be slushed full with mortar. Cut top tile obliquely and wedge in place at ceiling. Joints between tile and ceiling shall be slushed full with mortar. PYROBAR shall not be chased out for conduit or other piping. Exposed core holes shall be sealed with at least 2" of mortar.

plaster base erection

Perimeter straps of 2" x 26 ga. galvanized steel shall be installed horizontally around PYROBAR Tile no more than 24" from floor and ceiling and not to exceed 48" o.c. Strap ends shall be secured with ⅜" USG Type S pan head screws. 1⅜" x ⅞" x 22 ga. galvanized metal angles cut to ½" less than floor-to-ceiling height shall be placed over the perimeter straps at each corner. Corner angles shall be secured to each perimeter strap with ⅜" Type S pan head screws driven in each angle flange. ⅝" IMPERIAL Plaster Base, Type X shall be installed over and secured to corner angles with 1" Type S screws spaced 8" o.c.

lathing accessories

a. **Metal Base** 2½ inch, (18) (20) gauge, painted shall be notched to a neat miter in forming all angles. Masonry Base Clips, spaced 12" to 16" o.c., shall be nailed to Masonry. Base shall be securely held in place by engaging the base clips.

b. **Metal Corner Bead No. ()** shall be provided on all external plaster corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. Fasten 1-A Corner Bead securely with nails or galvanized staples, spaced not over 8" o.c., stagger in two wings. Fasten 800-A and 800-B Corner Bead with staples not over 12" o.c. on both flanges along the entire length of bead.

c. **Screws** shall be power-driven with an electric screwdriver and set so that the screwhead provides a slight depression below the surface of the IMPERIAL Plaster Base without tearing through the face paper.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); PYROBAR (gypsum partition tile); RED TOP (partition tile cement); IMPERIAL (plaster base, plaster).

d-1727

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



column fireproofing

d

SHEETROCK® Drywall Fireproofing
 GYPSUM WALLBOARD

1737

A.I.A. File No. 4-F/29-E

| fire rating | description | test no. | relative cost index | folder reference |
|-------------|---|--|---------------------|------------------|
| 4 hrs. | PYROBAR Gypsum Tile & Drywall Fireprfg—2" solid tile around col—tile banded 24" from ea end—contin met angles screw att to bands—1 layer 5/8" SHEETROCK FIRECODE wallbd screw att to angles—met beads on corners—joints fin wt 13 | UL Des 31-4 hr (f) UL Des 34-4 hr (f) (based on 3" hol tile) | 165 163 | d-1737 |
| 3 hrs. | Gypsum Drywall Fireprfg—3 layers 5/8" SHEETROCK FIRECODE wallbd around col—base & second layers att by DUR-A-BEAD & horiz double tie wires—2nd & 3rd layers lamin & screw att to beads—joints fin | UL Des 14-3 hr (f) | 69 | d-1737 |
| 2 hrs. | Gypsum Drywall Fireprfg—1/2" SHEETROCK FIRECODE "C" wallbd around col—double layer over ea flange end—double layer on flange faces separ by USG #158 met studs & screw att—met beads on corners—joints fin | UL Des 10-2 hr (f) | 37 | d-1737 |

description

These systems for column fireproofing consist of layers of SHEETROCK® FIRECODE® Gypsum Wallboard held in place by a combination of wire, steel studs, screws, and metal angles. The assemblies provide lightweight, thin, compact steel column fire protection of up to four hours depending on the construction. In the 4-hour assemblies the wallboard face layer is applied over a base of 2" solid or 3" hollow PYROBAR® Gypsum Partition Tile. To obtain the three-hour fire rating the layers of wallboard are laminated together with PERF-A-TAPE® Joint Compound (embedding type). Lower cost BAXBORD® FIRECODE Gypsum Backing Board may be used as base layers in the construction. DUR-A-BEAD® Corner Reinforcement concealed with PERF-A-TAPE Compound resists damage from impact at exterior corners.

function and utility


Fire Resistance—Constructed of incombustible components, these assemblies afford fire resistance ratings of up to four hours. Increased fire protection of primary structural framing members usually permits lower insurance premiums.

Lightweight—These thin drywall fire protection assemblies weigh only 6 to 14 lbs. per sq. ft., reduce dead load and save floor area.

Economy—Easily and quickly installed in one continuous operation without waiting for adhesives to dry. This speed of erection plus a minimum number of components and low material costs provide realistic and competitive construction costs.



limitations

The constructions should not be used where normally exposed to excessive moisture or humidity.



UL Des. 10—2 hrs

plan sections



**specifications—notes to architect**

Non-load bearing drywall column fireproofing will not resist stresses imposed by structural movement, and is subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements by control joints or other means where the column fireproofing abuts any structural element or dissimilar wall or ceiling assembly.

general conditions

In cold weather and during the period of wallboard lamination and joint finishing, temperatures within the building shall be maintained uniformly within the range of 55° to 75° F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period. All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series: Joint Treatment Folder for PERF-A-TAPE Joint System Specifications; Gypsum Wallboard Folder for information on Wallboard System Components; Paint Products Folder for Paint Specifications; Plaster Bases & Accessories Folder for information on PYROBAR Partition Tile.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. Faceboard—(1/2") (5/8") thick SHEETROCK FIRECODE "C" Wallboard, tapered edges, 48" wide, in standard lengths as required.
- b. Backing Board—5/8" thick, 24" wide BAXBORD FIRECODE 8' lengths.
- c. Laminating Adhesive—PERF-A-TAPE Joint Compound (embedding type).
- d. Joint Treatment—PERF-A-TAPE Joint System.
- e. Fasteners—USG Drywall Screws—1" Type S, 1 5/16" Type S, 3/8" Type S Pan Head.
- f. USG Corner Bead—103 DUR-A-BEAD or ECONO Metal Corner Reinforcement.
- g. 18 ga. Tie Wire.
- h. USG Metal Studs—No. 158 (1 5/8").
- i. PYROBAR Gypsum Partition Tile (2" Solid) (3" Hollow).
- j. RED TOP* Partition Tile Cement.
- k. Clean, sharp sand complying with ASTM C35 (not available from U.S.G.).
- l. USG 1 3/8" x 7/8" x 22 Ga. Galvanized Metal Angles.
- m. 2" x 26 ga. galv. steel straps (not available from U.S.G.).

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); SHEETROCK, FIRECODE (gypsum wallboard); BAXBORD (gypsum backing board); PERF-A-TAPE (joint treatment); DUR-A-BEAD, ECONO (corner reinforcement); PYROBAR (partition tile); RED TOP (partition tile cement).

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

column fireproofing erection

2-hour fire-resistance rating—Inner layer of 1/2" SHEETROCK FIRECODE "C" Wallboard shall be attached to USG No. 158 Metal Studs with 1" USG Drywall Screws Type S spaced 24" o.c. Assembly shall be placed with wallboard adjacent to column flange and another wallboard layer erected vertically around column. Base layer panels shall be attached to studs with 1" Type S drywall screws 24" o.c.; face layer panels 12" o.c. Second wallboard layer shall be applied to web face side of column and attached through base layer to web of studs with 1 5/16" Type S screws 12" o.c. and staggered from screws in first layer. ECONO Corner Bead shall be applied vertically at all corner, fastened with 1" Type S screws 12" o.c. and finished with PERF-A-TAPE Compound.

3-hour fire-resistance rating—Steel column fire protection shall be provided with three layers of 5/8" SHEETROCK FIRECODE Wallboard applied vertically with center layer and face layer laminated to preceding layer with PERF-A-TAPE Joint Compound (embedding type). DUR-A-BEAD shall be positioned at each corner of each layer and fastened on the center and face layers with 1" USG Drywall Screws, Type S spaced 12" o.c. Fasten innermost and center layers with a double strand of 18 ga. tie wire spaced no more than 1'-9" o.c. and a maximum of 6" from slab constructions. Corners of face layer shall be finished with PERF-A-TAPE Joint System.

4-hour fire-resistance rating—PYROBAR Gypsum Tile (2" Solid) (3" Hollow) shall be laid plumb and true around columns as shown on the plans. All mortar shall be mixed in proportions of 1 part Partition Tile Cement to 3 parts sand, by weight. Mortar shall not be retempered. After rough plumbing and wiring is in, place the first course with core holes horizontal by bedding mortar to a true and straight line. Set tile to provide 1/2" minimum clearance from the edges and faces of all columns. Lay succeeding courses in 1/2" thick full mortar beds uniformly level in each course. Stagger vertical joints and interlock tile at corners. Cut all joints flush. Use no broken tile. Chinks and crevices shall be slushed full with mortar. Cut top tile obliquely and wedge in place at ceiling. Joints between tile and ceiling shall be slushed full with mortar. PYROBAR shall not be chased out for conduit or other piping. Exposed core holes shall be sealed with at least 2" of mortar.

Perimeter straps of 2" x 26 ga. galvanized steel shall be installed horizontally around PYROBAR Tile no more than 24" from floor and ceiling and not to exceed 48" o.c. Strap ends shall be secured with 3/8" USG Type S pan head screws. 1 3/8" x 7/8" x 22 ga. galvanized metal angles cut to 1/2" less than floor-to-ceiling height shall be placed over the perimeter straps at each corner. Corner angles shall be secured to each perimeter strap with 3/8" Type S pan head screws driven in each angle flange. 5/8" SHEETROCK FIRECODE "C" Wallboard shall be installed over and secured to corner angles with 1" Type S screws spaced 8" o.c.

d-1737



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices



wall furring



USG® Drywall Wall Furring System

1777

| description | relative cost index | comments | folder reference |
|---|---------------------|---|------------------|
| USG Metal Furring Channels, 24" o.c., 1/2" Insulating SHEETROCK screw attached, PERF-A-TAPE Joint Treatment | 82 | Direct attachment by means of furring strips does not isolate the surface membrane from structural stresses. No limiting height | e-1777 |

description

This exterior wall furring assembly consists of SHEETROCK® Gypsum Wallboard screw attached to USG Drywall Furring Channels. This specially designed channel, roll-formed from 25 ga. electro-galvanized steel, is 2 3/4" wide x 7/8" deep and has 1/2" wing flanges for firm attachment directly to virtually any type of masonry. A specially designed self-tapping steel screw with a rust-inhibitive coating is used to attach the wallboard to the studs. To provide additional space for pipes, conduits or ducts, the metal channel may be furred out up to 3" with horizontal 3/4" cold rolled channels wire-tied to USG Adjustable Wall Furring Brackets. The assembly when completed with the PERF-A-TAPE® Joint System and DUR-A-BEAD® Corner Reinforcement may be used in new construction or in remodeling.

SHEETROCK for this assembly is available in three thicknesses and two types (see Specifications, page 3). With Insulating (foil back) SHEETROCK Wallboard the system is effective as a vapor barrier and provides significant insulating value.

thermal resistance (R) value
Insulating SHEETROCK wallboard (1)

| | |
|----------------|------|
| 3/8" thickness | 2.04 |
| 1/2" thickness | 2.15 |
| 5/8" thickness | 2.26 |

(1) Wall application, including air space of 3/4" or more.

function and utility

Versatility—The USG Drywall Wall Furring System is adaptable for use in all types of new construction and modernization. Single or double-layer construction may be installed over virtually any type of masonry—brick, tile, PYROBAR® Gypsum Tile, monolithic concrete.

Vapor Barrier—An efficient vapor barrier is obtained with Insulating (foil back) SHEETROCK Wallboard. Meets ASTM requirements for vapor permeability not exceeding 0.30 perm.

Insulation—The thermal insulating value of an air space faced with Insulating SHEETROCK properly applied, is equivalent to that of 1/2" fibrous insulation.

Economy—Utilizes low-cost materials. A minimum number of components and simplified installation procedures result in fast erection.


limitations

1. With the Adjustable Wall Furring Bracket, the limiting height is 12'.
2. Not recommended for use where furring would normally be exposed to excessive moisture or continued wetting.







OTHER U.S.G. WALL FURRING SYSTEMS

are listed and compared in Construction Selector, Section E. Full information on these additional systems may be found in the folders noted below:

| system | folder reference |
|---|------------------|
| Gypsum Lath & Plaster—Resilient Clips..... | a-1156 |
| Gypsum Lath & Plaster—Steel Channels..... | a-1036 |
| Gypsum Lath & Plaster—Wood Furring..... | a-1366 |
| Gypsum Lath & Plaster—TRUSSTEEL Studs..... | a-1187 |
| Gypsum Lath & Plaster—USG Metal Studs and Metal Channels..... | a-1197 |
| Gypsum Lath & Thin-Coat Plaster—Steel Channels..... | a-1147 |
| Metal Lath & Plaster—Steel Channels..... | a-1027 |
| Metal Lath & Plaster—TRUSSTEEL Studs..... | a-1177 |
| Gypsum Wallboard—Resilient Steel Channels.... | a-1407 |
| Gypsum Wallboard—Wood Furring..... | a-1387 |
| Gypsum Wallboard—USG Metal Studs..... | a-1207 |



components




see "gypsum wallboard & joint
treatment" product catalogs for
full description on accessories



1" USG drywall screw—type S—bugle head




1 1/8" USG drywall screw—type S—trim head



control joint

wall elevation—scale: 1/4" = 1'-0"

SHEETROCK gypsum wallboard—reg. or insulating




horizontal
application

vertical
application


details

scale: 3" = 1'-0"

furred wall plan sections




metal window-jamb



metal window-jamb


ceiling attachments



adjustable wall furring

suspended ceiling

floor attachments & bases



adjustable wall furring

attached furring top set

specifications

notes to architect

1. Drywall wall furring (non-load bearing) will not resist stresses imposed by structural movement, and is subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements except the floor by control joints or other means where:

- The wall furring abuts any structural element or dissimilar wall or ceiling assembly.
- The wall furring construction changes within the plane of the furring.

Install control joints in the furring over all expansion or control joints in the base exterior or interior wall.

In long wall furring runs, control joints should be provided no more than 30' o.c. Door frames extending from floor to ceiling or window frames are recommended as control joints. For doors less than ceiling height or windows, control joints extending from both corners of the frame to the ceiling and floor may be used.

2. Holes cut in a thin wallboard membrane such as door frames, windows, etc., cause a concentration of stresses in the wallboard. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint is not otherwise specified.

3. Ceramic Tile—The use of SHEETROCK W/R Gypsum Wallboard is recommended to provide a base for the adhesive application of ceramic, metal and plastic tile.

4. Where the furring channel is installed to exterior walls and there is a possibility of water penetration through the walls, an asphalt felt protection strip should be installed between the furring channel and the wall surface.

5. Temperature differentials in an exterior wall may cause interior condensation which when combined with airborne dust could result in photographing or shadowing over fasteners and furring. Because soiling and temperature differences are variables over which it has no control, United States Gypsum cannot be held responsible for surface blemishes that result.

The most expedient way to obtain additional information on details not covered in this publication is to direct inquiries to UNITED STATES GYPSUM sales offices.



wall furring



USG Drywall Wall Furring System

1777

general conditions

In cold weather and during the period of wallboard application and joint finishing, temperatures within the building shall be maintained uniformly with the range of 55° to 70°F. Adequate ventilation shall also be provided to eliminate excessive moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of all materials shall be in accordance with the latest printed directions or specifications of United States Gypsum Company.

materials

See USG product folders in this series:

Joint Treatment Folder for Joint System Specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company.

- a. USG Metal Furring Channel.
- b. Faceboards—($\frac{3}{8}$ " ($\frac{1}{2}$ " ($\frac{5}{8}$ " thick, 48" wide Tapered Edge SHEETROCK, (Regular) (Insulating—Foil Back) Gypsum Wallboard, lengths as required.
- c. Joint Treatment—PERF-A-TAPE or DURABOND* Joint System.
- d. Fasteners—(specify type from page 2).
- e. USG Metal Trim (specify type from page 2).
- f. USG Corner Bead—DUR-A-BEAD, PERF-A-BEAD* (specify type from page 2).
- g. USG Adjustable Wall Furring Bracket.
- h. $\frac{3}{4}$ " Cold Rolled Channels.
- i. Galvanized Tie Wire (16) (18) ga.
- j. USG Control Joint #093.

furring channel erection—direct attachment

USG Furring Channels spaced 24" o.c. maximum, shall be attached to masonry or concrete surfaces (vertically) (horizontally) with power driven anchors or concrete stub nails spaced 24" o.c. through alternate wing flanges (staggered) of the furring channel. End splices shall be provided by nesting channels no less than 8" and securely anchoring to masonry with two fasteners in each wing.

*TRADEMARKS: The following trademarks are owned and/or registered in the U. S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); SHEETROCK (gypsum wallboard); PERF-A-TAPE, DURABOND (joint treatment); DUR-A-BEAD, PERF-A-BEAD (corner reinforcement); PYROBAR (partition tile).

e-1777

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

furring channel erection—wall furring bracket

USG Adjustable Wall Furring Brackets, with serrated edges up, shall be attached to the masonry walls not over 4" from columns or other abutting construction and not over 36" o.c. horizontally; not over 6" from floor and ceiling, not over 48" vertically and as required above and below windows. Use (one 2" cut nail in mortar joints of brick or clay tile or cement block, or in the field or lightweight aggregate blocks) ($\frac{5}{8}$ " concrete stub nails or power-driven nails or other suitable fasteners in monolithic concrete) fastening through the top hole of the bracket. $\frac{3}{4}$ " cold rolled channels shall be laid horizontally on the furring brackets with the legs down, plumbed vertically from ceiling to floor and wire tied to the bracket with a double strand of 16 ga. or triple strand of 18 ga. tie wire. Bend down excess bracket length.

The USG Furring Channel shall be erected vertically and wire tied with a double strand of 16 ga. or triple strand of 18 ga. galvanized tie wire at the junction of each $\frac{3}{4}$ " channel. The USG Furring Channels shall be spaced (16" o.c. for $\frac{3}{8}$ " wallboard) (24" o.c. for $\frac{1}{2}$ " or $\frac{5}{8}$ " wallboard) maximum.

panel erection

Wallboard shall be applied with the long dimension (at right angles) (parallel) to the furring channel and fastened with 1" USG Drywall Screws Type S spaced 12" o.c. All abutting end joints when board is applied at right angles to channels and all abutting edge joints when board is applied parallel to channels shall occur over the web surface of the furring channel. Joints shall be fitted neatly and accurately with end joints staggered.

wallboard accessories

a. PERF-A-TAPE or DURABOND Joint System shall be used on all face board joints and internal angles formed by the intersection of walls and ceilings.

b. Metal Corner Bead No. () shall be securely installed at all external corners, and shall be in single lengths where the length of the corner does not exceed standard stock lengths. At least two coats of joint compound shall be applied over beads and each coat feathered out onto panel faces.

c. Metal Trim No. () shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.

d. Fasteners shall be as shown on drawings or as herein specified. Fasteners shall be driven not less than $\frac{3}{8}$ " from ends or edges of wallboard to provide uniform dimple not over $\frac{1}{32}$ " deep. Spot exposed fastener dimples on face layers with at least three coats of joint compound, feathered and sanded smooth.

e. Control Joints shall be provided in the face layer as indicated and where detailed. Staple in place. Supporting members are to be broken behind the control joints located over expansion or control joints in the base exterior or interior wall.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

wall furring

e

USG® Drywall and Rigid Foam Insulation

1786



A.I.A. File No. 20-B-2.1/23-L

| description | relative cost index | comments | folder reference |
|--|-------------------------------|--|------------------|
| Either 1½" (1) STYROFOAM FR, (2) DORVON FR 100, (3) THURANE NB, bonded to masonry wall, ½" SHEETROCK bonded to rigid foam, PERF-A-TAPE Joint Treatment | (1) 167 (2) 164 (3) 173 | Excellent insulation and moisture barrier characteristics. No pipe chase capacity. | e-1786 |

description

This exterior wall furring assembly consists of ⅜", ½" or ⅝" thick SHEETROCK® Gypsum Wallboard, adhesively bonded to STYROFOAM FR, *extruded* polystyrene; DORVON FR 100, *molded* polystyrene; or THURANE NB, urethane rigid foam insulation.

The insulation is available in thicknesses from 1" to 3". STYROFOAM and DORVON are readily attached to unit masonry and poured or precast concrete with either a modified portland cement adhesive or a special insulation mastic. For THURANE, only insulation mastic is used. Wallboard is finished with the PERF-A-TAPE® Joint System and DUR-A-BEAD® Corner Reinforcement.

In new construction or in remodeling, the system provides a highly insulative, self-furred solid backup for SHEETROCK Wallboard. Thermal insulation values (U factors) for the various assemblies are shown in the adjoining table.

This system provides a fully insulated wall at a cost competitive with many non-insulated furred walls.

function and utility

Insulation—This thin, lightweight assembly has constant, excellent thermal insulation values even under variable moisture conditions.

Moisture Barrier—The rigid foam has good moisture resistance properties. The drywall-foam furring system provides effective vapor resistance for the wall assembly.

Flame Retardant—All three types of rigid foam described above meet ASTM requirements for self-extinguishing plastics.

Economy—Low-cost materials and a minimum number of components that offer simple speedy erection combine to provide low in-place costs. This thin lightweight system offers possible structural savings. The high insulation values offer possible economies in initial and operating expenses for heating and cooling.

limitations

1. Non-load bearing.
2. Gypsum wallboard is not recommended for use where it would be exposed to excessive moisture or continued wetting.

design heat transmission coefficients (U-factors)

| wall construction | nom. thickn. | unfin. wall | furred wall† | wall insulated with | | | | | | | |
|---|--------------|-------------|--------------|------------------------|------------|------------|------------|------------|------------|------------|------------|
| | | | | STYROFOAM FR/DORVON FR | | | | THURANE NB | | | |
| | | | | 1" | 1½" | 2" | 3" | 1" | 1½" | 2" | 3" |
| 4" face brick 8" block | 12" | .42 | .26 | .15 | .12 | .09 | .07 | .11 | .08 | .06 | .04 |
| 4" face brick 4" common brick | 8" | .48 | .29 | .16 | .12 | .10 | .07 | .11 | .08 | .06 | .04 |
| SCR brick | 6" | .68 | .35 | .17 | .13 | .11 | .08 | .12 | .08 | .07 | .05 |
| concrete block sand and gravel aggregate | 8" 12" | .51 .47 | .30 .29 | .16 .15 | .12 .12 | .10 .10 | .07 .07 | .11 .11 | .08 .08 | .06 .06 | .04 .04 |
| poured concrete 140 lb./cu. ft. sand and gravel or stone aggregate | 8" 12" | .67 .55 | .35 .31 | .17 .16 | .13 .13 | .11 .10 | .08 .07 | .12 .11 | .08 .08 | .07 .06 | .05 .04 |

† Interior wall finish: ½" SHEETROCK Wallboard. All U-factors expressed in BTU/sq. ft./hr/°F.

3. Requires wood nailers to facilitate mechanical attachment of base, mouldings, casings, closure strips, etc., (see specifications for details).

specifications**notes to architect**

1. Drywall wall furring (non-load bearing) will not resist stresses imposed by structural movement, and is subject to dimensional variations due to changes in temperature and humidity. It is recommended that wallboard surfaces be isolated from all structural elements by control joints, metal trim or other means where:

- a. The wall furring abuts any structural element or dissimilar wall or ceiling assembly.
- b. The wall furring construction changes within the plane of the furring or the base wall construction changes.

Install control joints in the furring system where expansion or control joints occur in the base exterior wall.

In long wall furring runs, control joints should be spaced no more than 30' o.c. Door frames or window frames extending from floor to ceiling may be considered control joints. For frames less than ceiling height or other openings, vertical control joints extending from either the center or both corners of the frame to the ceiling and floor may be used.

2. Holes cut in a thin wallboard membrane such as door frames, windows, etc., cause a concentration of stresses in the wallboard. The use of additional reinforcement such as cross taping joints is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy or design, a control joint or other relief is not specified.

3. All wallboard joints should be completely taped and finished in the normal manner, particularly beneath window trim, door trim, base mouldings and where the furring system extends above suspended ceilings.

4. Wood nailers should be securely attached to the wall at the base, wall-ceiling juncture and around windows and other

(continued on page 3)




A.I.A. File No. 20-B-2.1/23-L


components/details



tapered edge
SHEETROCK gypsum wallboard



no. 200-A USG metal trim




1/4" GWB-54 annular ring nail




1/4" USG drywall screw—type W—bugle head




USG metal trim




see "gypsum wallboard & joint treatment" product catalogs for full description on accessories



partition
wall intersection




wall
control joint





isolated column
or masonry wall

ceiling attachment



floor attachment & base



elevation—vertical application



adhesive application

foam insulation



push-box



troweled spot

wallboard




troweled spot



notched spreader

notch designs



notch spacings



adhesive application methods

| adhesive and method | insulation applied to | | | wallboard applied to insulation |
|---|-----------------------|--------------------|-------------------------------|---------------------------------------|
| | unit masonry | formed concrete | precast concrete panels | |
| portland cement mortar (3) • push box to insulation, 1/4" thick layer | X | | | |
| portland cement mortar, mod. (1) (3) • push box to insulation, 3/16" thick layer | | X | | |
| STYROTAC Bonding Adhesive Premix (2) (3) • notched spreader to wall or insulation within 20 min. • troweled spot to insulation within 20 min.—spots: 2" to 3" diam., 1" peak ht., 8" o.c. • notched spreader to insulation or wallboard within 10 min. • troweled spot to insulation or wallboard within 20 min.—spots: 2" to 3" diam., 1/2" peak ht., 8" to 12" o.c. also strip lightly along edges | X | X | | X |
| STYROTAC Bonding Adhesive Premix (2), mod. (1) (3) • notched spreader to insulation within 10 min. • notched doctor blade in push box to wall or insulation within 10 min. • troweled spot to insulation within 10 min.—spots: 2" to 3" diam., 1" peak ht., 8" o.c. | X | X | | X |
| Insulation Mastic No. 7 • notched spreader to wall or insulation within 20 min. • troweled spot to wall or insulation within 20 min.—spots: 1 1/2" diam., 1" peak ht., 8" o.c. • mechanical or pneumatic dispenser to insulation within 20 min., 3/16" diam. heads 3" from long edge of board • notched spreader to insulation or wallboard within 10 min. • troweled spot to wallboard within 10 min.—spots: 1" diam., 1" peak ht., 8" to 12" o.c., also 2" from taped edges & 6" o.c. • mechanical or pneumatic dispenser to wallboard within 10 min. 4 longitudinal 3/16" diam. heads, 2" from edge, 11" o.c. | X | X | X | X |

(1) Modify with STYROCRETE Latex Mortar Additive. (2) STYROTAC Adhesive Concentrate, jobmixed with sand, cement and water may be used. (3) Not suitable for THURANE NB.

specifications (continued from page 1)

openings to facilitate mechanical attachment of wallboard, base, mouldings, casings, closure strips, etc.

5. Wallboard should be applied vertically in this system which does not require wood nailers beneath wallboard field joints.

6. Insulating (foil-back) SHEETROCK Wallboard is not recommended for use in this system.

7. Shallow electrical outlet boxes are recommended when rigid foam less than 1 1/2" thick is used.

8. Generally, SHEETROCK can be bonded to rigid foam insulation 24 hours after foam installation. However, when outdoor temperatures are below 50°F. during and after application of insulation, allow 48 to 72 hours for adhesive to develop bond strength before application of the SHEETROCK gypsum wallboard. Once insulation is applied to the wall, the wall and the adhesive are isolated from any source of heat from within the building. Therefore, a longer time is required for the adhesive to develop adequate bond strength.

If outdoor temperatures below 32°F. are anticipated or immediate wallboard application is desired, Dow Insulation Mastic No. 7 must be used as an adhesive to bond insulation to masonry. Supplemental mechanical attachment as described in Dow Technical Data Sheet No. 5-7 is recommended when temperatures are below 32°F.

The most expedient way to obtain additional information on details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architectural Services Dept., 101 So. Wacker Dr., Chicago, Ill. 60606.

general conditions

Rigid foam insulation shall not be applied to masonry walls with portland cement mortar or portland cement base adhesives when outdoor temperatures during the installation period may fall below 32°F. A minimum temperature of 55°F. shall be provided and maintained in the building at least 72 hours prior to, during and after, application of rigid foam insulation, gypsum wallboard and joint treatment. Adequate ventilation shall also be provided to eliminate moisture within the building during this same period.

All materials, as specified below, shall be delivered to the job in their original, unopened containers or bundles; stored in a place providing protection from damage and exposure to the elements.

The installation and application of materials shall be in accordance with the latest printed directions or specifications of the manufacturer.

materials

See USG product folders in this series:

Joint Treatment Folder for PERF-A-TAPE Joint System specifications.

Gypsum Wallboard Folder for information on Wallboard System Components.

Paint Products Folder for Paint Specifications.

See Dow Chemical Company Technical Data Sheets for information on rigid foam insulations and adhesives.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- a. Insulation—(STYROFOAM FR) (DORVON FR-100) (THURANE NB) Insulation (1") (1½") (2") (3") thick, as manufactured by the Dow Chemical Company.
- b. Adhesive—{Insulation Mastic No. 7} {STYROTAC Bonding Adhesive (Premix) (Concentrate)} {modified with STYROCRETE Latex Mortar Additive}, as manufactured by Dow Chemical Company.
- c. Faceboards—(¾") (½") (⅜") thick, 48" wide Tapered Edge SHEETROCK Gypsum Wallboard, in standard lengths as required.
- d. Joint Treatment—PERF-A-TAPE or DURABOND* Joint System.
- e. USG Metal Trim—(#200-A) (#200-B) (#400) (#401) (#402).
- f. Fasteners—(specify type from page 2).

erection of rigid foam insulation

Mortar joints on surface of unit masonry to which insulation is to be bonded shall be cut flush with masonry to provide an even surface. The wall surface shall be plumb, true to dimensions, and clean. Old or dirty masonry must be hosed; swept and wiped down to remove loose material. Form mark protrusions must be removed from poured or precast concrete; form release agents must be removed. Pockets or holes greater than 4" in diameter and ⅛" deep must be filled with mortar. *Specify as required by particular job conditions.*

Prior to installation, nailer strips shall be attached by mechanical means to the wall surface at base and wall-ceiling junctions, at termination of wallboard above suspended ceilings, around window and door openings where shown and wherever required for subsequent attachment of moldings, trim, casings, cabinets, heavy drapes or other heavy wall fixtures.

Rigid foam insulation shall be firmly bonded to the base wall using the specified adhesive applied to the (wall surface) (insulation) using a (push box) (notched spreader) (troweled

spot) (notched doctor blade in push box) (mechanical or pneumatic dispensing tool). *Specify as required from table, page 3.*

Insulation shall be installed horizontally with edges tightly butted, vertical joints staggered, and surface level. Insulation shall be placed on the wall within (20) (10) minutes after adhesive is applied.

erection of gypsum wallboard

A minimum of 24 hours after insulation has been installed, SHEETROCK wallboard shall be firmly bonded directly on the foam with adhesive herein specified. Adhesive shall be applied to (insulation) (wallboard) using (notched spreader) (troweled spot) (notched doctor blade in push box) (mechanical or pneumatic dispensing tool). Wallboard shall be placed on the insulation within (20) (10) minutes after adhesive is applied. *Specify from page 3.*

Wallboard shall be cut to floor-to-ceiling height, less at least ⅛" for floor clearance, and applied vertically with joints neatly fitted. Board shall be attached to all nailers with GWB-54 nails 8" o.c. or 1¼" USG Drywall Screws Type W 16" o.c.

After adhesive is well set (minimum of 24 hours), forming a firm bond between the SHEETROCK wallboard and the foam, SHEETROCK shall be finished in conventional manner, taking care not to severely shock the surface by impact for at least 72 hours. Wallboard joints shall be taped and treated their full length including areas above suspended ceilings and under base and trim around openings.

wallboard accessories

- a. PERF-A-TAPE or DURABOND Joint System shall be used on all face board joints and internal angles formed by the intersection of walls and ceilings.
- b. Metal Trim shall be securely installed where indicated. Finish with PERF-A-TAPE Joint Compound, as required.
- c. Fasteners shall be as shown on drawings or as herein specified. Fasteners shall be driven not less than ⅜" from ends or edges of wallboard to provide uniform dimple not over 1/32" deep. Exposed fastener dimples on face layers shall be spotted with at least three coats of joint compound, feathered and sanded smooth.
- d. Control Joints shall be provided in the wallboard face layer as indicated and shall consist of two pieces of Metal Trim back-to-back. Supporting members are to be broken behind the control joints located over expansion or control joints in the base exterior or interior wall.

*TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company, and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); SHEETROCK (gypsum wallboard); PERF-A-TAPE, DURABOND (joint treatment).

STYROFOAM, DORVON, THURANE, STYROTAC and STYROCRETE are registered trademarks of the Dow Chemical Company.

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.

e-1786



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

exterior walls

e

Exterior Stucco and Stucco Mesh

1796


 UNITED
STATES
GYPSUM

A.I.A. File No. 21-D

description

This system consists of ORIENTAL* Exterior Stucco Finish applied over a portland cement-lime basecoat and reinforced with expanded metal lath. It is suitable for use in both commercial and residential applications, in new construction or remodeling, to provide a hard, strong fire-resistant exterior wall finish that does not deteriorate after repeated wetting and drying. It may be used in both warm and cold climates over concrete or other masonry, over sheathing in wood or steel frame construction, or in prefabricated curtain wall panels.

ORIENTAL Exterior Finish, a factory-prepared stucco, requiring the addition of water only on the job, is suitable for machine or hand application. It is available in white and 11 colors, machine mixed in the factory using mineral pigments and selected aggregate.

Reinforcing for this assembly is available in two types. USG* Expanded Metal Stucco Mesh, weighing 1.8 and 3.6 lbs. per sq. yd., is slit and expanded into diamond-shaped openings approximately $1\frac{1}{2}$ "x3" in size. It is available in sheets 48"x99", painted with a rust-inhibitive coating and applied with a stucco furring nail. The alternate material, USG Self-Furring Diamond Mesh Lath, has small diamond-shaped openings and $\frac{1}{4}$ " indentations $1\frac{1}{2}$ " o.c. to hold the body of the lath away from the sheathing. It weighs 3.4 lbs. per sq. yd. and is available in sheets 27"x96", painted. Diamond Mesh Lath is also manufactured from galvanized sheets.

function and utility

Fire-resistant—The system components are incombustible.

Weather-resistant—Withstands intense heat, freezing and thawing, rain and long periods of extreme cold.

Durable—Strong, hard surface provides an attractive exterior finish with negligible maintenance.


Versatile—Adaptable to all types of new construction and modernization. Suitable for concrete, steel, or wood framing systems for application on the job or in prefabricated curtain wall panels.

Decorative—The system offers opportunity for unique design expression. The combinations of textures, colors, exposed colored aggregates and three-dimensional shapes and patterns are unlimited.

Economical—Low cost materials, fast machine application, and long life with low maintenance costs combine to make this an economical exterior finish.

limitations

1. Not recommended for application in freezing weather or immediately before or during a rainstorm.
2. Apply only over a portland cement-lime basecoat.
3. Not designed for use as a smooth trowel finish.

 USG
expanded
metal
stucco
mesh


stucco finishes



machine spray-applied texture



dashed and troweled texture



hand-float texture

A.I.A. File No. 21-D



specifications

notes to architect

1. Portland cement stucco and plaster should never be applied to surfaces containing frost or when there is danger of the temperature dropping below freezing. The temperature of the material must be maintained above 50° F for not less than 48 hours after application.

2. Exterior stucco requires moist-curing to properly hydrate and harden. Proper hydration requires sufficient water, favorable temperature and time. The surface of newly stuccoed walls should be protected from hot dry winds or excessive ventilation, and should be kept moist with a fog spray of water until proper hydration takes place.

3. Exterior stucco surfaces will not resist shrinkage stresses or stresses imposed by structural movement, and are subject to dimensional variations due to changes in temperature and humidity. It is recommended that stucco surfaces be divided into panels with control joints.

The spacing between control joints should not exceed 10 ft. in either direction and the area between separate sections should not exceed 100 sq. ft. Control joints should also be specified where:

- A stucco wall abuts a dissimilar wall or ceiling assembly.
- The wall construction changes within the plane of the wall.
- The basic wall construction contains a control joint.

Lath should be broken behind control joints. Where there is an intersection of vertical and horizontal joints, the vertical joint should be continuous and the horizontal joint should abut to it. Splices and intersections exposed to the elements should be caulked with a silicone rubber caulking cement.

4. Holes cut in a stucco membrane for door frames, windows, etc. cause a concentration of stresses in the wall. The use of additional reinforcement is recommended at the weakened area to resist and distribute concentrated stresses where, in the judgment of the architect, for reasons of economy of design, a control joint is not otherwise specified.

5. Metal corner beads are not recommended for use on exterior corners exposed to the weather. The plasterer should form the arris by stripping.

6. High-grade, rust-resisting flashings should be properly placed and installed to prevent water from getting behind stucco or plaster. Expanded metal reinforcing should extend over the flashing.

7. Metal reinforcement should be used for a stucco base on all wood or steel frame structures of open or sheathed type, over

old masonry walls, over flashing and all surfaces that do not provide a satisfactory bond for the stucco. All surfaces to receive metal reinforcement except areas to be back plastered should be covered with a 15 lb. felt or waterproof building paper.

The most expedient way to obtain information on details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Architect Service Department, 101 S. Wacker Dr., Chicago, Ill. 60606.

materials

See USG product folders in this series:

Gypsum Plasters Folder for Plaster Specifications.

Plaster Bases & Accessories Folder for General Lathing Specifications.

Paint Products Folder for Paint Specifications.

All materials herein specified shall be manufactured by the United States Gypsum Company, unless otherwise indicated.

- Metal reinforcement shall be: USG (1.8) (3.6) lb. Stucco Mesh, 48" x 99", ptd., or USG 3.4 lb. Galvanized Self-Furring Junior Diamond Mesh Lath 27"x96".
- USG Selv-edge Cornerite (2"x2") (3"x3").
- USG Striplath.
- 18 Ga. Galvanized Tie Wire.
- Stucco Furring Nails (not available from U.S.G.).

stucco base erection


Expanded metal reinforcement shall be applied with the long dimension of the sheet across the supports. The ends of diamond mesh lath shall be lapped not less than 1". If end laps are made between supports, they shall be adequately laced or tied with 18 ga. tie wire. The sides of diamond mesh lath shall be lapped not less than 1/2". Stucco mesh shall be lapped one diamond at sides and ends. Wherever possible, ends of lath in adjacent courses shall be staggered. At all interior angles, metal lath shall be formed into the corners and carried out at least 6" onto the abutting surface, and adequately secured, or cornerite shall be applied.

Metal reinforcement shall be securely attached to all supports at intervals not exceeding 6" in the direction of supports and 16" in the opposite direction. Reinforcement shall be securely attached to steel framing with 18 ga. galvanized tie wire; to wood framing with galvanized nails having a penetration into vertical supports of at least 1" and into horizontal supports of at least 1 3/8"; to concrete with concrete stub nails or power driven anchors. The attachment of stucco mesh shall provide at least 1/4" furred space between the mesh and the backing.

TRADEMARKS: The following trademarks are owned and/or registered in the U.S. Patent Office by United States Gypsum Company and are used throughout this catalog to designate particular products manufactured by that company: USG (metal products); ORIENTAL (color finish).

NOTE: Since methods and conditions of application and use are beyond our control, the United States Gypsum Company will not be responsible for failure of its products when not used according to our directions and specifications.

e-1796



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector
for
Sales
Offices

exterior walls

e

1817

U.S.
GUNITED
STATES
GYPSUM**ARMORWEAVE* Fascia Walls**
EXPANDED METAL**description**

Countless new opportunities for creative design are available with ARMORWEAVE Expanded Metal building fascia. Whether used in new construction, in remodeling to hide an old building, or for sunshading, ARMORWEAVE provides attractive, functional and economical exterior fascia.

In this system lightweight, rigid ARMORWEAVE sheets are fastened to a job-fabricated or commercially available grid attached to the exterior wall or supporting structure.

ARMORWEAVE, a sturdy, massive mesh pattern, is available in 1½" and 4" styles to adapt to varying proportion requirements. Its wide-offset strands and bonds come in two widths; (L)—Light Strands and (H)—Heavy Strands, and give ARMORWEAVE its excellent shading and concealing power; its pleasing depth and texture, its high strength and rigidity. Yet this mesh retains a high percentage of open area for passage of air and usable light.

ARMORWEAVE, made from carbon steel or aluminum, is available from nationwide distributors' stocks in a variety of sheet sizes (see Technical Data, page 2).

function and utility

When used as sunshading, ARMORWEAVE Fascia Panels effectively block the sun's glare and heat—reduce air conditioning costs. As screening ARMORWEAVE panels are ideal for giving old buildings a fresh new look or concealing unsightly equipment to preserve a building's beauty. They also are effectively used as a combination decorative front and sign background.

Design Freedom—Unlimited opportunities for individual design creativity through the many beautiful colored finishes, patterns and textures available.

Versatile—The large variety of styles, sizes, alloys available readily adapt to job requirements.

Practical—High strength and rigidity plus large open area serve to minimize wind resistance, make ARMORWEAVE suitable for nationwide use. Lightweight, easily fabricated, requires only light structural support.

Economical—Initial cost is less than other types of decorative fascia. ARMORWEAVE Fascia Panels have no moving parts; are quickly fabricated, readily installed, and easily maintained.

sunshading

ARMORWEAVE is an efficient and practical "sunshading" material. This versatile expanded metal shuts out unwanted glare and heat by shading the openings in wall areas, yet permits passage of needed light, as well as air. Screening out heat increases comfort indoors, substantially lowers air-conditioning costs. While cutting down on the heat of the summer sun, it does not minimize the warmth of the winter sun.

ARMORWEAVE used as a vertical sunshade gives nearly 180° of horizontal out-look and still affords desirable privacy from the vision of passersby. ARMORWEAVE is all in one piece, and has no moving parts to be relied on for effectiveness.

The several styles of ARMORWEAVE available provide a choice of materials to meet various sunshading requirements. 1½" and 4" (L) ARMORWEAVE placed vertically give 100% shading at a 45° profile angle. For more critical sunshading requirements, 1½" and 4" (H) ARMORWEAVE, a heavier strand material created especially for use as a sunshade, gives 100% shading at a 36° profile angle.



For screening—ARMORWEAVE panels provide functional fascias with colorful, textured design.

For sunshading—ARMORWEAVE panels cut out direct sunlight—reduce air conditioning cost.

The table below shows shading percentages of ARMORWEAVE placed vertically for various profile angles of the sun. The slope of the bond in the ARMORWEAVE is down and toward the sun to provide maximum shading and these results.

| percent shading— ARMORWEAVE | profile angle—degrees | | | | | |
|--------------------------------|-----------------------|----|----|----|-----|---------|
| | 0 | 10 | 20 | 30 | 36 | 40 45 |
| 1½" and 4" (L) Styles | 63 | 71 | 79 | 87 | — | 96 100 |
| 1½" and 4" (H) Styles | 73 | 81 | 88 | 95 | 100 | 100 100 |

Profile Angle: The angle through which a horizontal plane must be rotated about a horizontal axis located in the plane of the ARMORWEAVE Expanded Metal in order to include the position of the sun. The profile angle, sometimes called the shadow angle, is used on sectional drawings to calculate the positions and dimensions of shading devices.

(L)—light strands (H)—heavy strands

screening

ARMORWEAVE Expanded Metal has effective hiding properties that are required in remodeling or in covering equipment on the top of a building. The wide strand is placed to most effectively block the view from the ground (see details) and is opposite to the placement for shading. Because ARMORWEAVE is an openwork of metal, complete hiding from all viewing angles cannot be achieved. But hiding properties can be greatly improved by shutting out objectionable overhead light and by painting the background structure a dark color.

framing


Unique ARMORWEAVE Expanded Metal adapts readily to framing sections and fastenings that are common in architectural use. Some typical examples, shown on page 3, are angles, bars, tees, channels and I-beams. Aluminum extrusions, such as rectangular and square tubing and various types of metal store-front trim, are also used.

finishing

A variety of finishes may be applied to ARMORWEAVE Expanded Metal to provide appropriate color and added cor-

(continued on page 2)

technical data



maximum recommended span—(unsupported clear span—L.W.D.)

| Style of ARMORWEAVE Expanded Metal | | | | | | | | | | | | | | |
|------------------------------------|--------------|-------|-------------|------|-------------------------|-------|---------------|-------|---------------|------|---------------|------|--------------|------|
| design wind pressure psf | carbon steel | | | | aluminum alloy 3003-H14 | | | | | | | | | |
| | 1½" — 18(L) | | 1½" — 18(H) | | 1½" — .051(L) | | 1½" — .051(H) | | 1½" — .081(L) | | 1½" — .081(H) | | 4" — .081(L) | |
| | (1) | (2) | (1) | (2) | (1) | (2) | (1) | (2) | (1) | (2) | (1) | (2) | (1) | (2) |
| 20 | 3'2" | 8'0" | 8'0" | 8'0" | 3'6" | 5'6" | 4'7" | 6'0" | 7'0" | 8'0" | 8'0" | 8'0" | 1'0" | 1'8" |
| 25 | 2'8" | 6'4" | 8'0" | 8'0" | 2'10" | 4'4" | 4'0" | 5'4" | 5'6" | 8'0" | 8'0" | 8'0" | — | 1'4" |
| 30 | 2'5" | 5'5" | 8'0" | 8'0" | 2'4" | 3'8" | 3'2" | 4'4" | 5'0" | 7'6" | 8'0" | 8'0" | — | 1'2" |
| 35 | 2'0" | 4'8" | 7'0" | 8'0" | 2'1" | 3'4" | 2'8" | 3'7" | 4'0" | 6'6" | 7'0" | 8'0" | — | 1'0" |
| 40 | 1'10" | 4'1" | 6'0" | 7'0" | 1'11" | 2'11" | 2'6" | 3'4" | 3'7" | 6'0" | 6'0" | 8'0" | — | — |
| 45 | 1'7" | 3'8" | 5'0" | 7'0" | 1'8" | 2'6" | 2'4" | 3'0" | 3'2" | 5'0" | 5'0" | 8'0" | — | — |
| 50 | 1'6" | 3'5" | 5'0" | 6'0" | 1'6" | 2'5" | 2'0" | 2'10" | 3'0" | 4'7" | 5'0" | 8'0" | — | — |
| 55 | 1'5" | 3'2" | 4'6" | 5'6" | 1'5" | 2'1" | 1'10" | 2'6" | 2'8" | 4'4" | 4'6" | 7'6" | — | — |
| 60 | 1'2" | 2'11" | 4'0" | 5'0" | 1'4" | 2'0" | 1'7" | 2'4" | 2'6" | 4'0" | 4'0" | 7'0" | — | — |

(1) At Yield Point (2) At Permanent Set of 1/360 of Span

ARMORWEAVE characteristics—size and weight

| material | reg. flat. | style designation | design size a x b (inches) | opening size (inches) | strand size c x d (inches) | overall thick- ness e (inches) | standard sheet size | | per cent open area | wt.-lbs. per 100 sq. ft. |
|-----------------|---------------|----------------------|-------------------------------------|-----------------------------|-------------------------------------|--|------------------------|-----------------|-----------------------------|-----------------------------------|
| | | | | | | | width (SWO) | length (LWO) | | |
| carbon steel | R | 1½" #20 (L) | 1.33x3.00 | .71 x2.26 | .036x.500 | .500 | 4' | 8' | 25 | 113 |
| | | 1½" #20 (H) | 1.50x3.00 | .65 x2.28 | .036x.675 | .600 | 4 | 8 | 10 | 135 |
| | | 1½" #18 (L) | 1.37x3.00 | .70 x2.26 | .048x.500 | .540 | See Footnote 1 | | 27 | 146 |
| | | 1½" #18 (H) | 1.50x3.00 | .54 x2.10 | .048x.675 | .550 | See Footnote 1 | | 10 | 180 |
| | | 1½" #16 (L) | 1.37x3.00 | .70 x2.30 | .060x.500 | .570 | 4 | 8 | 27 | 183 |
| | | 1½" #16 (H) | 1.50x3.00 | .48 x2.03 | .060x.675 | .550 | 4 | 8 | 10 | 226 |
| | | 4 #16 (L) | 3.44x8.00 | 1.625x6.25 | .059x1.25 | 1.187 | 4 | 8 & 10 | 30 | 182 |
| | | *4 #16 (H) | 2.75x8.00 | .55 x5.00 | .059x1.25 | 1.00 | 4 | 8 & 10 | 20 | 224 |
| aluminum | R | 1½" .051 (L) | 1.24x3.00 | .52 x2.10 | .051x.500 | .500 | See Footnote 2 | | 21 | 59 |
| | | 1½" .051 (H) | 1.47x3.00 | .40 x2.00 | .051x.675 | .470 | See Footnote 2 | | 10 | 67 |
| | | 1½" .081 (L) | 1.26x3.00 | .52 x2.10 | .081x.500 | .530 | See Footnote 1 | | 23 | 91 |
| | | 1½" .081 (H) | 1.46x3.00 | .43 x2.00 | .081x.675 | .520 | See Footnote 1 | | 10 | 106 |
| | | 4 .051 (L) | 3.0 x8.00 | .76 x6.25 | .051x1.25 | 1.020 | 4 | 8 | 10 | 61 |
| | | *4 .051 (H) | 2.82x8.00 | .51 x5.65 | .051x1.25 | .900 | 4 | 8 | 25 | 65 |
| | | 4 .081 (L) | 3.0 x8.00 | 1.25 x6.00 | .081x1.25 | 1.187 | 4 | 8 & 10 | 20 | 96 |
| | | 4 .081 (H) | 2.75x8.00 | .50 x5.30 | .081x1.25 | 1.00 | 4 | 8 & 10* | 18 | 103 |

*Produced on special order. (H)=Heavy Strand (L)=Light Strand Footnote 1: Sheet Sizes are 4' x 8', 6' x 8', and 6' x 6'3" 2: Sheet Sizes are 4' x 8', 6' x 8', 6' x 6'3", and 8' x 4'
All dimensions and weights are approximate. "a"=SWO (Short Way of the Opening); "b"=LWO (Long Way of the Opening).

finishing (continued from page 1)

rosion resistance. The meshes readily adapt to standard methods of applying painted, anodic, porcelain enamel, plastic coated and baked enamel finishes. It is recommended that aluminum meshes which are to be erected without finishing be thoroughly cleaned before erection to eliminate dirt, soot, and oils that accumulate. Tables of common finishes suitable for this application are shown at right.

aid to architects and designers

To promote a better understanding of expanded metals and assure a satisfactory result, design and sales service to aid architects is offered by U.S.G. Sales Engineers. They are equipped to assist in working out specific problems concerning design, fabrication, finishing and attachment of expanded metals. Further information is available in USG brochure IS-85, "Design Data for ARMORWEAVE Building Fascia Panels."

limitations

1. See table above for maximum spans. Panels must be rigidly attached to framing with suitable fastening about 6" o.c.
2. Certain precautions regarding cleaning, use of aluminum meshes and bending must be taken when using ARMORWEAVE Expanded Metal for fascia walls. See Specifications, page 4 for details.

finishes—Aluminum ARMORWEAVE

| alloy | type | remarks |
|----------|---------------------|--|
| 5005-H34 | Unfinished | Specify thorough surface cleaning prior to painting. |
| 5005-H34 | Painted | Resists mild abrasion. Colors generally available: natural, red, blue, green, yellow, gold, silver, copper, brass and black. |
| 5005-H34 | Exterior Anodized | Higher abrasion resistance. |
| 5005-H34 | Heavy Duty Anodized | Highest resistance to abrasion and to attack by combinations of sea air, humidity and industrially contaminated atmospheres. |
| 6061-0 | Porcelain Enameled | Better structural properties after firing. This alloy expanded on special order only. |

finishes—Carbon Steel ARMORWEAVE




| type | remarks |
|---|---|
| Painted | Steel used has scale-free surface, but is shipped lightly oiled. Specify cleaning prior to finishing. |
| Bonderized & Enameled Plastic Coated Porcelain Enameled | Produced from low-carbon open-hearth steel adaptable to this finish. |

NOTES: Finishes are listed in descending order of generally added initial cost. United States Gypsum does not apply above finishes.






details

over existing structures



sunshades and railings



specifications

notes to architect

1. The table on page 2 shows maximum recommended span for various styles of carbon steel and aluminum ARMORWEAVE. This is an unreinforced clear span L.W.D. (or span parallel to the "long way of the design," or long way of the opening). When erecting ARMORWEAVE, the material should be supported along the full width of the panel. If the panel is placed vertically with the L.W.D. axis in a horizontal position, the panel should be fully supported along the vertical edges. It is desirable from an appearance standpoint to reveal support at the top and bottom of the panel, but additional horizontal supports are not necessary to achieve the results shown in the table, and for proper support. Cantilevering or extension of the ARMORWEAVE beyond the supports is not recommended.

2. ARMORWEAVE should be attached to the supporting framework about 6" o.c. by bolting, riveting, or welding.

3. For the best appearance and uniformity on the job, care should be taken in the placement of the ARMORWEAVE panels to make sure they are all installed in a like manner. ARMORWEAVE has a different light reflectance on opposite sides of the sheet due to the inherent product characteristics. The side with the tool impression extending between the openings is more contoured than the reverse side of the sheet. For the best sunshading properties, the ARMORWEAVE strand width should be placed to most effectively block the sun's rays. For the best hiding properties the ARMORWEAVE strand width should be placed to most effectively block the view from the ground.

4. At times it is desirable to use panels of ARMORWEAVE that are larger than the maximum sheet size available, as long vertical runs may be desired for accentuation. Because of the sunshading and hiding characteristics of ARMORWEAVE, this means individual sheets must be joined in width (or span parallel to the "short way of the design") to form the panel. A method has been developed for joining by lapping individual sheets over one full design and fastening in pieces together with rivets or sheet metal screws. If desired, sheets can be matched, drilled and tagged at the plant and shipped to the customer for on-the-job assembly into panels. Due to the inherent characteristics of ARMORWEAVE, it is not economically feasible to

join two sheets in the long direction of the diamond; a guaranteed match is impractical. It is best to allow for tolerances in the design by providing a cover plate or section over the outside edges of the ARMORWEAVE panel. To insure proper seating of ARMORWEAVE in the framework for fastening purposes, it is recommended that framing of the sheet extend over at least two bonds on the sides and at least one bond on the ends. Without this support, the ARMORWEAVE may buckle or bow as the fastenings are tightened.

5. Aluminum meshes which are to be erected without finishing should be thoroughly cleaned before erection to eliminate dirt, soot and oils that accumulate.

6. If an aluminum mesh is attached to a steel frame, a gasket of rubber or other non-conductor should be used to provide insulation and prevent galvanic corrosion.

7. Bending ARMORWEAVE on a very short radius may cause fracturing and is not recommended.

8. A hot-dipped galvanizing finish is not recommended for application to ARMORWEAVE.

The most expedient way to obtain additional information or details not covered in this publication is to direct inquiries to: UNITED STATES GYPSUM, Industrial Steel Department, 101 S. Wacker Dr., Chicago, Ill. 60606.

scope

The contractor shall supply all labor, material and equipment to install the ARMORWEAVE Expanded Metal in all areas where shown on the drawings.

materials

ARMORWEAVE Expanded Metal shall be (specify by complete style designation. Example: 1½"-18 (H) Carbon Steel ARMORWEAVE Expanded Metal). (The architect should specify the finish required on the Expanded Metal, i.e., cleaned and painted, anodized, etc., with appropriate specification for such finishing.)

installation

The ARMORWEAVE shall be attached to the supporting framework with (specify type of material, size and finish of fasteners) no greater than (specify distance) on centers.

TRADEMARKS: "ARMORWEAVE" is a trademark owned by the United States Gypsum Company and is used to identify the particular expanded metal manufactured by the United States Gypsum Company.

e-1817

NOTE: Since methods and conditions of application and use are beyond the control of the United States Gypsum Company, its warranties of FITNESS and MERCHANTABILITY as well as any other warranties, express or implied, made in connection with the sale of these products, SHALL NOT BE EFFECTIVE OR ACTIONABLE UNLESS the products are applied according to United States Gypsum Company's directions and specifications.



UNITED STATES GYPSUM

THE GREATEST NAME IN BUILDING

GENERAL OFFICES: 101 South Wacker Drive, Chicago, Illinois 60606

See
USG
Construction
Selector[®]
for
Sales
Offices

Digitized by:



ASSOCIATION
FOR
PRESERVATION
TECHNOLOGY,
INTERNATIONAL
www.apti.org

BUILDING
TECHNOLOGY
HERITAGE
LIBRARY

<https://archive.org/details/buildingtechnologyheritagelibrary>

From the collection of:

United States Gypsum

